


Bb: Bibb sandy loam, 0 to 2 percent slopes, frequently flooded CoC: Cowarts loamy sand, 6 to 10 percent slopes FaA: Faceville sandy loam, 0 to 2 percent slopes FaB: Faceville sandy loam, 2 to 6 percent slopes GoA: Goldsboro sandy loam, 0 to 2 percent slopes Gr: Grantham silt loam, 0 to 2 percent slopes Ly: Lynchburg sandy loam, 0 to 2 percent slopes MaA: Marlboro sandy loam, 0 to 2 percent slopes MaB: Marlboro sandy loam, 2 to 8 percent slopes NnB: Nason silt loam, 2 to 8 percent slopes NnD: Nason silt loam, 8 to 15 percent slopes


NoA: Norfolk loamy sand, 0 to 2 percent slopes NoB: Norfolk loamy sand, 2 to 6 percent slopes NuA: Norfolk-Urban land complex, 0 to 3 percent slopes Ra: Rains sandy loam, 0 to 2 percent slopes StA: State sandy loam, 0 to 3 percent slopes, occasionally flooded Tn: Toisnot loam, 0 to 2 percent slopes To: Toisnot loam, 0 to 2 percent slopes To: Tomotley sandy loam, 0 to 2 percent slopes, rarely flooded VrA: Varina loamy sand, 0 to 2 percent slopes VrB: Varina loamy sand, 2 to 6 percent slopes W: Water




Bb: Bibb sandy loam, 0 to 2 percent slopes, frequently flooded BoA: Bonneau sand, 0 to 3 percent slopes CeB: Cecil loam, 2 to 6 percent slopes CoB: Cowarts loamy sand, 2 to 6 percent slopes CoC: Cowarts loamy sand, 6 to 10 percent slopes DoA: Dorian fine sandy loam, 0 to 2 percent slopes, rarely flooded FaA: Faceville sandy loam, 0 to 2 percent slopes FaB: Faceville sandy loam, 2 to 6 percent slopes GeB: Gilead sandy loam, 2 to 8 percent slopes GoA: Goldsboro sandy loam, 0 to 2 percent slopes Gr: Grantham silt loam, 0 to 2 percent slopes Ly: Lynchburg sandy loam, 0 to 2 percent slopes MaA: Marlboro sandy loam, 0 to 2 percent slopes MaB: Marlboro sandy loam, 2 to 8 percent slopes Na: Nahunta silt loam, 0 to 2 percent slopes













Norfolk loamy sand, 0 to 2 percent slopes



/:\Clients\D-F\DOM\SRPP_ArcGIS\2017\03\06_NC_County_Maps_ACP_Tar_Pamlico_Soil_Maps.mxd, REVISED: 3/8/2017







GOA





NoA

CoB

CoB

CoB

CoA

NoA

GoA.

GoA

500

Feet

1:12,000

GoA

GeB

1 inch = 1,000 feet

1,000

Ra

NoA

Bb

NC







∆a/ Atlantic Coast **Pipeline**

Bb

UCB

GeB

NoB

UcB

Ra

Neuse

River Basin

Ww

AaA


/:\Clients\D-F\DOM\SRPP_ArcGIS\2017\03\06_NC_County_Maps_ACP_Tar_Pamlico_Soil_Maps.mxd, REVISED: 3/8/2017

001


Proposed Route

SSURGO Soils

River Basin Boundary




ERM DRAWN BY: JPB





DRAWN BY: JPB



AaA: Altavista fine sandy loam, 0 to 2 percent slopes, occasionally flooded AsA: Augusta sandy loam, 0 to 2 percent slopes, occasionally flooded AuA: Autryville sand, 0 to 2 percent slopes Bb: Bibb sandy loam, 0 to 2 percent slopes, frequently flooded BnA: Blanton sand, 0 to 3 percent slopes BoA: Bonneau sand, 0 to 3 percent slopes CoC: Cowarts loamy sand, 6 to 10 percent slopes DoA: Dorian fine sandy loam, 0 to 2 percent slopes, rarely flooded FaA: Faceville sandy loam, 0 to 2 percent slopes FaB: Faceville sandy loam, 2 to 6 percent slopes GeB: Gilead sandy loam, 2 to 8 percent slopes GeD: Gilead sandy loam, 8 to 15 percent slopes GoA: Goldsboro sandy loam, 0 to 2 percent slopes

GeB

Gr: Grantham silt loam, 0 to 2 percent slopes Le: Leaf silt loam, 0 to 2 percent slopes Ly: Lynchburg sandy loam, 0 to 2 percent slopes NoA: Norfolk loamy sand, 0 to 2 percent slopes NoB: Norfolk loamy sand, 2 to 6 percent slopes Pn: Pantego loam, 0 to 1 percent slopes, occasionally floode Ra: Rains sandy loam, 0 to 2 percent slopes UcB: Uchee loamy coarse sand, 2 to 6 percent slopes UcC: Uchee loamy coarse sand, 6 to 12 percent slopes Ud: Udorthents, loamy W: Water

BOA

BnA

BnA


FaB

Bb

UcB

WaB: Wagram loamy sand, 0 to 6 percent slopes

B Gr GeB 107.6 107. UCB GeB AsA WaB 6.5 Gr Johnston Co. Le Le WaB Le UcB GeB **P**B Neuse River UcB Basir Le GeD NoA Gr GeB GeB UcB Gel GeE UcB GeB Gr Proposed Route 500 1,000 Atlantic SSURGO Soils Feet Coast **Pipeline River Basin Boundary** 1:12,000 1 inch = 1,000 feet /I:\Clients\D-F\DOM\SRPP_ArcGIS\2017\03\06_NC_County_Maps_ACP_Tar_Pamlico_Soil_Maps.mxd, REVISED: 3/8/2017



AsA: Augusta sandy loam, 0 to 2 percent slopes, occasionally flooded AuA: Autryville sand, 0 to 2 percent slopes Bb: Bibb sandy loam, 0 to 2 percent slopes, frequently flooded BnA: Blanton sand, 0 to 3 percent slopes BoA: Bonneau sand, 0 to 3 percent slopes CoB: Cowarts loamy sand, 2 to 6 percent slopes GeB: Gilead sandy loam, 2 to 8 percent slopes GeD: Gilead sandy loam, 8 to 15 percent slopes GoA: Goldsboro sandy loam, 0 to 2 percent slopes Gr: Grantham silt loam, 0 to 2 percent slopes Ly: Lynchburg sandy loam, 0 to 2 percent slopes

BOA

100

Ra

Ra

Na: Nahunta silt loam, 0 to 2 percent slopes NoA: Norfolk loamy sand, 0 to 2 percent slopes NoB: Norfolk loamy sand, 2 to 6 percent slopes Pn: Pantego loam, 0 to 1 percent slopes, occasionally floode Ra: Rains sandy loam, 0 to 2 percent slopes To: Tomotley sandy loam, 0 to 2 percent slopes, rarely flooded UcB: Uchee loamy coarse sand, 2 to 6 percent slopes UcC: Uchee loamy coarse sand, 6 to 12 percent slopes Ud: Udorthents, loamy W: Water WaB: Wagram loamy sand, 0 to 6 percent slopes

То

110

BOA 111.5 Neuse River Basin

GeE

Ucb


ATTA

BnA

BoA .

111.6

Johnston Co. Ly



AsA

110.5

VaB

NoA

BOA

UCB


BOA

CB

Bb


Pipeline

River Basin Boundary 1:12,000 1 inch = 1,000 feet /:\Clients\D-F\DOM\SRPP_ArcGIS\2017\03\06_NC_County_Maps_ACP_Tar_Pamlico_Soil_Maps.mxd, REVISED: 3/8/2017



DRAWN BY: JPB

Au: Autryville loamy sand, 0 to 6 percent slopes AuA: Autryville sand, 0 to 2 percent slopes BH: Bibb and Johnston soils, frequently flooded Bb: Bibb sandy loam, 0 to 2 percent slopes, frequently flooded BoA: Bonneau sand, 0 to 3 percent slopes CoB: Cowarts loamy sand, 2 to 6 percent slopes Fo: Foreston loamy sand GeB: Gilead sandy loam, 2 to 8 percent slopes GoA: Goldsboro loamy sand, 0 to 2 percent slopes GoA: Goldsboro sandy loam, 0 to 2 percent slopes Gr: Grantham silt loam, 0 to 2 percent slopes Ln: Lynchburg sandy loam Ly: Lynchburg sandy loam, 0 to 2 percent slopes MaA: Marlboro sandy loam, 0 to 2 percent slopes



/I:\Clients\D-F\DOM\SRPP_ArcGIS\2017\03\06_NC_County_Maps_ACP_Tar_Pamlico_Soil_Maps.mxd, REVISED: 3/8/2017

DRAWN BY: JPB

ATLANTIC COAST PIPELINE, LLC ATLANTIC COAST PIPELINE

and

DOMINION TRANSMISSION, INC. SUPPLY HEADER PROJECT

Supplemental Filing January 10, 2017

APPENDIX G

Restoration and Rehabilitation Plan



ATLANTIC COAST PIPELINE, LLC ATLANTIC COAST PIPELINE Docket Nos. CP15-554-000 & CP15-554-001

and



DOMINION TRANSMISSION, INC. SUPPLY HEADER PROJECT Docket No. CP15-555-000

Restoration and Rehabilitation Plan

Updated, Rev 4



an ERM Group company **December 30, 2016**

TABLE OF CONTENTS

1.0	INTR	ODUCTION	1
2.0	PURP	POSE	1
3.0		NING	
4.0	VEGE	ETATION TYPES IN PROJECT AREA	2
5.0	BEST	MANAGEMENT PRACTICES	3
	5.1	EROSION CONTROL	3
	5.2	SOIL RESTORATION	4
	5.3	SOIL COMPACTION	4
	5.4	TOPSOIL SEGREGATION, REPLACEMENT, AND SOIL CONDITIONING	35
	5.5	RE-CONTOURING	5
	5.6	STEEP SLOPE AREAS	6
	5.7	SITE PREPARATION AND SEEDING	7
		5.7.1 Seedbed Preparation	7
		5.7.2 Seeding	8
		5.7.3 Seeding Revegetation Units along the Pipeline Route	9
		5.7.4 Summary of State and Federal Agencies and Subject Matter Experts	
		Consulted	
		5.7.5 Seed Mix Recommendations	11
		5.7.6 Seeding Methods	23
	5.8	SEEDBED AUGMENTATION	23
		5.8.1 Lime and Fertilizer Application	23
		5.8.2 Mulching	24
		5.8.3 Supplemental Plantings	25
	5.9	RIPARIAN RESTORATION	25
		5.9.1 Non-forested Riparian Areas	25
		5.9.2 Forested Riparian Areas	26
	5.10	WETLAND RESTORATION	26
	5.11	AGRICULTURAL AREAS	27
	5.12	EXPOSED BEDROCK	27
	5.13	UPLAND FOREST	27
6.0	FEDE	CRAL LANDS	28
7.0		E LANDS	
8.0	REST	ORATION MONITORING AND MAINTENANCE	29
	8.1	MONITORING	
	8.2	GRAZING DEFERMENTS	
	8.3	PERMANENT RIGHTS-OF-WAY MAINTENANCE	29
9.0	ROLE	ES AND RESPONSIBILITIES	
	9.1	ENVIRONMENTAL INSPECTORS	30
	9.2	DOCUMENTATION	
10.0	REFE	CRENCES	32

LIST OF TABLES

Table 5.7.4-1	Summary of Federal and State/Commonwealth Agencies and Subject Matter
	Expert Consultations
Table 5.7.5-1	Seed Mix P-MUDW01: Recommended Mountain Physiographic Region Seed
	Mix and Application Rates for Excessively to Moderately Well Drained Sites
	in West Virginia15
Table 5.7.5-2	Seed Mix P-MUDW01: Recommended Mountain Physiographic Region Forb
	Seed Mix and Application Rates for Excessively to Moderately Well Drained
	Sites in West Virginia
Table 5.7.5-3	Seed Mix P-VABCHNP01: Recommended Mountain Physiographic Region
	Grass Seed Mix and Application Rates for Excessively to Moderately Well
	Drained Sites in Virginia
Table 5.7.5-4	Seed Mix P-VABCHNP01: Recommended Mountain Physiographic Region
	Forb Seed Mix and Application Rates for Excessively to Moderately Well
	Drained Sites in Virginia
Table 5.7.5-5	Seed Mix P-MUMP02: Recommended Mountain Physiographic Region Grass
	Seed Mix and Application Rate for Somewhat Poorly to Very Poorly Drained
	Sites in West Virginia
Table 5.7.5-6	Seed Mix P-MUMP02: Recommended Mountain Physiographic Region Forb
	Seed Mix Application Rate for Somewhat Poorly to Very Poorly Drained
	Sites in West Virginia
Table 5.7.5-7	Seed Mix P-VABCHNP02:Recommended Mountain Physiographic Region
	Grass Seed Mix and Application Rates for Somewhat Poorly to Very Poorly
	Drained Sites in Virginia
Table 5.7.5-8	Seed Mix P-VABCHNP02: Recommended Mountain Physiographic Region
	Forb Mix and Application Rates for Somewhat Poorly to Very Poorly Drained
	Sites in Virginia
Table 5.7.5-9	Seed Mix P-VACSDGS01: Recommended Coastal Plain Physiographic
	Region Grass Seed Mix and Application Rates for Excessively to Moderately
	Well Drained Sites in Virginia
Table 5.7.5-10	Seed Mix P-VACSDGS01: Recommended Coastal Plain Physiographic
	Region Forb Seed Mix and Application Rates for Excessively to Moderately
	Well Drained Sites in Virginia
Table 5.7.5-11	Seed Mix P-CPDW01: Recommended Coastal Plain Physiographic Region
	Grass Seed Mix and Application Rates for Excessively to Moderately Well
	Drained Sites in North Carolina
Table 5.7.5-12	Seed Mix P-CPDW01: Coastal Plain Physiographic Region Seed Mix for
	Excessively to Moderately Well Drained Sites in North Carolina
Table 5.7.5-13	Seed Mix P-VACSDGS02: Coastal Plain Physiographic Region Seed Mix for
	Somewhat Poorly to Very Poorly Drained Sites in Virginia
Table 5.7.5-14	Seed Mix P-VACSDGS02: Coastal Plain Physiographic Region Seed Mix for
	Somewhat Poorly to Very Poorly Drained Sites in Virginia
Table 5.7.5-15	Seed Mix P-CPDW02:Recommended Coastal Plain Physiographic Region
	Grass Seed Mix and Application Rates for Somewhat Poorly to Very Poorly
	Drained Sites in North Carolina

Table 5.7.5-16	Seed Mix P-CPDW02: Recommended Coastal Plain Physiographic Region	ı
	Forb Seed Mix and Application Rates for Somewhat Poorly to Very Poorly	/
	Drained Sites in North Carolina	22

LIST OF FIGURES

Figure 5.7.3-1	Revegetation Unit Areas	Along the Pipeline	Corridor	11
1 1guie 5.7.5 1	Revegetation Onit meas	r nong the r ipenne		11

LIST OF APPENDICES

Appendix A	Major Soil and Drainage Slope Classes Crossed by the Projects
Appendix B	Recommended Seed Mix Prescriptions and Soil Amendments
Appendix C	Recommended Seed Mixes by Milepost (to be provided prior to construction)

LIST OF ACRONYMS AND ABBREVIATIONS

ACP	Atlantic Coast Pipeline
Atlantic	Atlantic Coast Pipeline, LLC
BFM	bonded fiber matrix
BMP	best management practice
DTI	Dominion Transmission, Inc.
EI	Environmental Inspector
FERC	Federal Energy Regulatory Commission
lbs/acre/PLS	pounds per acre of pure live seed
NRCS	Natural Resources Conservation Service
Plan	Upland Erosion Control, Revegetation, and Maintenance Plan
Procedures	Wetland and Waterbody Construction and Mitigation Procedures
Projects	Atlantic Coast Pipeline and Supply Header Projects
RU	revegetation unit
SHP	Supply Header Project
USFS	U.S. Forest Service
WMA	Wildlife Management Area

1.0 INTRODUCTION

Atlantic Coast Pipeline, LLC (Atlantic) – a company formed by four major energy companies – Dominion Resources, Inc.; Duke Energy Corporation; Piedmont Natural Gas Co., Inc.; and AGL Resources, Inc. – proposes to construct and operate approximately 600 miles of natural gas transmission pipelines and associated aboveground facilities in West Virginia, Virginia, and North Carolina. This Project, referred to as the Atlantic Coast Pipeline (ACP), will deliver up to 1.5 million dekatherms per day of natural gas from supply areas in the Appalachian region to demand areas in Virginia and North Carolina. Atlantic has contracted with Dominion Transmission, Inc. (DTI), a subsidiary of Dominion Resources, Inc., to construct and operate the ACP on behalf of Atlantic.

In conjunction with the ACP, DTI proposes to construct and operate approximately 37.5 miles of pipeline loop and modify existing compression facilities in Pennsylvania and West Virginia. This Project, referred to as the Supply Header Project (SHP), will enable DTI to provide firm transportation service to various customers, including Atlantic.

2.0 PURPOSE

This *Restoration and Rehabilitation Plan* was prepared for the ACP and SHP (collectively, the Projects) to address post-construction restoration and rehabilitation activities. The plan will be implemented in conjunction with the 2013 versions of the Federal Energy Regulatory Commission's (FERC) Upland Erosion Control, Revegetation, and Maintenance *Plan* (Plan) (FERC, 2013a) and *Wetland and Waterbody Construction and Mitigation Procedures* (Procedures) (FERC, 2013b) as well as Atlantic's and DTI's other construction, restoration, and mitigation plans (e.g., *Spill Prevention, Control, and Countermeasures Plan, Invasive Species Management Plan*, and *Winter Construction Plan*). The measures described in this plan reflect generally accepted best management practices (BMP) for restoration and rehabilitation of pipeline projects.

Atlantic and DTI have consulted with the U.S. Department of Agriculture's Natural Resources Conservation Service (NRCS) and are still in the process of consulting with other Federal, State/Commonwealth, and local agencies, including Federal and State/Commonwealth land managing agencies, to identify appropriate seed mixes for use during restoration. Based on discussions to date with the local NRCS offices, seed mixes have been developed and added to this plan. Seed mixes and how they were developed are described below. A more detailed description of seed mixes by region is presented in Appendix B.

On most pipeline projects, the seed mixes used for rights-of-way restoration generally consist of cool season grass species that grow well in the local area. Cool season grasses typically become established quickly and form a dense mat of grass and roots that is effective in controlling soil erosion in areas that have been disturbed by pipeline construction. These grasses may also provide food and habitat for some wildlife.

Atlantic is planning to incorporate regionally-specific and endemic forb (flowering plant) seeds in its traditionally all-grass seed mix. The incorporation and development of native flowering plants on the pipeline rights-of-way will create, where conditions and land

management practices are suitable (i.e., areas with slope less than or equal to about 15 percent), substantial acreages of pollination habitat where this type of habitat is currently non-existent, primarily previously forested areas.

Atlantic has consulted and continues to consult with various county offices of the NRCS, Federal land management resource specialists at the U.S. Forest Service (USFS) and U.S. Fish and Wildlife Service, soil and water conservation districts, the Xerces Society, private groups, and organizations that have specific knowledge of both perennial cover grasses as well as native pollinator forb species seed mixes. Atlantic has obtained recommendations regarding species, seeding rates, mulching during planting, and maintenance mowing. Atlantic has also met and consulted with various national, State/Commonwealth, and local groups and experts on pollinators and pollination species endemic to the region that the pipeline crosses to learn which native forb seed mixes will be complimentary to the various grass seed mixes. These meetings and consultations provided information about the appropriate seeding rates and percentages of each type of seed within a specific seed mix, as well as the location each seed mix is to be used considering the various soil types, elevations, temperatures, and other growing conditions along the rights-of-way.

Through consultations with regional native seed experts, particularly those working with the NRCS and the Xerces Society, Atlantic has determined that native flowering forbs grow best and reproduce most successfully when planted with native warm season grasses. Warm season grasses are slower to establish than cool season grasses, and are bunch grasses instead of mat forming. Warm season grasses and forbs do not provide soil coverage that is as dense or as effective at controlling erosion as cool season grasses. Therefore, Atlantic was advised and has elected to use native warm season grass and forb mixtures only in areas with gradual or low percent slopes. In general, in areas of the rights-of-way with slopes greater than 15 percent Atlantic will use cool season grass mixes without flowering forbs to most effectively control the potential for erosion. These areas are specified in Section 5.7.5 and in Appendix B.

Atlantic is committed to use only forb species that are native to the area or region where they will be planted, to try to source seed from local growers, as available, and to avoid the introduction of non-native and potentially invasive species to the extent practicable.

3.0 TRAINING

Prior to the start of construction, Atlantic and DTI will conduct environmental and safety training for Company and Contractor personnel. The training program will focus on the FERC's Plan and Procedures; other construction, restoration, and mitigation plans, including this *Restoration and Rehabilitation Plan*; and applicable permit conditions. In addition, Atlantic and DTI will provide large-group training sessions before each work crew commences construction with periodic follow-up training for groups of newly assigned personnel.

4.0 VEGETATION TYPES IN PROJECT AREA

Atlantic and DTI characterized vegetation types in the ACP Project area and SHP Project area based on review of the U.S. Geological Survey's National Gap Analysis Program Land Cover Data and recent digital aerial photography augmented by field reconnaissance (2014 and

2015). Based on these data, the proposed ACP pipeline facilities cross upland forest/woodland (241.8 miles), cultivated cropland (86.8 miles), wetlands (69.9 miles), pasture land (64.2 miles), tree plantation/harvested forest (59.4 miles), developed land (21.7 miles), open land (17.0 miles), and open water (3.3 miles). The proposed SHP pipeline facilities cross upland forest/woodland (33.0 miles), pasture land (2.2 miles), developed land (1.3 miles), cultivated cropland (0.5 mile), wetlands (0.3 mile), open water (0.2 mile), tree plantation/harvested forest (less than 0.1 mile), and open land (less than 0.1 mile). The types of upland woodland/forest crossed by the Projects include coniferous forests, deciduous forests, mixed forests, deciduous savanna and glades, and floodplain and riparian forests.

5.0 BEST MANAGEMENT PRACTICES

Based on FERC requirements identified in the Plan and Procedures and industry-accepted practices, Atlantic and DTI have identified and developed BMPs for restoration and rehabilitation of areas disturbed by construction. These BMPs have been used to establish Atlantic's and DTI's standards for restoration and revegetation as described below.

5.1 Erosion Control

Atlantic and DTI anticipate that construction activities requiring the installation of temporary erosion control devices will begin with access road preparation and timber clearing in 2017, and continue through the completion of construction in late 2019. Construction of the pipelines will be followed by restoration of the rights-of-way, stabilization of the soil, and seeding (where needed). Atlantic and DTI will complete final grading and installation of permanent erosion control structures (e.g., trench breakers or permanent slope breakers) generally within 20 days after backfilling the trench (10 days in residential areas), seasonal or other weather conditions permitting. For construction activities occurring in Winter, conditions such as frozen soils or snow cover could delay successful soil compaction mitigation or seeding activities. In these conditions, Atlantic and DTI will resume clean-up and restoration efforts the following Spring. Atlantic and DTI will monitor and maintain temporary erosion controls (e.g., temporary slope breakers, sediment barriers, or mulch) until conditions allow for completion of cleanup and installation of permanent erosion control structures.

Temporary erosion control measures and permanent erosion control devices to be employed during and after construction are described below. Atlantic and DTI will continue to consult with the applicable land managing agencies to identify other site-specific measures which may be required on Federal or State/Commonwealth lands.

• Slope Breakers – Temporary and permanent slope breakers will be installed, where required, to slow runoff velocity and direct water off the rights-of-way. Temporary slope breakers, such as hay bales (weed free), silt fence, or earthen berms, will be installed prior to the start of construction activities. Permanent slope breakers will be installed during final grading.

• Temporary Sediment Barriers – Temporary sediment barriers, such as silt fences, staked hay or straw bales (weed free), or a combination of barriers, will be installed at the

base of slopes adjacent to road, wetland, and waterbody crossings, and in other areas where required to prevent the transport of sediment off the construction rights-of-way.

• Permanent Trench Breakers – Sacks of subsoil or sand, polyurethane foam, or bentonite clay bags installed around the pipe will remain in the trench to prevent subsurface channeling of water along the trench.

• Mulch – Straw (weed free), hay (weed free), erosion-control fabric, or other equivalent material will be placed on the rights-of-way, where required, to protect the soil surface from water and wind erosion and to optimize the soil moisture regime necessary for successful revegetation, especially on dry, sandy sites.

During construction, the effectiveness of temporary erosion control devices will be monitored by Atlantic's and DTI's Environmental Inspectors (EI). Where appropriate for local resource needs, the role of the EI may be filled by agricultural or horticultural monitors. The effectiveness of revegetation and permanent erosion control devices will be monitored for the life of the project by Atlantic and DTI operating personnel during the long-term operation and maintenance of the pipeline systems.

5.2 Soil Restoration

Successful revegetation is dependent on appropriate soil conditions and can be influenced by several factors, including soil texture, drainage class, salinity, and acidity. Soil characteristics along the pipeline routes and access roads and at contractor yards and aboveground facility sites are identified in Resource Report 7. Unless otherwise approved by a land managing agency or landowner, soil restoration will include:

- removal of excavated rock that is not returned to the trench and is considered construction debris;
- distribution of rock on the work area that is of similar size and density to adjacent areas not disturbed by construction;
- grading of the rights-of-way to restore preconstruction contours to the extent practicable; and
- preparation of the soil for revegetation.

5.3 Soil Compaction

Soil compaction resulting from construction activities may reduce the potential for successful revegetation. Fine-textured soils with poor internal drainage that are moist or saturated during construction are the most susceptible to compaction and rutting. Atlantic and DTI will minimize impacts by implementing the mitigation measures for compaction and rutting as described in the Plan and Procedures. Atlantic and DTI will test for soil compaction:

• in residential and agricultural areas (e.g., active croplands, pastures, nurseries, and orchards);

- in other areas requested by the land managing agency or landowner;
- in undisturbed areas adjacent to the construction workspace with the same soil type under similar moisture conditions to approximate preconstruction conditions; and
- in areas identified by the EIs, who will be responsible for conducting subsoil and topsoil compaction testing and determining the need for corrective measures.

Compaction impacts will be mitigated through the use of tillage equipment during restoration activities such as a paraplow or similar implement. In areas where topsoil segregation occurs, plowing with a paraplow or other deep tillage implement to alleviate subsoil compaction will be conducted before replacement of the topsoil. In rocky or heavily rooted soils, compaction may be impossible to measure and rectify without additional damage. If compaction testing is impeded by rock or roots, Atlantic and DTI may conclude that there is a suitable amount of large material in the soil to rectify potential compaction. Soil compaction will be remediated prior to re-spreading of salvaged topsoil.

5.4 Topsoil Segregation, Replacement, and Soil Conditioning

The potential mixing of topsoil or surface soil with the subsoil from construction activities could result in a loss of soil fertility. To prevent mixing of the soil horizons or incorporation of additional rock into the topsoil, topsoil segregation will be:

• performed in the trenchline within non-saturated wetlands, croplands, pastures, hayfields, residential areas, and in other areas requested by the land managing agency or landowner;

- conducted as described in the Plan and Procedures;
- stockpiled on the rights-of-way; and
- excluded from materials used for padding the pipe.

Topsoil will be layered above subsoil where seeds stored in the soil will be encouraged to grow. Topsoil segregation will generally not occur in forested areas. Most forested areas are not conducive to topsoil segregation due to the amount of root materials present and the wider construction rights-of-way that would be required to store segregated topsoil. Topsoil segregation may be required on certain public lands as identified by land managing agencies; these will be identified and addressed through ongoing consultations with the land managing agencies (see Sections 5.0 and 6.0).

5.5 Re-Contouring

Grading will be conducted prior to construction where necessary to provide a reasonably level work surface. Upon completion of construction, Atlantic and DTI will:

• restore the ground surface as closely as practicable to original contours to restore natural overland water flow patterns, aquifer recharge, and drainage patterns;

- re-contour disturbed areas in a fashion designed to stabilize slopes, remove ruts and scars, and support successful revegetation; and
- restore, to original or better condition, drainage ditches and culverts that are diverted or damaged during construction.

5.6 Steep Slope Areas

Areas with steep slopes along the pipeline routes may make the establishment of vegetation more difficult due to the increased potential for stormwater runoff and erosion by water. In areas with slopes greater than 15 percent, Atlantic and DTI are planning to use seed mix prescriptions that utilize appropriate cool season grass species to quickly stabilize the disturbed areas and minimize erosion and sedimentation. Table 5.6-1 in Appendix A quantifies by county the major soil drainage and slope classes crossed by the Projects. Soil drainage classes were used to determine some of the grass seed types utilized in specific mixes (see Section 5.7.5).

The use of fast-growing cool season grasses will help to ensure faster soil stabilization in steeper terrain because of the faster development of stable root systems, which hold the soil in place. Additionally, in areas with slopes greater than 35 percent, the rights-of-way will be restored to natural contours to the extent practicable or in accordance with requests from land managing agencies or landowners. These steep slope areas are mostly located along the route in the Appalachian region of West Virginia and western Virginia but occasionally in other areas along the entire rights-of-way. Restoration of steep terrain may include:

- grading to the natural conditions;
- installation of permanent erosion control devices (i.e., slope breakers) designed to reduce runoff velocity, divert water from the surface of the rights-of-way, and encourage retention of soils; and
- the use of additional structural materials (e.g., rock or woody debris) to provide an anchor for revegetation and deposition of soil.

In addition to these general measures, Atlantic and DTI will develop and implement other additional site-specific measures, where warranted, to address land movement, surface erosion, backfill erosion, general soil stability when backfilling the trench, and restoring of the rights-of-way in steep slope areas. Specifically, as discussed in Resource Report 6, Atlantic and DTI are committed to employing best in class measures to protect the environment in steep slope areas. Best in class is defined as the most efficient and/or protective design or configuration with the least environmental impact providing reliable construction and operations.

Also as discussed in Resource Report 6, Atlantic and DTI will implement the Slip Avoidance, Identification, Prevention, and Remediation – Policy and Procedure, and are conducting geotechnical studies along the proposed pipeline routes in Pennsylvania, West Virginia, and western Virginia in steep terrain areas to assess the potential for landslides and landslips to occur during construction and operation of the Projects. The following lists some of the design and construction mitigation measures that will be implemented during construction in steep slope areas:

• targeted management and diversion of surface water around landslide sites, including the use of ditches, berms, slope breakers, and/or grading;

• mitigation of surface erosion by armoring or otherwise stabilizing surface soils using riprap, coir cloth, hydroseeding, mulching, and/or tracking;

• targeted management of water sources along the trench, including the use of trench breakers and/or added drainage piping in the trench;

• targeted mitigation of seeps, springs, or other subsurface water encountered along the rights-of-way using subsurface drains or other special drainage measures;

• engineering of the backfill around or within steep slope areas to dry the backfill, add compaction, improve backfill soil strength, and reduce saturation;

• installation of targeted structures to stabilize backfill using engineered fill, retaining walls, sack-crete placements, key trenches, and/or shear trenches; and

• reduction in surcharge on steep slope areas by reducing excess or saturated backfill.

5.7 Site Preparation and Seeding

Atlantic and DTI will complete final grading and permanent erosion control measures within 20 days after backfilling of the trench (10 days in residential areas), seasonal or other weather conditions permitting. In the event that these timeframes cannot be met or construction or restoration activities are interrupted for an extended period, mulch will be spread prior to seeding. In these cases, all slopes within 100 feet of wetlands or waterbodies will be mulched at a rate of 3 tons per acre.

5.7.1 Seedbed Preparation

Proper preparation of the soil surface and seedbed is essential for rapid and healthy revegetation (Virginia Department of Environmental Quality, 1992). Successful germination of seed is enhanced by a well-prepared seedbed, the suitability of which decreases rapidly after rainfall.

Seedbed preparation starts immediately after soil has been replaced on the rights-of-way and final grading, contouring, and de-compaction activities are complete. Seedbed preparation will be conducted immediately prior to seeding to prepare a firm seedbed conducive to proper seed placement. Seedbed preparation will also be performed to break up surface crusts and to reduce weeds that develop between the initial ground clearing and final seeding.

Unless otherwise specified by land managing agencies or landowners or as needed to support the establishment of pollinator habitat, the seedbed will be prepared in disturbed areas to

a depth of 3 to 4 inches using appropriate equipment (e.g., cultipacker roller) to provide a seedbed that is firm, yet rough. Atlantic and DTI will imprint exposed soils with a sheepsfoot, landfill compactor, tractor with studded tires, or land imprinter equipment. Soil imprinting, or tracking, leaves divots on the ground surface that trap moisture and seeds, creating catchments for native plant material to be spread across the seeded area (West Virginia Department of Environmental Protection, 2012). In addition, a seedbed with a rough surface is conducive to the capturing or lodging of seed when broadcasted or hydroseeded, and can reduce runoff and erosion potential. The rough seedbed surface will also retain soil moisture for seedling germination and promote faster establishment of vegetation.

In compacted areas, additional measures such as chisel plowing or disking may be necessary to improve water infiltration and soil aeration, which are needed to prepare an adequate seedbed. When hydroseeding, Atlantic and DTI will scarify the soil surface prior to seeding to anchor the seed to the soil surface and encourage germination. Where residential lawns or landscaped areas are disturbed or as needed to support the establishment of pollinator habitat, more intensive ground and seedbed preparations may be required, including rock collection, grading, and soil preparation/amending.

5.7.2 Seeding

Seeding will not be conducted in actively cultivated croplands unless requested by the landowner. In residential areas, lawns will be restored on a schedule established during easement negotiations with the landowner. On all other lands, Atlantic and DTI will perform seeding of permanent vegetation during the Fall of the year construction is completed, within the recommended seeding dates, and within six working days of final grading, weather and soil conditions permitting. Atlantic and DTI will prioritize seeding and other restoration work in high-elevation areas, in an attempt to avoid restoration delays due to Winter-related weather and field conditions. If seeding cannot be done within recommended Fall timeframes, appropriate temporary erosion control measures will be installed and temporary grass cover will be seeded. If temporary grass cover is used, seeding of permanent vegetation will occur at the beginning of the next recommended seeding season.

In addition, as part of the restoration and rehabilitation plan to revegetate disturbed areas along the pipeline routes, Atlantic and DTI will use cool season grasses to revegetate areas with slopes greater than 15 percent.

All seed will be certified weed free. The EIs will review all seed tags prior to use to ensure that the seed is properly certified.

5.7.2.1 Pollinator Habitat Planting

Atlantic, in support of a 2014 <u>Presidential Memorandum</u> that directs federal agencies to cooperate on the development of a national pollinator strategy, has committed to a pollinator habitat initiative where suitable along the rights-of-way. The successful establishment of pollinator habitat will require specialized: soil preparation, seeding techniques, and maintenance practices.

The most common causes for failed establishment when planting pollinator species are: (1) poor soil/seed contact and planting the seed more than one-quarter inch deep in the soil, and (2) competition from annual weeds, non-natives or invasive vegetation. To prevent competition from other vegetation, Atlantic will reduce the existing seed bank in the rights-of-way. The seed bank will be reduced by clearing the existing vegetation (done during construction) and by using herbicides.

Additional soil preparation is also needed to ensure seed germination. The soil surface must be relatively smooth and compact to allow shallow seeding, no more than one-quarter inch deep. Typically, planting will include the use of a nurse crop or cover crop to ensure proper soil erosion control and the survival of the pollinator plant species. Cover crops (e.g., annual oats) are also generally used in traditional rights-of-way seeding.

The warm season grasses and endemic forbs used to establish pollinator habitat need to be planted in the Spring. Therefore,

- For Fall, Rights-of-way Restoration: Plant a cover crop and then plant the pollinator seed mix with a nurse crop in the Spring after a herbicide application.
- For Spring, Rights-of-way Restoration: Apply a herbicide prior to planting but after the weed seeds germinate and then plant the pollinator seed mix and a nurse crop together.
- For Summer, Rights-of-way Restoration: Plant a cover crop and then plant the pollinator seed mix with a nurse crop in the Spring after a herbicide application.

Atlantic plans to plant the pollinator species in both the permanent and construction rights-of-way. Atlantic has proposed seed mixes based on the recommendations from consultations with state and federal agencies. These seed mixes are described in more detail below and in Appendix B. Pollinator species seed mixes will be finalized in consultation with these agencies.

5.7.2.2 Pollinator Habitat Maintenance

Additional mowing is required in the first two years to reduce the height of the weeds and to prevent them from going to seed which will greatly reduce weed competition. Spot use of herbicides should be an option to control woody and invasive plants. Pollinator habitat experts recommend periodic prescription burning of the rights-of-way to reduce accumulated duff (i.e., dead vegetation on top of the ground) so that the pollinator species (flowers) can continue to reseed and maintain a viable population. Mowing close, 4 inches, and or thatching/raking may be viable alternatives to prescribed burning. Maintenance practices should be adapted to what is proven to be the best practices to ensure quality pollinator habitat.

5.7.3 Seeding Revegetation Units along the Pipeline Route

After consultations with Federal, State/Commonwealth, local resource and land managing agencies, and subject matter experts and in order to ensure optimum seed germination

and growth, the areas crossed by the Projects were divided into four Revegetation Units (RU). One of the RUs is dependent on and defined by the steepness of the slopes crossed by the proposed pipelines. This RU can occur in site-specific locations anywhere along the pipeline corridors. The three other RUs are based on physiographic regions, and cover areas that are relatively homogenous with regards to factors such as soil type, vegetation, and climate that will affect the revegetation potential of the area. Each RU has distinct seed mix prescriptions. The four RUs include the following:

- Steep to Very Steep Slope RU;
- Mountain Physiographic Region RU;
- Piedmont Physiographic Region RU; and
- Coastal Plain Physiographic Region RU.


Figure 5.7.3-1 shows the distribution of the RUs, including the areas with slopes greater than 15 percent, along the pipeline route. Seed mix descriptions specific for each RU are provided in Appendix B.

5.7.3.1 Steep to Very Steep Slope

Although the Steep to Very Steep Slope RU includes areas with greater than 15 percent slope located anywhere along the Projects, most of these areas are located within the mountainous areas of the western Piedmont Physiographic RU and the Mountain Physiographic RU (see Figure 5.7.3-1). To a much lesser extent, the Steep to Very Steep Slope RU may also be found in smaller, site-specific areas along the pipeline rights-of-way where the steepness of the local terrain increases the erosion potential. The areas in this RU require appropriate seed mix prescriptions, erosion control measures, and BMPs that are able to quickly stabilize the disturbed areas to minimize erosion and sedimentation.

5.7.3.2 Mountain Physiographic Region

The ACP Project area extends across the Mountain Physiographic Region RU in West Virginia and western Virginia (see Figure 5.7.3-1). In West Virginia, the RU encompasses the Western Allegheny Plateau, Central Appalachians, and Ridge and Valley ecoregions. The SHP Project area also extends across the Western Allegheny Plateau in northeastern West Virginia and southwestern Pennsylvania. In Virginia, this RU encompasses the Ridge and Valley, Blue Ridge (mountains), and the Southeastern Plains ecoregions. The soils in the Mountain Region RU generally consist of shallow soils with a loamy surface and subsoil texture. Steep slopes with shallow, stony, droughty soils are common throughout the area, and many mountainous soils have been severely eroded due to steepness. In less steep areas, the soils are deep and stable (less erodible).



The recommended seed mix prescriptions identified for each of the RUs will be identified by milepost in Appendix C, which will be filed with the FERC prior to construction. The sitespecific seed mixes will also be included on the construction alignments sheets to identify the seed mixes to be used by the construction contractors during restoration.

			TABLE 5.7.4-1		
	Summary of Federal a	nd State/Commonw	ealth Agencies and Subj	ect Matter Expert	Consultations
	Agency/				
Contact Name	Organization	County	Title/Role	Phone	Email
West Virginia					
Greg Stone	NRCS - State Office	All Counties	Acting State Resource Conservationist	304-284-7579	greg.stone@wv.usda.gov
Jeff Griffith	USDA NRCS	Harrison; Lewis; Doddridge	District Conservationist	304-624-9232 x 110	jeff.griffith@wv.usda.gov
Jack O'Connell	USDA NRCS	Pocahontas	District Conservationist	304-799-4317	jack.oconnell@wv.usda.gov
Barbara Sargent	West Virginia Department of Natural Resources	Wetzel	Wildlife Biologist	304-637-0245	barbara.d.sargent@wv.gov
Cliff Brown	West Virginia Department of Natural Resources	Wetzel	Wildlife Biologist	304-637-0245	clifford.l.brown@wv.gov
Idun Guenther	NRCS	Pocahontas	District Conservationist	304-255-9225	idun.guenther@wv.usda.gov
Susan Davis	NRCS	Pocahontas	Soil Conservationist	304-799-4317	susan.davis@wv.usda.gov
Rob Silvester	West Virginia Department of Natural Resources	Randolph	District Wildlife Biologist	304-924-6211	rob.a.silvester@wv.gov
Steve Rauch	West Virginia Department of Natural Resources	Randolph; Wetzel	District Wildlife Biologist	304-825-6787	steven.e.rauch@wv.gov
Ben Collier	NRCS	Randolph; Upshur	District Conservationist	304-636-6703 x 305	ben.collier@wv.usda.gov
Jeremy Bennett	NRCS	Randolph; Upshur	District Conservationist	304-457-4516	jeremy.bennett@wv.nrcs.gov
Dustin Adkins	NRCS	Tyler; Wetzel	District Conservationist	304-758-2173 x 1	dustin.adkins@wv.usda.gov
Katie Fitzsimmons	NRCS	Marshall	District Conservationist	304-242-0576 x 108	katie.fitzsimmons@wv.usda.gov
Virginia					
Amy Ewing	Virginia Department of Game and Inland Fisheries	Virginia Counties	Environmental Services Biologist/Fish & Wildlife Information Manager	804-367-2211	<u>Amy.Ewing@dgif.virginia.gov</u>
Charles Ivins	NRCS	Augusta; Highland	District Conservationist	540-248-6218 x 122	charles.ivins@va.usda.gov
Charles Simmons	NRCS	Bath	District Conservationist	540-463-7124 x111	charles.simmons@va.usda.gov
Justin Folk	NRCS/Virginia Department of Game and Inland Fisheries	Bath	Private Lands Wildlife Biologist	540-248-6218 x 108	justin.folks@va.usda.gov
Davie Wade Harris	NRCS	Brunswick	District Conservationist	434-848-2145 x 102	davie.harris@va.usda.gov
David Harris	NRCS	Buckingham; Cumberland	District Conservationist	434-983-4757 x 101	david.harris@va.usda.gov

			TABLE 5.7.4-1		
	Summary of Federal a	nd State/Commony	vealth Agencies and Subj	iect Matter Expert	Consultations
Contact Name	Agency/ Organization	County	Title/Role	Phone	Email
Bryan Poovey	U.S. Fish and Wildlife Service	Chesapeake; Suffolk (City); (Great Dismal Swamp National Wildlife Refuge)	Forestry Scientist	757-986-3705	bryan_poovey@fws.gov
David Bryd	U.S. Fish and Wildlife Service	Great Dismal Swamp NWR	Forestry Scientist	804-824-2412	david_byrd@fws.gov
Robert E. Williams	NRCS	Chesapeake	District Conservationist	757-547-7172 x 102	robert.williams@va.usda.gov
Bob Glennon	NRCS	Eastern Virginia Counties	Private Lands Biologist	757-357-7004 x 126	robert.glennon@va.usda.gov
Anthony Howell	NRCS	Dinwiddie	District Conservationist	804-469-7297 x 106	anthony.howell@va.usda.gov
Harvey Baker	NRCS	Greensville	District Conservationist	434-634-2115 x 109	harvey.baker@va.usda.gov
Jay Jeffreys	Virginia Department of Game and Inland Fisheries	Highland; Nelson	Biologist	540-248-9360	jay.jeffreys@dgif.virginia.gov
Kory Kirkland	NRCS	Nelson	District Conservationist	540-967-0233 x 111	kory.kirkland@va.usda.gov
Jeffray Jones	NRCS	All Counties	State Biologist	804-287-1691	jeffray.jones@va.usda.gov
J.B. Daniel	NRCS	Prince Edward	Agronomist Director	434-392-4171	j.b.daniel@va.usda.gov
Derek Hancock	NRCS	Nottoway; Prince Edward	District Conservationist	434-392-4127 x 101	derek.hancock@va.usda.gov
Yamika Bennett	NRCS	Southampton	District Conservationist	757-653-2532 x 122	yamika.bennett@va.usda.gov
Michael A. Faulk	NRCS	Suffolk (City)	District Conservationist	757-357-7004 x 114	mike.faulk@va.usda.gov
Ryan McCormick	National Park Service		Specialist Coordinator	828-348-3441	
J. Christopher Ludwig Marc Puckett	g DCR DGIF	All Counties All Counties	Chief Biologist QMAP Coordinator	804-371-6206 434-392-9645	Chris.Ludwig@dcr.virginia.gov Marc.Puckett@dgif.virginia.gov
			-		
North Carolina Renessa Hardy- Brown	NRCS	Cumberland	District Conservationist	910-484-8479	renessa.brown@nc.usda.gov
Terry Best	NRCS	Halifax	District Conservationist	252-583-3481	terry.best@nc.usda.gov
Brian Loadholt	NRCS	Johnston	District Conservationist	919-934-7156	brian.loadholt@nc.usda.gov
Patrick Evens	NRCS	Nash	District Conservationist	252-459-4116 x 124	patrick.evans@nc.usda.gov
Paul Boone	NRCS	Northampton	District Conservationist	252-534-2591	paul.boone@nc.usda.gov
Jeremy Ruston	NRCS	Robeson	District Conservationist	910-739-5478	jeremy.roston@usda.gov
Gavin Thompson	NRCS	Sampson	District Conservationist	910-592-7963	gavin.thompson@nc.usda.gov
David Little	NRCS	Wilson	District Conservationist	252-237-2711	david.little@nc.usda.gov
Pennsylvania					
Chris Droste	Westmoreland Conservation District	Westmoreland	Erosion Control Specialist	724-837-5271	chris@wcdpa.com
Subject Matter Expe	erts				
Mark Fiely	Ernst Seeds	All Counties	Horticulturist	800-873-3321	hortpath@ernstseed.com

TABLE 5.7.4-1					
Summary of Federal and State/Commonwealth Agencies and Subject Matter Expert Consultations					
Contact Name	Agency/ Organization	County	Title/Role	Phone	Email
Jeremy Hamlington	Roundstone Native Seed	All Counties	Horticulturist	270-531-3034	jeremy@roundstoneseed.com
Bob Glennon	NRCS / The Xerces Society	All Counties	Private Lands Biologist	757-357-7004 x 126	robert.glennon@va.usda.gov
Nancy Lee Adamson	The Xerces Society for Invertebrate Conservation &	All Counties	Pollinator Conservation Specialist	336-370-3443	nancy@xerces.org
	NRCS East National Technology Support Center				

5.7.5.1 Steep to Very Steep Slope Seed Mixes

As described in Sections 5.7.3, the Steep to Very Steep Slope RU includes areas with high erosion potential (e.g., slopes greater than 15 percent). These areas require appropriate seed mixtures and erosion control measures that are able to quickly stabilize disturbed areas. The recommended seed mixes include the use of cool season grasses, which are identified by County in Appendix B.

5.7.5.2 Mountain Physiographic Region Seed Mixes

Excessively to Moderately Well Drained Sites

West Virginia

The proposed Mountain Physiographic Region Seed Mix P-MUDW01 (Tables 5.7.5-1 and 5.7.5-2) was designed to be compatible with the Mountain Physiographic Region RU in areas with slopes of 15 percent or less. The mix is based on selected native grass and forb species suitable for the restoration of excessively to moderately well-drained mountainous areas in West Virginia.

Virginia

The proposed Mountain Physiographic Region Seed Mix P-VABCHNP01 (Tables 5.7.5-3 and 5.7.5-4) was designed to be compatible with the Mountain Physiographic Region RU in areas with slopes of 15 percent or less. The mix is based on selected native grass and forb species suitable for restoration in excessively to moderately well-drained mountainous areas in Virginia.

Somewhat Poorly to Very Poorly Drained Sites

West Virginia

The proposed Mountain Physiographic Region Seed Mix P-MUDW02 (Tables 5.7.5-5 and 5.7.5-6) was designed to be compatible with the Mountain Physiographic Region RU in

areas with slopes of 15 percent or less. The mix is based on selected native grasses and forb species suitable for restoration in somewhat poorly to very poorly-drained mountainous areas in West Virginia.

<u>Virginia</u>

The proposed Mountain and Upland Seed Mix P-VABCHNP02 (Tables 5.7.5-7 and 5.7.5-8) was designed to be compatible with the Mountain Physiographic Region RU in areas with slopes of 15 percent or less. The mix is based on selected native grasses and forb species suitable for restoration in somewhat poorly to very poorly-drained mountainous areas in Virginia.

Seed Mix P-MUDW01: Recommended Mountain Physiological Region Grass Seed Mix and Application Rates for Excessively to Moderately Well Drained Sites in West Virginia ^a						
Common Name	Scientific Name	Height (feet)	Sun Exposure	Seed Mix Rate (lbs/acre/PLS)		
Little Bluestem	Schizachyrium scoparium	2 - 4	Full Sun	0.250		
Virginia Wild Rye	Elymus virginicus	2 - 4	Full Sun	0.250		
Tall Dropseed	Sporobolus compositus	2 - 3	Full Sun	0.050		
Purple Top	Tridens flavus	3 - 5	Part Shade	0.058		
Indian Grass	Sorghastrum nutans	3 - 6	Full Sun	0.167		
Switchgrass	Panicum virgatum	3 - 7	Full Sun	0.183		
Fall Panicum	Panicum anceps	2 - 4	Part Shade	0.042		
Total	—	_	—	1.0		
	ive Seed, 2015; Glennon, 2015					

		TABLE 5.7.5-2				
	Seed Mix P-MUDW01: R	ecommended Mou	ntain Physiological F	Region		
Forb Seed Mix and Application Rates for Excessively to Moderately Well Drained Sites in West Virginia						
Common Name	Scientific Name	Color	Bloom Period	Seed Application Rate (lbs/acre/PLS)		
Lance Leaved Coreopsis	Coreopsis lanceolata	Yellow	Spring,Summer	0.385		
Smooth Beardtongue	Penstemon digitalis	White	Spring	0.146		
Common Milkweed	Asclepias syriaca	Pink	Spring, Summer	0.128		
Goat's Rue	Tephrosia virginiana	White/Pink	Spring, Summer	0.128		
Partridge Pea	Cassia fasciculata	Yellow	Summer	0.745		
Slender Mountain Mint	Pycnanthemum tenuifolium	White	Summer	0.069		
Early Goldenrod	Solidago juncea	Yellow	Summer	0.086		
Bergamot	Monarda fistulosa	Lavender	Summer	0.103		
Spiked Blazing Star	Liatris spicata	Pink	Summer	0.343		
Sneezeweed	Helenium autumnale	Yellow	Summer, Fall	0.128		
Gray Goldenrod	Solidago nemoralis	Yellow	Fall	0.086		
Iron Weed	Vernonia altissima	Purple	Summer, Fall	0.343		
Tall Coreopsis	Coreopsis tripteris	Yellow	Summer, Fall	0.051		
Total				2.74		

TABLE 5.7.5-2

Seed Mix P-MUDW01: Recommended Mountain Physiological Region

Forb Seed Mix and Application Rates for Excessively to Moderately Well Drained Sites in West Virginia

Sources: Roundstone Native Seed, 2015; Glennon, 2015 ^a lbs/acre/PLS = pounds per acre of pure live seed

TABLE 5.7.5-3

Common Name	Scientific Name	Cultivar or Germplasm	Drilled Seeding Rate ^a (weight of pure live seed (PLS) per acre)	Seeds per Square Foot
Little Bluestem	Schizachyrium scoparium	Cimarron (OK) or Suther Germplasm (NC)	0.5 pound	3
Splitbeard Bluestem	Andropogon ternarius	Missouri or Kentucky Ecotype	0.5 pound	3

TABLE 5.7.5-4

Common Name ^a	Scientific Name	Flowering Season	Seeding Rate (weight of bulk seed per acre)	Seeds per Square Foot
Bearded Beggartick (A)	Bidens aristosa	Late Summer	1 pound	3
Plains Coreopsis (A)	Coreopsis tinctoria	Late Spring	1 ounce	3
Partridge Pea (A)	Chamaecrista fasciculata	Mid-Summer	2 pounds	3
Black-eyed Susan (B)	Rudbeckia hirta	Early Summer	2 ounces	3
Wild Bergamot (P)	Monarda fistulosa	Summer	1 ounce	3
Lanceleaf Coreopsis (P)	Coreopsis lanceolata	Late Summer	10 ounces	3
Maximilian Sunflower (P)	Helianthus maximilianii	Late Summer	11 ounces	3
Slender Mountain Mint (P)	Pycnanthemum tenuifolium	Late Summer	1 ounce	3
Purple Coneflower (P)	Echinacea purpurea	Early Summer	1.2 pound	3
Total	_	_	6.8 lbs/acre	33

Grass	Seed Mix and Application Rate		untain Physiographic Re to Very Poorly Drained 3	8
Common Name	Scientific Name	Height (feet)	Sun Exposure	Seed Mix Rate (lbs/acre/PLS) ^b
Switchgrass	Panicum virgatum	3 - 7	Full Sun	0.233
Red Top Panicum	Panicum rigidulum	2 - 4	Full Sun	0.017
Fowl Manna Grass	Glyceria striata	3 - 5	Part Shade	0.008
Virginia Wild Rye	Elymus virginicus	2 - 4	Full Sun	0.217
Canada Wild Rye	Elymus canadensis	2 - 5	Part Shade	0.167
Deer Tongue Grass	Panicum clandestinum	2 - 4	Full Sun	0.058
Big Bluestem	Andropogon gerardii	4 - 10	Full Sun	0.167
Frank's Sedge	Carex frankii	1 - 2	Part Shade	0.042
Fox Sedge	Carex vulpinoidea	2 - 3	Part Shade	0.025
Fall Panicum	Panicum anceps	2 - 4	Part Shade	0.067
Total	_	_	_	1.0

For	Seed Mix P-MOMPO Seed Mix Application Rate fo		ountain Physiographic F	8
Common Name	Scientific Name	Color	Bloom Period	Seed Application Rate (lbs/acre/PLS)
Ohio Spiderwort	Tradescantia ohiensis	Blue	Spring, Summer	0.167
Smooth Beardtongue	Penstemon digitalis	White	Spring	0.083
Butterfly Milkweed	Asclepias tuberosa	Orange	Spring, Summer	0.083
Blackeyed Susan	Rudbeckia hirta	Yellow	Spring, Summer	0.134
Wild Senna	Senna marilandica	Yellow	Summer	0.668
Hoary Mountain Mint	Pycnanthemum incanum	White	Summer	0.033
Lupine	Lupinus perennis	Blue	Summer	0.501
Bergamot	Monarda fistulosa	Lavender	Summer	0.083
Boneset	Eupatorium perfoliatum	White	Summer	0.083
Joe-Pye Weed	Eupatorium fistulosum	Pink	Summer, Fall	0.125
Showy Tickseed	Bidens aristosa	Yellow	Summer, Fall	0.501
Sneezeweed	Helenium autumnale	Yellow	Summer, Fall	0.125
Rough Goldenrod	Solidago rugosa	Yellow	Fall	0.083
Total	_	_	_	2.67

		TABLE 5.7.5-7		
Grass S		P02: Recommended Mounta es for Somewhat Poorly to V	in Physiographic Region Very Poorly Drained Sites in	Virginia ^a
Common Name	Scientific Name	Cultivar or Germplasm	Drilled Seeding Rate ^a (weight of pure live seed (PLS) per acre)	Seeds per Square Foot
Beaked Panicum	Panicum anceps	SC or MD Ecotype	0.25 pound	3
Redtop Panicum	Panicum rigidulum	NC Ecotype	0.20 pound	3
Source: Glennon, 2015 ^a If the broadcas	st method is more feasible, incr	ease the perennial grasses in t	he mixture by 0.25 pounds.	

TABLE 5.7.5-8

Common Name ^a	Scientific Name	Flowering Season	Seeding Rate (weight of bulk seed per acre)	Seeds per Square Foo
Aster, Purple-stemmed (P)	Symphyotrichum puniceum var. puniceum	Fall	3 ounces	3
Bergamot, Wild (P)	Monarda fistulosa	Summer	1 ounce	3
Coreopsis, Plains (A)	Coreopsis tinctoria	Late Spring	1 ounce	3
Goldenrod, Pine Barrens (P)	Solidago fistulosa	Late Summer	3 ounces	3
Joe Pye Weed, Spotted (P)	Eupatoriadelphus fistulosus	Late Summer	2 ounces	3
Partridge Pea (A)	Chamaecrista fasciculata	Mid-Summer	2 pounds	3
Rattlesnake Master (P)	Eryngium yuccifolium	Summer	8 ounces	3
Rosemallow (P)	Hibiscus moscheutos	Summer	2 ounces	3
Narrowleaf Sunflower (P)	Helianthus angustifolius	Late Summer	4 ounces	3
Total	_	_	4.0 lbs/acre	33

Pennsylvania

In Pennsylvania, the SHP pipeline (approximately 3.9 miles) will be collocated with DTI's existing LN-25 pipeline in Westmoreland County. In general, the SHP pipeline will be constructed within and directly adjacent to the existing LN-25 pipeline rights-of-way which is seeded with cool season grasses. As presented in Appendix B, the recommended seed mixtures, rates, and amendments for the SHP were based on existing site conditions and compatibility with existing grasses, which includes the use of cool season grasses. No pollinator species specific to the area were recommended.

5.7.5.3 Piedmont Physiographic Region Seed Mixes

Excessively to Moderately Well Drained Sites

Virginia

The proposed Mountain Physiographic Seed Mix P-VABCHNP01 that is described in Section 5.7.5.2 was designed to also be compatible with the Piedmont Physiographic Region RU in excessively to moderately well drained areas in Virginia.

Somewhat Poorly to Very Poorly Drained Sites

Virginia

The proposed Mountain Physiographic Seed Mix P-VABCHNP02 described in Section 5.7.5.2 was designed to also be compatible with the Piedmont Physiographic Region RU in somewhat poorly to very poorly drained sites in Virginia.

5.7.5.4 Coastal Plain Physiographic Region Seed Mixes

Excessively to Moderately Well Drained Sites

Virginia

The proposed Coastal Plain Seed Mix P-VACSDGS01 (Tables 5.7.5-9 and 5.7.5-10) was designed to be compatible with the Coastal Plain Physiographic Region RU in areas with slopes of 15 percent or less. The mix is based on selected native grass and forb species suitable for restoration in excessively to moderately well drained coastal areas in Virginia.

North Carolina

The proposed Coastal Plain Seed Mix P-CPDW01 (Tables 5.7.5-11 and 5.11.5-12) was designed to be compatible with the Coastal Plain Physiographic Region RU in areas with slopes of 15 percent or less and is based on selected native grass and forb species suitable for restoration in excessively to moderately well drained coastal areas in North Carolina.

Somewhat Poorly to Very Poorly Drained Sites

Virginia

The proposed Coastal Plain Seed Mix P-VACSDGS02 (Tables 5.7.5-13 and 5.7.5-14) was designed to be compatible with the Coastal Plain Physiographic Region RU in areas with slopes of 15 percent or less. The mix is based on selected native grass and forb species suitable for restoration in somewhat poorly to very poorly drained coastal areas in Virginia.

		TABLE 5.7.5-9		
Gr		GS01: Recommended Coastal Plai n Rates for Excessively to Modera	in Physiographic Region htely Well Drained Sites in Virginia	
Common Name	Scientific Name	Cultivar or Germplasm	Drilled Seeding Rate ^a (weight of pure live seed (PLS) per acre)	Seeds per Square Foot
Little Bluestem	Schizachyrium scoparium	Cimarron (OK) or Suther Germplasm (NC)	0.5 pound	3
Splitbeard Bluestem	Andropogon ternarius	Missouri or Kentucky Ecotype	0.5 pound	3
Source: Glennon, 2015 ^a If the broad		ncrease the perennial grasses in the	mixture by 0.25 pounds.	

TABLE 5.7.5-10

Common Name ^a	Scientific Name	Flowering Season	Drilled Seeding Rate (weight of bulk seed per acre)	Seeds per Square Foo
Narrowleaf Mountain Mint (P)	Pycnanthemum tenuifolium	Late Summer	1 ounce	3
Plains Coreopsis (A)	Coreopsis tinctoria	Late Spring	1 ounce	3
Partridge Pea (A)	Chamaecrista fasciculata	Mid-Summer	2 pounds	3
Black-eyed Susan (B)	Rudbeckia hirta	Early Summer	2 ounces	3
Bergamot, Spotted (P)	Monarda fistulosa	Summer	1 ounce	3
Lanceleaf Coreopsis (P)	Coreopsis lanceolata	Late Summer	10 ounces	3
Maximilian Sunflower (P)	Helianthus maximilianii	Late Summer	11 ounces	3
Indian Blanket (A)	Gaillardia pulchella	Indeterminate	9 ounces	3
Purple Coneflower (P)	Echinacea purpurea	Early Summer	1.2 pound	3
Total	_	—	6.4 lbs/acre	33

Seed Mix P-CPDW01: Recommended Coastal Plain Physiographic Region Grass Seed Mix and Application Rates for Excessively to Moderately Well Drained Sites in North Carolina					
Common Name	Scientific Name	Height (feet)	Sun Exposure	Seed Mix Rate (lbs/acre/PLS) ^b	
Little Bluestem	Schizachyrium scoparium	2-4	Full Sun	0.250	
Virginia Wild Rye	Elymus virginicus	2 - 4	Full Sun	0.250	
Tall Dropseed	Sporobolus compositus	2 - 3	Full Sun	0.050	
Purple Top	Tridens flavus	3 - 5	Part Shade	0.058	
Indian Grass	Sorghastrum nutans	3 - 6	Full Sun	0.167	
Switchgrass	Panicum virgatum	3 - 7	Full Sun	0.183	
Fall Panicum	Panicum anceps	2 - 4	Part Shade	0.042	
Total	—	—	—	1.0	
Sources: Roundstone	 Native Seed, 2015; Glennon, 201	5			
	nded seeding application rate is 8				
^b lbs/acre/PL	S = pounds per acre of pure live	seed			

Seed Mix P-CPDW01: Recommended Coastal Plain Physiographic Region Forb Seed Mix and Application Rates for Excessively to Moderately Well Drained Sites in North Carolina					
Common Name	Scientific Name	Color	Bloom Period	Seed Application Rate (lbs/acre/PLS)	
Lance Leaved Coreopsis	Coreopsis lanceolata	Yellow	Spring, Summer	0.266	
Spotted Beebalm	Monarda punctata	Pink	Spring, Summer	0.124	
Common Milkweed	Asclepias syriaca	Pink	Spring, Summer	0.107	
Smooth Beardtongue	Penstemon digitalis	White	Spring	0.107	
Bergamot	Monarda fistulosa	Lavender	Summer	0.124	
Partridge Pea	Cassia fasciculata	Yellow	Summer	0.621	
Spiked Blazing Star	Liatris spicata	Pink	Summer	0.222	
Lupine	Lupinus perennis	Blue	Summer	0.497	
Early Goldenrod	Solidago juncea	Yellow	Summer	0.160	
Starry Silphium	Silphium asteriscus	Yellow	Summer, Fall	0.178	
Iron Weed	Vernonia altissima	Purple	Summer, Fall	0.222	
Sneezeweed	Helenium autumnale	Yellow	Summer, Fall	0.124	
Hairy Mountain Mint	Pycnanthemum pilosum	White	Summer, Fall	0.089	
Total	_	_	_	2.84	

TABLE 5.7.5-13

		Cultivar or	Drilled Seeding Rate a (weight	
Common Name	Scientific Name	Germplasm	of pure live seed (PLS) per acre)	Seeds per Square Foot
Beaked Panicum	Panicum anceps	SC or MD Ecotype	0.25 pound	3
Redtop Panicum	Panicum rigidulum	NC Ecotype	0.20 pound	3

If the broadcast method is more feasible, increase the perennial grasses in the mixture by 0.25 pounds.

Forb See	Seed Mix P-VACSDGS02: Recommended (d Mix and Application Rates for Somewhat P	•	8 i 8	
Common Name ^a	Scientific Name	Flowering Season	Drilled Seeding Rate (weight of bulk seed per acre)	Seeds per Square Foo
Aster, Purple-stemmed (P)	Symphyotrichum puniceum var. puniceum	Fall	3 ounces	3
Sneezeweed, Common (P)	Helenium autumnale	Fall	2 ounces	3
Coreopsis, Plains (A)	Coreopsis tinctoria	Late Spring	1 ounce	3
Goldenrod, Wrinkleleaf (P)	Solidago rugosa	Late Summer	2 ounces	3
Joe Pye Weed, Spotted (P)	Eupatoriadelphus fistulosus	Late Summer	2 ounces	3
Partridge Pea (A)	Chamaecrista fasciculata	Mid-Summer	2 pounds	3
Rattlesnake Master (P)	Eryngium yuccifolium	Summer	8 ounces	3
Rosemallow (P)	Hibiscus moscheutos	Summer	2 ounces	3
Narrowleaf Sunflower (P)	Helianthus angustifolius	Late Summer	4 ounces	3
Total	—	_	4.0 lbs/acre	33

North Carolina

The proposed Coastal Plain Seed Mix P-CPDW02 (Tables 5.7.5-15 and 5.7.5-16) was designed to be compatible with the Coastal Plain Physiographic Region RU in areas with slopes of 15 percent or less and is based on selected native grass and forb species suitable for restoration in somewhat poorly to very poorly drained coastal areas in North Carolina.

		TABLE 5.7.5-1	5		
Seed Mix P-CPDW02: Recommended Coastal Plain Physiographic Region Grass Seed Mix and Application Rates for Somewhat Poorly to Very Poorly Drained Sites in North Carolina ^a					
Common Name	Scientific Name	Height (feet)	Sun Exposure	Seed Mix Rate (lbs/acre/PLS) ^b	
Switchgrass	Panicum virgatum	3 - 7	Full Sun	0.233	
Red Top Panicum	Panicum rigidulum	2 - 4	Full Sun	0.017	
Fowl Manna Grass	Glyceria striata	3 - 5	Part Shade	0.008	
Virginia Wild Rye	Elymus virginicus	2 - 4	Full Sun	0.217	
Canada Wild Rye	Elymus canadensis	2 - 5	Part Shade	0.167	
Deer Tongue Grass	Panicum clandestinum	2 - 4	Full Sun	0.058	
Big Bluestem	Andropogon gerardii	4 - 10	Full Sun	0.167	
Frank's Sedge	Carex frankii	1 - 2	Part Shade	0.042	
Fox Sedge	Carex vulpinoidea	2 - 3	Part Shade	0.025	
Fall Panicum	Panicum anceps	2 - 4	Part Shade	0.067	
Total	—	—	—	1.0	
Sources: Roundstone N	 Native Seed, 2015; Glennon, 201	5			
a Recommend	ded seeding application rate is 8	to 18 pounds per acre.			
b lbs/acre/PL	S = pounds per acre of pure live	seed			

Forb Seed Mix	Seed Mix P-CPDW02: Recomm and Application Rates for Some			North Carolina	
Common Name	Scientific Name	Color	Bloom Period	Seed Application Rat (lbs/acre/PLS) ^a	
Smooth Beardtongue	Penstemon digitalis	White	Spring	0.169	
Butterfly Milkweed	Asclepias tuberosa	Orange	Spring, Summer	0.056	
Ohio Spiderwort	Tradescantia ohiensis	Blue	Spring, Summer	0.084	
Blackeyed Susan	Rudbeckia hirta	Yellow	Spring, Summer	0.180	
Spiked Blazing Star	Liatris spicata	Pink	Summer	0.264	
Hoary Mountain Mint	Pycnanthemum incanum	White	Summer	0.034	
Early Goldenrod	Solidago juncea	Yellow	Summer	0.113	
Bergamot	Monarda fistulosa	Lavender	Summer	0.169	
Showy Tickseed	Bidens aristosa	Yellow	Summer, Fall	0.366	
Starry Silphium	Silphium asteriscus	Yellow	Summer, Fall	0.113	
Narrow-Leaved Sunflower	Helianthus angustifolius	Yellow	Summer, Fall	0.113	
Joe-Pye Weed	Eupatorium fistulosum	Pink	Summer, Fall	0.141	
Total		_	_	2.84	

5.7.6 Seeding Methods

Seeding may be conducted with the use of a seed drill, a mechanical broadcast seeder, or by hydroseeding. In the absence of requirements to the contrary, the standard application method will be seeding with a seed drill equipped with a cultipacker. In rocky soils or where site conditions may limit the effectiveness of this equipment, other alternatives may be appropriate (e.g., use of a chain drag) to lightly cover seed after application, as approved by an EI. Broadcast or hydroseeding at double the recommended seeding rates may be used in lieu of drilling (see Appendix B for recommendations).

Broadcast seeding will be used for areas with minimal to moderate slopes and will be performed by dry dispersal or wet broadcast seeding. Wet broadcast seeding is an effective treatment for temporary erosion control and may be used when hydroseeding late in the season or on certain site conditions where hydroseeding is not practical. To support successful seed germination, seed will be broadcast once soil compaction has been rectified and soil composition includes proper aeration and water percolation to support plant development. Where seed is broadcast, the seedbed will be restructured with a cultipacker or imprinter after seeding. Once seed is broadcast, Atlantic and DTI will rake the area lightly to encourage plant establishment and minimize the seed that migrates from the site (North Carolina Department of Environment and Natural Resources, 2009).

Hydroseeding involves the mixing of slurry (i.e., seed, water, fertilizer, tackifier, or mulch) in a truck-mounted mixing tank and ground application via a pressurized pump. Hydroseeding is the preferred method of seed dispersal on steep slopes greater than 60 percent, where site conditions require seed adherence to the disturbed soil. Prior to hydroseeding, Atlantic and DTI will scarify the seedbed to facilitate lodging and germination of seed. Tackifiers will be applied where necessary so that seed adheres to soil. Polymer binders, if selected, will be used in accordance with manufacturer's specifications to ensure proper compatibility with fertilizers and to avoid foaming that might otherwise result from excessive agitation. All chemical components will be mixed and administered in accordance with manufacturer and applicable agency guidelines. In addition, hydroseeding near wetlands or waterbodies will only be conducted in accordance with the FERC Plan and Procedures and other applicable agency regulations.

5.8 Seedbed Augmentation

5.8.1 Lime and Fertilizer Application

Lime and fertilizer recommendations provided by the various Federal, State/Commonwealth, local and land management and subject matter experts consulted for each County/City are provided in Appendix B. Each county crossed by the Projects may have different fertilization and liming requirements based on the soil characteristics and the proposed seed mix prescriptions. In general, and in accordance with the Plan and Procedures, upland areas will have a fertilizer and pH supplement (i.e., lime) mixed in to the upper two inches of topsoil. No lime or fertilizer will be used within 100 feet of wetlands or waterbodies or within 300 feet of karst features. In upland areas without specific fertilization requirements, Atlantic and DTI will:

- apply 150 pounds per acre of 10-20-20 (or similar) fertilizer;
- apply phosphorus or potassium during the same installation, if required;
- avoid fertilizer drift through restricted application times that exclude periods of high winds or heavy rains; and
- store and mix all fertilizers in upland areas and away from karst features, so as to avoid wetlands, waterbodies, or karst features.

5.8.2 Mulching

Mulching recommendations provided by the various Federal, State/Commonwealth, local and land management agencies, and subject matter experts consulted for each County/City are provided in Appendix B. Each County/City crossed by the Projects may have different mulching requirements based on the landscape characteristics, soil types, and the proposed seed mix prescriptions. In general, and in accordance with the Plan, Atlantic and DTI will apply mulch to slopes immediately after seeding to prevent erosion. In non-forested areas, mulch will be spread uniformly over a minimum of 75 percent of the surface at a rate of 2 tons per acre, or 1 ton per acre if wood chips are used, or per directions from land managing agencies or landowners. In forested areas, if the amount of mulch will likely exceed these parameters due to the shredding of non-merchandisable forest materials cleared from the rights-of-way, Atlantic and DTI will request a variance from FERC prior to applying mulch greater than 1 ton/acre. Mulch materials will be anchored to the soil with stakes or liquid mulch tackifiers. No tackifiers will be used within 100 feet of wetlands and waterbodies or within 300 feet of karst features.

Possible mulch materials and application techniques are described below.

• Salvaged wood materials, including slash and non-merchantable timber, will be retained in forested areas and placed on the rights-of-way after final grading, recontouring, and seeding is complete. Woody debris is expected to support revegetation while preventing erosion and providing micro-habitat for various species.

• Native wood chip materials will be used in forested systems and will be generated from cleared materials that are chipped and stockpiled on the edge of the rights-of-way. Native wood chips are expected to aid in the successful revegetation of disturbed areas.

• Wood fiber hydromulch may be used in shrubby areas to augment biomass salvaged during clearing. Hydromulch is evenly distributed and absorbs water quickly, which enhances seed survival rates and discourages erosion during regeneration of shrubby species.

• Bonded fiber matrix (BFM), a type of hydromulch designed to control erosion on steep slopes, may also be used where appropriate. BFM slurry contains thermally processed wood fibers (approximately 80 percent), water (approximately 10 percent), and tackifiers and polymer-based binding agents that are quick to dry upon application. BFM is hydraulically applied, which allows for controlled application on steep slopes where

access may be difficult. BFM will only be applied to stable slopes where final grading has been completed and water runoff has been diverted from the slope face. Once BFM has had 24 to 48 hours to cure, an erosion-resistant blanket is formed that is flexible, absorbent, and biodegradable, and that will accelerate plant growth. BFM may be used in conjunction with slope breakers and other erosion control devices on slopes longer than 70 feet. BFM application rates will depend on manufacturers specifications, based upon the slope of the disturbed areas.

• Straw or hay that has been certified as weed-free will be used to preserve the soil base in areas where native salvaged material is not available. In areas that are seeded by drill, Atlantic and DTI will apply one bale of clean straw or hay per 1,000 square feet. Where broadcast seeding is used, Atlantic and DTI will apply two bales of clean straw or hay per 1,000 square feet, or in accordance with requirements specified by Federal or State/Commonwealth land managing agencies.

5.8.3 Supplemental Plantings

Where required, Atlantic and DTI may supplement seeding with the planting of tree seedlings or small shrubs. No supplemental plantings are anticipated for maintained areas within the permanent easements for the pipelines. Public lands will be revegetated in accordance with land management objectives and direction from land managing agencies (see Sections 5.0 and 6.0).

5.9 Riparian Restoration

Following initial stream bank stabilization, Atlantic and DTI will restore the banks of waterbodies to preconstruction contours to the extent practicable. In steep-slope areas, regrading may be required to reestablish stable contours capable of supporting preconstruction drainage patterns. Riparian areas will be revegetated with native species across the entire width of the construction corridor. Restoration of riparian areas will be designed to:

- restore stream bank integrity, including both shore crossings up to the ordinary high water mark;
- withstand periods of high flow without increasing erosion and downstream sedimentation; and
- include temporary erosion control fencing, which will remain in place until stream bank and riparian restoration is complete.

Permanent bank stabilization and erosion control devices (e.g., natural structures, rock riprap, and/or large woody debris) will be installed as necessary on steep banks in accordance with permit requirements to permanently stabilize the banks and minimize sediment deposition into waterbodies.

5.9.1 Non-forested Riparian Areas

All disturbed banks and riparian work areas will be seeded as soon as possible after final grading, weather and soil conditions permitting and subject to the recommended seeding dates

for the area. Seeding is intended to stabilize the soil, improve the appearance of the area disturbed by construction, and restore native flora. As discussed above, Atlantic and DTI will determine appropriate seeding prescriptions based upon the vegetative community of the disturbed area, and will continue to consult with land managing agencies regarding seeding requirements for riparian areas.

5.9.2 Forested Riparian Areas

Restoration of forested riparian areas will include seeding as discussed above, and may include supplemental plantings of tree seedlings and shrubs. Clearing of riparian trees in forested areas will reduce shade near streams, and may allow for an increase in local water temperature. Large woody debris, where available and appropriate habitat conditions exist, will be placed adjacent to waterbody crossings to add shade and fish habitat. Forested riparian areas will be restored and enhanced using plantings of native shrubs and trees, excluding the permanent easement, which will be retained in an herbaceous state. On a site-specific basis and in consultation with land managing agencies or landowners, Atlantic and DTI will design riparian revegetation with the use of fast growing native trees and shrubs placed closest to the bank top to provide canopy recovery as quickly as possible to shade and overhang the waterbodies. Restoration of forested riparian areas on Federal and State/Commonwealth lands will be determined based upon consultations with the appropriate land managing agencies.

5.10 Wetland Restoration

Atlantic and DTI will employ clearing and construction techniques designed to support regeneration of existing wetland vegetation, including the following:

• clearing vegetation at ground level in all non-forested wetland areas outside of the trench line to leave existing root systems intact to help stabilize soils, preserve existing ground elevations, and promote revegetation through sprouting and from existing seed stocks;

• using equipment mats to prevent soil compaction and allow intact root systems to regrow;

• replacing the topsoil segregated from the trenchline in unsaturated wetlands to promote reestablishment of existing wetland species and preserving the vegetative propagules (i.e., seeds, tubers, rhizomes, and bulbs) within the soil, which will have the potential to germinate or sprout when the topsoil is replaced; and

• limiting the removal of stumps to the trench area in forested wetlands, except where safety considerations necessitate additional stump removal, as retained stumps will facilitate reestablishment of woody species by enabling re-sprouting from existing root structures.

In accordance with the Procedures, sediment barriers will be installed immediately following clearing activities occurring within wetlands or adjacent upland areas along the pipeline rights-of-way. Where necessary, sediment barriers will be installed across the

construction rights-of-way immediately upslope of the wetland boundary to prevent sediment flow into wetlands. Sediment barriers will be properly maintained throughout construction, reinstalled as necessary, and removed after restoration is complete and revegetation has stabilized the disturbed areas.

Seeding of wetlands is not anticipated as wetlands are expected to naturally revegetate. Unless specified by landowners or land managing agencies, revegetation will be monitored annually until wetland revegetation is successful in accordance with the Procedures. Wetland revegetation will be considered successful when vegetation community characteristics are similar to the vegetation in adjacent wetland areas that were not disturbed by construction. As described in the Procedures, restored wetland vegetation will include at least 80 percent of the species targeted for restoration, and the density (i.e., percent cover) and distribution (e.g., microsites and patches) of individual plants will be similar to areas not disturbed by construction. Revegetation requirements appropriate for Federal and State/Commonwealth lands will be determined through consultation with those agencies.

After revegetation, Atlantic and DTI anticipate no permanent impact on emergent wetland vegetation within the rights-of-way. Scrub-shrub and forested wetlands will not be allowed to fully reestablish within portions of the permanent rights-of-way centered over the pipeline trench lines. Atlantic and DTI will periodically remove woody species from wetlands to facilitate post-construction inspections of the permanently maintained rights-of-way. Where the pipelines cross wetlands, Atlantic and DTI will maintain a 10-foot-wide corridor centered over the pipelines in an herbaceous condition, and remove deep rooted trees within a 30-foot-wide corridor centered over the pipelines.

5.11 Agricultural Areas

Atlantic and DTI will work with individual landowners to address restoration of active agricultural areas. Generally, agricultural areas will be replanted by the landowner or tenant, unless otherwise requested by the landowner. Anticipated impacts on and restoration of irrigation systems, drain tiles, gates, and other structures are discussed in Resource Report 8.

5.12 Exposed Bedrock

In areas with exposed bedrock or bedrock, Atlantic and DTI will restore the area using crushed rock rather than attempting to revegetate the area.

5.13 Upland Forest

Atlantic and DTI have prepared and will implement a *Timber Removal Plan*, which describes construction and restoration activities in areas where timber is removed. The plan also addresses compensation for loss of merchantable timber as well as elements of timber removal/sale that are unique to public lands. Elements of the plan include:

• completion of a timber cruise to appraise the value of merchantable timber;

- installation of flagging/fencing of timber removal limits, riparian areas, and other exclusion zones prior to timber removal operations;
- identification of access and staging requirements for timber removal, including log landing locations, temporary bridges at waterbody crossings, etc.; and
- identification of timber removal methods (e.g., high line yarder logging, mechanical harvesting, helicopter logging).

Following construction in forested areas, seed mixes and/or seedlings will be planted in temporary workspace areas in accordance with recommendations from the NRCS, land managing or other applicable agencies, and operators of commercial tree farms. In non-cultivated uplands, including forested areas, the permanent easement for each pipeline will be maintained in an herbaceous state.

6.0 FEDERAL LANDS

The AP-1 mainline will cross approximately 5.5 miles of Federal lands in the Monongahela National Forest and approximately 14.5 miles of Federal lands in the George Washington National Forest, which are administered by the USFS. As described in Atlantic's and DTI's Resource Reports, Federal lands are managed in accordance with various management directives, including standards and guidelines for restoration and revegetation activities. Restoration activities on Federal lands will be in accordance with these standards and guidelines. Additional or site-specific requirements for restoration of Federal lands will be addressed in a Construction, Operations, and Maintenance Plan to be developed in conjunction with USFS staff.

Consultation with USFS staff regarding seed mixes, soil amendments, and application rates, including appropriate cultural practices recommended by USFS staff to be used in the Monongahela National and George Washington National Forest is ongoing. This information will be provided in Appendix B when consultation is complete.

In addition to USFS lands, the AP-1 mainline will also cross approximately 0.1 mile of National Park Service lands along the Blue Ridge Parkway. Atlantic is proposing the use of the horizontal directional drill construction method to install the proposed pipeline under the Blue Ridge Parkway at this location. The horizontal directional drill method will avoid direct impacts on the parkway, including impacts on adjacent vegetation.

7.0 STATE LANDS

In West Virginia, the AP-1 mainline crosses 3.8 miles of the Seneca State Forest in Pocahontas County, West Virginia, and the SHP crosses approximately 3.6 miles of the Lewis Wetzel WMA in Wetzel County, West Virginia. Seneca State Forest is managed by the WV Division of Forestry and the Lewis Wetzel WMA is managed by the West Virginia Department of Natural Resources. The AP-1 mainline crosses 1.2 miles of the James River WMA in Nelson County, Virginia, which is managed by the Virginia Department of Game and Inland Fisheries.

The seed mixes, soils amendments, and application rates, including appropriate cultural practices recommended by the State/Commonwealth staff, for the Lewis Wetzel WMA and

James River WMA are provided in Appendix B. In Virginia, the DGIF has indicated that it may want to be responsible for replanting the rights-of-way on its lands. Consultation with the WV Division of Forestry regarding seed mixes, soil amendments, and application rates is ongoing. This information will be provided in Appendix B when consultation is complete.

8.0 RESTORATION MONITORING AND MAINTENANCE

8.1 Monitoring

The general objectives of the monitoring program will be to determine the status and effectiveness of restoration efforts and to determine locations where additional maintenance may be required. Atlantic and DTI will inspect disturbed areas after the first and second growing seasons to determine the success of revegetation. In agricultural areas, revegetation will be considered successful when the area has been revegetated and is similar to adjacent undisturbed areas of the same field. In all other non-forested areas, revegetation will be considered successful when the density and cover of non-nuisance vegetation is similar to adjacent areas that were not disturbed by construction activities. In Federal and State/Commonwealth forested areas, monitoring activities will be performed until reforestation is determined successful based on pre-defined success criteria, as determined through consultations with Federal and State/Commonwealth land managing agencies.

Atlantic and DTI will continue revegetation efforts until they are successful. Restoration will be considered successful when construction debris is removed, similar vegetative cover or bedrock has been restored, the original surface elevations are restored as closely as practicable to preconstruction contours, the surface condition is similar to adjacent non-disturbed areas, and proper drainage is restored.

8.2 Grazing Deferments

Where warranted, Atlantic and DTI will work with landowners or lessees to implement grazing deferment plans (e.g., by fencing off restoration sites) to minimize impacts on emergent vegetation due to grazing.

8.3 Permanent Rights-of-way Maintenance

In order to maintain accessibility of the rights-of-way and to accommodate pipeline integrity surveys, vegetation within the permanent easements will be periodically cleared over the pipelines. In accordance with the Plan, in non-cultivated uplands, a 10-foot-wide herbaceous corridor may be maintained annually, as needed. In addition, trees and brush will be cleared over the entire width of the permanent rights-of-way on an as-needed basis not to exceed once every 3 years. In wetlands and riparian areas, the Procedures allow a 10-foot-wide corridor centered over pipelines to be permanently maintained in an herbaceous state. The Procedures also allow for cutting and removing trees greater than 15 feet in height within 15 feet of pipelines in wetlands.

Atlantic and DTI will use mechanical mowing or cutting along their rights-of-way for normal vegetative maintenance. Atlantic and DTI will monitor the rights-of-way for infestations of invasive species that may have been created or exacerbated by construction, restoration, or

maintenance activities, and will treat such infestations in consultation with landowners and applicable agencies in accordance with its *Invasive Species Management Plan*.

9.0 ROLES AND RESPONSIBILITIES

9.1 Environmental Inspectors

Els will have the authority to stop activities that violate environmental conditions of Federal or State/Commonwealth environmental permits and landowner agreements and to order appropriate corrective action. During revegetation and restoration, the Els will be responsible for:

• ensuring compliance with the requirements of the Plan and Procedures; Atlantic's and DTI's construction, restoration, and mitigation plans; conditions required by permits and other approvals; this Restoration and Rehabilitation Plan; and environmental requirements identified in landowner easement agreements;

• identifying, documenting, and overseeing corrective actions, as necessary, to bring an activity back into compliance;

• verifying that the limits of authorized construction work areas and locations of access roads are visibly marked before clearing;

• verifying the location of restoration sites, and maintaining appropriate signage for boundaries of sensitive resource areas, waterbodies, wetlands, farm improvements (i.e., repair of fences, drain tiles, irrigation systems, or structures), or areas with special restoration requirements;

• monitoring erosion and sediment control devices and soil stabilization measures in construction areas, and identifying additional needs for new controls or maintenance of existing controls;

• verifying that dewatering activities are properly monitored and do not result in the deposition of sand, silt, and/or sediment into sensitive environmental resource areas, including but not limited to wetlands, waterbodies, cultural resource sites, and sensitive species habitats;

• ensuring that subsoil and topsoil are tested in agricultural and residential areas to measure compaction and determine the need for corrective action;

• advising the Construction Inspector when environmental conditions (such as wet or frozen soils) make it advisable to restrict or delay construction activities to avoid topsoil mixing or excessive compaction;

• ensuring restoration of contours and topsoil;

• verifying that soils imported for agricultural or residential use have been certified as free of invasive species and soil pests, unless otherwise approved by the landowner;

• determining the need for and ensuring that erosion controls are properly installed, as necessary, to prevent sediment flow into wetlands, waterbodies, sensitive areas, and onto roads;

• inspecting and ensuring the maintenance of temporary erosion control measures at least:

- o on a daily basis in areas of active construction or equipment operation;
- on a weekly basis in areas with no construction or equipment operation; and
- within 24 hours of each 0.5 inch of rainfall.

• ensuring the repair of all ineffective temporary erosion control measures within 24 hours of identification;

• keeping records of compliance or non-compliance with conditions of environmental regulatory permits and approvals, including activities that could result in decertification of organic farms; and

• identifying areas that will require special attention to ensure stabilization and restoration success.

Where appropriate for local resource needs, the role of EIs may be filled by agricultural or horticultural specialists.

9.2 Documentation

In accordance with the Plan, Atlantic and DTI will maintain post-construction records of activities performed and will submit quarterly activity reports to the FERC. Reports will document any issues that arise during revegetation, including those identified by the landowner or land managing agency, and corrective actions taken for at least two years following construction. Reports will identify by milepost:

• method of application, application rate, and type of fertilizer, pH modifier, seed, and mulch used;

- acreage treated;
- dates of backfilling and seeding;

• names of landowners requesting special seeding treatment and a description of the follow-up actions;

• the location of subsurface drainage repairs or improvements made during restoration; and

• problem areas, such areas where vegetation did not establish or erosion occurred, and how they were addressed.

10.0 REFERENCES

- Federal Energy Regulatory Commission. 2013a. Upland Erosion Control, Revegetation, and Maintenance Plan. Available online at <u>http://www.ferc.gov/industries/gas/enviro/</u><u>plan.pdf</u>.
- Federal Energy Regulatory Commission. 2013b. Wetland and Waterbody Construction and Mitigation Procedures. Available online at <u>http://www.ferc.gov/industries/gas/enviro/</u> <u>procedures.pdf</u>.
- Glennon, Robert. 2015. Personal communication with Herbert Pirela of Environmental Resources Management, Inc. Private Lands Biologist.
- North Carolina Department of Environment and Natural Resources. 2009. North Carolina Erosion and Sediment Control Planning and Design Manual. Available online at <u>http://portal.ncdenr.org/web/lr/576</u>. Accessed June 2015.
- Roundstone Native Seed. 2015. Jeremy Hamlington, personal communication with Herbert Pirela of Environmental Resources Management, Inc. Horticulturist.
- Virginia Department of Environmental Quality. 1992. Virginia Erosion and Sediment Control Handbook. Available online at <u>http://www.deq.virginia.gov/Programs/Water/</u> <u>StormwaterManagement/Publications/ESCHandbook.aspx</u>. Accessed June 2015
- West Virginia Department of Environmental Protection, Office of Oil and Gas. 2012. West Virginia Erosion and Sediment Control Field Manual. Available online at http://www.dep.wv.gov/oil-and-gas/Documents/Erosion%20Manual%2004.pdf. Accessed June 2015.

ATLANTIC COAST PIPELINE, LLC ATLANTIC COAST PIPELINE

and

DOMINION TRANSMISSION, INC. SUPPLY HEADER PROJECT

Restoration and Rehabilitation Plan

Appendix A Major Soil Drainage and Slope Classes Crossed by the Projects

TABLE 5.6-1 Atlantic Coast Pipeline and Supply Header Project Major Soil Drainage and Slope Classes Crossed by the Projects				
Commonwealth/County	Drainage Class ^a	Total	0-15% ^b	>16% ^b
ATLANTIC COASTAL F	PIPELINE			
West Virginia				
Harrison	Excessively to Moderately Well Drained	1.0	0.2	0.8
	Somewhat Poorly to Very Poorly Drained	0.1	<0.1	< 0.1
	Total	1.1	0.3	0.8
Lewis	Excessively to Moderately Well Drained	19.8	6.9	12.9
	Null ^{b/}	0.1	<0.1	0.1
	Total	19.9	6.9	13.0
Upshur	Excessively to Moderately Well Drained	21.5	8.8	12.7
	Somewhat Poorly to Very Poorly Drained	0.6	0.6	< 0.1
	Null	0.1	0.1	< 0.1
	Total	22.2	9.5	12.7
Randolph	Excessively to Moderately Well Drained	28.6	12.3	16.3
	Somewhat Poorly to Very Poorly Drained	0.3	0.3	0.00
	Null	1.9	1.4	0.5
	Total	30.8	14.0	16.8
Pocahontas	Excessively to Moderately Well Drained	23.4	8.4	15.0
	Somewhat Poorly to Very Poorly Drained	0.8	0.8	< 0.1
	Null	< 0.1	<0.1	0.00
	Total	24.3	9.3	15.0
Virginia				
Highland	Excessively to Moderately Well Drained	10.5	3.0	7.5
	Somewhat Poorly to Very Poorly Drained	0.1	0.1	0.0
	Null	< 0.1	< 0.1	0.0
	Total	10.6	3.1	7.5
Bath	Excessively to Moderately Well Drained	20.4	9.6	10.8
	Somewhat Poorly to Very Poorly Drained	1.2	1.2	0.00
	Null	< 0.1	< 0.1	< 0.1
	Total	21.6	10.8	10.8
Augusta	Excessively to Moderately Well Drained	50.4	35.5	14.9
	Somewhat Poorly to Very Poorly Drained	1.9	1.9	< 0.1
	Null	2.0	1.1	0.9
	Total	54.3	38.5	15.8
Nelson	Excessively to Moderately Well Drained	26.9	10.3	16.7
	Somewhat Poorly to Very Poorly Drained	0.3	0.3	< 0.1
	Null	< 0.1	<0.1	0.0
	Total	27.3	10.6	16.7
Buckingham	Excessively to Moderately Well Drained	22.8	20.0	2.7
	Somewhat Poorly to Very Poorly Drained	4.9	4.6	0.3
	Null	< 0.1	< 0.1	0.0
	Total	27.7	24.7	3.0
Cumberland	Excessively to Moderately Well Drained	8.5	7.8	0.7
	Somewhat Poorly to Very Poorly Drained	0.5	0.5	0.0
	Null	< 0.1	<0.1	0.0
	Total	9.1	8.4	0.7

TABLE 5.6-1 (continued) Atlantic Coast Pipeline and Supply Header Project				
Major Soil Drainage and Slope Classes Crossed by the Projects				
Project /State or			Crossing Length (m	
Commonwealth/County	Drainage Class ^a	Total	0-15% ^b	>16% ^b
Prince Edward	Excessively to Moderately Well Drained	5.0	4.1	0.9
	Somewhat Poorly to Very Poorly Drained	0.2	0.2	<0.1
	Null	<0.1	<0.1	0.0
	Total	5.2	4.3	0.9
Nottoway	Excessively to Moderately Well Drained	21.1	19.1	2.0
	Somewhat Poorly to Very Poorly Drained	2.3	2.2	0.1
	Null	<0.1	<0.1	0.0
	Total	23.4	21.3	2.1
Dinwiddie	Excessively to Moderately Well Drained	11.0	10.9	0.1
	Somewhat Poorly to Very Poorly Drained	0.8	0.8	0.0
	Total	11.8	11.7	0.1
Brunswick	Excessively to Moderately Well Drained	21.4	21.2	0.2
	Somewhat Poorly to Very Poorly Drained	1.6	1.6	< 0.1
	Total	23.0	22.8	0.2
Greensville	Excessively to Moderately Well Drained	11.4	11.1	0.3
	Somewhat Poorly to Very Poorly Drained	7.1	7.1	0.0
	Null	0.1	0.1	0.0
	Total	18.6	18.3	0.3
Southampton	Excessively to Moderately Well Drained	16.1	16.0	< 0.1
	Somewhat Poorly to Very Poorly Drained	10.0	10.0	0.0
	Null	< 0.1	<0.1	0.0
	Total	26.1	26.1	< 0.1
City of Suffolk	Excessively to Moderately Well Drained	16.2	15.8	0.4
	Somewhat Poorly to Very Poorly Drained	16.4	16.3	0.1
	Null	0.6	0.6	0.0
	Total	33.2	32.7	0.5
City of Chesapeake	Excessively to Moderately Well Drained	0.6	0.6	0.0
	Somewhat Poorly to Very Poorly Drained	9.0	9.0	0.0
	Null	1.7	1.7	0.0
	Total	11.3	11.3	0.0
lorth Carolina				
Northampton	Excessively to Moderately Well Drained	17.8	17.6	0.2
	Somewhat Poorly to Very Poorly Drained	4.2	4.2	< 0.1
	Null	0.1	0.1	0.0
	Total	22.1	21.9	0.2
Halifax	Excessively to Moderately Well Drained	16.8	16.6	0.2
	Somewhat Poorly to Very Poorly Drained	7.5	7.5	< 0.1
	Null	0.0	0.0	0.0
	Total	24.3	24.1	0.2
Nash	Excessively to Moderately Well Drained	20.1	19.9	0.2
	Somewhat Poorly to Very Poorly Drained	11.8	11.8	0.0
	Null	<0.1	<0.1	0.0
	Total	31.9	31.7	0.2
Wilson	Excessively to Moderately Well Drained	6.5	6.5	0.0
··· •	Somewhat Poorly to Very Poorly Drained	5.4	5.4	<0.1
	Total	11.9	11.9	<0.1

roject /State or			Crossing Length (mi	iles)
Commonwealth/County	Drainage Class ^a	Total	0-15% ^b	>16% ^b
Johnston	Excessively to Moderately Well Drained	19.0	19.0	< 0.1
	Somewhat Poorly to Very Poorly Drained	19.1	19.1	0.0
	Null	< 0.1	< 0.1	0.0
	Total	38.1	38.1	< 0.1
Sampson	Excessively to Moderately Well Drained	4.7	4.7	0.0
	Somewhat Poorly to Very Poorly Drained	3.1	3.1	0.0
	Total	7.8	7.8	0.0
Cumberland	Excessively to Moderately Well Drained	16.8	16.7	0.1
	Somewhat Poorly to Very Poorly Drained	22.7	22.7	0.0
	Null	0.1	0.1	0.0
	Total	39.6	39.5	0.1
Robeson	Excessively to Moderately Well Drained	9.4	9.4	0.0
	Somewhat Poorly to Very Poorly Drained	13.1	13.1	0.0
	Total	22.5	22.5	0.0
TOTAI	L	599.7	482.1	117.6
UPPLY HEADER PROJ	IECT			
ennsylvania				
Westmoreland	Excessively to Moderately Well Drained	3.8	2.2	1.6
	Somewhat Poorly to Very Poorly Drained	0.1	0.1	0.0
	Total	3.9	2.3	1.6
Vest Virginia				
Harrison	Excessively to Moderately Well Drained	0.3	0.2	0.1
	Somewhat Poorly to Very Poorly Drained	0.3	0.1	0.2
	Total	0.6	0.3	0.3
Doddridge	Excessively to Moderately Well Drained	22.1	4.2	17.9
-	Null	0.1	0.1	< 0.1
	Total	22.2	4.3	17.9
Tyler	Excessively to Moderately Well Drained	0.8	0.1	0.7
	Total	0.8	0.1	0.7
Wetzel	Excessively to Moderately Well Drained	10.0	1.2	8.8
	Total	10.0	1.2	8.8
OTAL		37.5	8.2	29.3
		637.2	490.3	146.9

TABLE 5.6-1 (continued)

ATLANTIC COAST PIPELINE, LLC ATLANTIC COAST PIPELINE

and

DOMINION TRANSMISSION, INC. SUPPLY HEADER PROJECT

Restoration and Rehabilitation Plan

Appendix B Recommended Seed Mix Prescriptions and Soil Amendments



ATLANTIC COAST PIPELINE, LLC ATLANTIC COAST PIPELINE Docket Nos. CP15-554-000 & CP15-554-001

and



DOMINION TRANSMISSION, INC. SUPPLY HEADER PROJECT Docket No. CP15-555-000

Recommended Seed Mixes by Milepost

Updated, Rev 3

Prepared by



July 15, 2016

TABLE OF CONTENTS

1.0	INTE	RODUC	TION	1
2.0	ATL	ANTIC	COAST PIPELINE	1
	2.1	WEST	「VIRGINIA	1
		2.1.1	Harrison, Lewis, Randolph, and Upshur Counties	1
		2.1.2	Pocahontas County	
		2.1.3	Federal Lands	4
		2.1.4	State Lands	5
		2.1.5	Recommended Native Grasses and Pollinators Seed Mixtures, Applic	cation
			Rates, and Non-Native Cover Crop by Physiographical Region	5
	2.2	VIRG	INIA	8
		2.2.1	Augusta, Brunswick, Buckingham, Cumberland, Highland, Bath, Nel	lson,
			Nottoway, and Prince Edward Counties	
		2.2.2	Federal Lands	16
		2.2.3	State Lands	16
		2.2.4	Dinwiddie, Greensville, and Southampton Counties, and Chesapeake	and
			Suffolk Cities (Coastal Plain Region)	18
	2.3	NORT	TH CAROLINA	21
		2.3.1	Northampton County	21
		2.3.2	Halifax and Wilson Counties	22
		2.3.3	Nash and Johnston Counties	23
		2.3.4	Sampson County	24
		2.3.5	Cumberland County	26
		2.3.6	Robeson County	27
		2.3.7	Recommended Native Grass and Pollinator Seed Mixtures, Applicati	on
			Rates, and Non-Native Cover Crop by Physiographical Region (Coas	stal
			Plain)	28
3.0	SUPI	PLY HE	ADER PROJECT	31
	3.1	WEST	Γ VIRGINIA	31
		3.1.1	Wetzel and Tyler Counties	31
		3.1.2	State Lands	32
		3.1.3	Doddridge and Harrison Counties	33
		3.1.4	Recommended Native Grasses and Pollinators Seed Mixtures, Applic	cation
			Rates, and Non-Native Cover Crop by Physiographical Region	35
	3.2	PENN	ISYLVANIA	35
		3.2.1	Westmoreland County	35
4.0	REF	ERENC	ES	37

LIST OF TABLES

Table 2.1.1-1	Seed Mix WVHLRU01 Recommended Cool Season Seed Mixture
Table 2.1.1-2	Harrison, Lewis, Randolph, and Upshur Counties, West Virginia
	Recommended Seeding Dates for Permanent Cover
Table 2.1.1-3	Harrison, Lewis, Randolph, and Upshur Counties, West Virginia
	Recommended Lime and Fertilizer Application
Table 2.1.2-1	Seed Mix WVPO01: Cool or Warm Season Seed Mixture
Table 2.1.2-2	Recommended Lime and Fertilizer Application
Table 2.1.2-3	Recommended Mulch Material Rates and Uses
Table 2.1.5-1	Seed Mix P-MUDW01: Recommended Mountain Physiographic Region
	Grass Seed Mix and Application Rates for Excessively to Moderately Well
	Drained Sites in West Virginia
Table 2.1.5-2	Seed Mix P-MUDW01:Recommended Mountain Physiographic Region Forb
	Seed Mix and Application Rates for Excessively to Moderately Well Drained
	Sites in West Virginia
Table 2.1.5-3	Seed Mix P-MUMP02: Recommended Mountain Physiographic Region Grass
14010 2010 0	Seed Mix and Application Rate for Somewhat Poorly to Very Poorly Drained
	Sites in West Virginia
Table 2.1.5-4	Seed Mix P-MUMP02: Recommended Mountain Physiographic Region Forb
14010 20100	Seed Mix Application Rate for Somewhat Poorly to Very Poorly Drained
	Sites in West Virginia
Table 2.1.5-5	Seed Mix P-NNTC: Recommended Mountain Physiographic Region Non-
14010 21110 0	Native Temporary Cover Crop Species for Steep Slope Areas in West
	Virginia
Table 2.1.5-6	Seed Mix P-NNGC: Recommended Mountain Physiographic Region Non-
14010 2.110 0	Native Grass Cover Mix for Steep Slope Areas in West Virginia
Table 2.2.1-1	Seed Mix VABCHNP01:Recommended Cool Season Erosion Prevention
14010 2.2.1 1	Species and Seed Mixtures
Table 2.2.1-2	Seed Mix VABCHNP02: Recommended Cool and Warm Season Forage
14010 2.2.1 2	Species and Seed Mixtures
Table 2.2.1-3	Recommended Soil Amendments
Table 2.2.1-4	Mulch Specifications
Table 2.2.1-5	Mulch Considerations
Table 2.2.1-6	Seed Mix P-VABCHNP01: Recommended Mountain Physiographic Region
10010 2.2.1 0	Grass Seed Mix and Application Rates for Excessively to Moderately Well
	Drained Sites in Virginia
Table 2.2.1-7	Seed Mix P-VABCHNP01: Recommended Mountain Physiographic Region
10010 2.2.1 7	Forb Seed Mix and Application Rates for Excessively to Moderately
	Well/Well Drained Sites in Virginia
Table 2.2.1-8	Seed Mix P-VABCHNP02: Native Grasses and Forbs for Somewhat Poorly to
10010 2.2.1 0	Very Poorly Drained Soils and have a High Pollinator Value
Table 2.2.1-9	Seed Mix VJRWMA01: Recommended Grass Seed Mix and Application
1 auto 2.2.1-7	Rates for Excessively to Moderately Well Drained – Partially Shade Sites 17
Table 2.2.1-10	Seed Mix VJRWMA02: Recommended Grass Seed Mix and Application
1 abic 2.2.1-10	Rates for Excessively to Moderately Well Drained – Wildlife Site
	Rates for Excessively to inductately well Dialited – whulle site

Table 2.2.1-11	Seed Mix VJRWMA03: Recommended Grass Seed Mixes and Application
	Rates for Steep Slopes Stabilization
Table 2.2.4-1	Seed Mix VACSDGS01: Recommended Cool and Warm Season Species,
	Cultivars, Seeding Rates, Seeding Dates, and Temporary Cover
Table 2.2.4-2	Seed Mix P-VACSDGS01: Perennial Grass and Forb Mixture for Excessively
	to Moderately Well Drained Soils that Meets NRCS Pollinator Mix
	Requirements – Higher Pollinator Value (7 of 9 High Value) DRILLED 20
Table 2.2.4-3	Seed Mix P-VACSDGS02: Native Grasses and Forbs for Somewhat Poorly to
	Very Poorly Drained Soils and have a High Pollinator Value - Higher
	Pollinator Value (8 of 9 High Value)
Table 2.3.1-1	Seed Mix NCNO01: Recommended Cool Season Seed Mixture
Table 2.3.1-2	Seed Mix NCNO02: Recommended Warm Season Seed Mixture
Table 2.3.1-3	Recommended Soil Amendments
Table 2.3.2-1	Seed Mix NCHW01:Recommended Cool Season Seed Mixture
Table 2.3.3-1	Seed Mix NCNJ01: Recommended Cool Season Grass Seed Mixture
Table 2.3.3-2	Recommended Lime and Fertilizer Application
Table 2.3.4-1	Seed Mix NCSA01: Recommended Cool Season Seed Mixture
Table 2.3.4-2	Seed Mix NCSA02: Recommended Warm Season Seed Mixture
Table 2.3.4-3	Recommended Lime and Fertilizer Application
Table 2.3.5-1	Seed Mix NCCU01: Recommended Cool and Warm Season Seed Mixture . 26
Table 2.3.5-2	Recommended Lime and Fertilizer Application
Table 2.3.5-3	Recommended Mulch Material Rates and Uses
Table 2.3.6-1	Seed Mix NCRO01: Recommended Warm Season Seed Mixture
Table 2.3.6-2	Seed Mix P-NCRO01:Recommended Pollinator Seed Mixture
Table 2.3.7-1	Seed Mix P-CPDW01:Recommended Coastal Plain Physiographic Region
	Grass Seed Mix and Application Rates for Excessively to Moderately Well
	Drained Sites in North Carolina
Table 2.3.7-2	Seed Mix P-CPDW01:Recommended Coastal Plain Physiographic Region
	Forb Seed Mix and Application Rates for Excessively to Moderately Well
	Drained Sites in North Carolina
Table 2.3.7-3	Seed Mix P-CPDW02: Recommended Coastal Plain Physiographic Region
	Grass Seed Mix and Application Rates for Somewhat Poorly to Very Poorly
	Drained Sites in North Carolina
Table 2.3.7-4	Seed Mix P-CPDW02: Recommended Coastal Plain Physiographic Region
	Forb Seed Mix and Application Rates for Somewhat Poorly to Very Poorly
	Drained Sites in North Carolina
Table 2.3.7-5	Seed Mix P-NNTC: Recommended Non-native Temporary Cover Crop
	Species
Table 2.3.7-6	Seed Mix P-NNGC: Recommended Non-native Grass Cover Mix
Table 3.1.1-1	Seed Mix WVWE01: Recommended Cool Season Seed Mixture
Table 3.1.1-2	Recommended Seeding Dates for Permanent Cover
Table 3.1.1-3	Recommended Lime and Fertilizer Application for Permanent Seeding 32
Table 3.1.1-4	Recommended Lime and Fertilizer Application for Temporary Seeding
	(Absent of a Soil Test)
Table 3.1.2-1	Seed Mix WVLWWMA01: Recommended Grass Seed Mixes and
	Application Rate

Table 3.1.2-2	Recommended Lime and Fertilizer Application	33
Table 3.1.3-1	Seed Mix WVDH01: Recommended Cool Season Seed Mixtures	34
Table 3.1.3-2	Recommended Seeding Dates for Permanent Cover	34
Table 3.1.3-3	Recommended Lime and Fertilizer Application	34
Table 3.2.1-1	Seed Mix PAWE01: Recommended Cool Season Seed Mixture	35
Table 3.2.1-2	Soil Amendment Application Rate Equivalents	
Table 3.2.1-3	Recommended Mulch Type and Rates	

LIST OF ATTACHMENTS

Attachment A Summary of Seed Mixes by County for the Atlantic Coast Pipeline and Supply Header Project

LIST OF ACRONYMS AND ABBREVIATIONS

ACPAtlantic Coast PipelineNRCSNatural Resources Conservation ServiceSHPSupply Header ProjectWMAWildlife Management Area

ATLANTIC COAST PIPELINE – Docket Nos. CP15-554-000 & CP15-554-001 SUPPLY HEADER PROJECT – Docket No. CP15-555-000

1.0 INTRODUCTION

This appendix compiles seed mix prescriptions and soil amendment recommendations provided by Federal and State/Commonwealth agencies, and subject matter experts consulted for the restoration and rehabilitation of the proposed Atlantic Coast Pipeline (ACP) and Supply Header Project (SHP). The recommendations are summarized by county in Attachment A and discussed below.

2.0 ATLANTIC COAST PIPELINE

2.1 WEST VIRGINIA

2.1.1 Harrison, Lewis, Randolph, and Upshur Counties

The following seed mixtures and application rates, seeding dates, soil amendments recommendations, and planting recommendations are for Harrison, Lewis, Randolph, and Upshur counties in West Virginia. These recommendations are based on the collection of correspondences and discussions with Federal and State agencies, including communication with Greg Stone (Natural Resources Conservation Service [NRCS] Acting State Resource Conservationist) and Jeff Griffith (NRCS Conservationist). The tables and lists below provide the specific recommendations for these counties. No specific recommendations were made in these counties regarding tackifiers, mulching, or anchoring of mulch or seed.

Seed Mix WVHLRU01: Recommended Cool Season Seed Mixture				
Seed Mixture	Potentially Suitable Land Use	Common Species Name ^a	Seed Application Rate (lbs/acre/PLS)	
1	Pasture or Hay	Orchardgrass	10	
		Ladino Clover	2	
		Red Clover	3	
		Redtop	3	
2	Pasture	Kentucky Bluegrass	20	
		Ladino Clover	2	
		Red Clover	3	
		Redtop	3	
3	Pasture or Hay	Orchardgrass	20	
		Redtop	5	
		Birdsfoot Trefoil	10	

Recommended Seed Mixes and Application Rates

Recommended Seeding Dates

TABLE 2.1.1-2			
Harrison, Lewis, Randolph, and Upshur Counties, West Virginia Recommended Seeding Dates for Permanent Cover			
Seeding Dates	Suitability		
March 1 to April 15	Best seeding period		
August 1 to October 1	Best seeding period		
December 1 to March 1	Good seeding period (dormant seeding)		
April 15 to August 1	High risk (moisture stress likely)		
October 1 to December 1	High risk (potential freeze damage to young seedlings)		

Recommended Soil Amendments and Application Rates

	TABLE 2.1.1-3
Harrison, Lewis, Randolph, and Upsh	ur Counties, West Virginia Recommended Soil Amendments and Application Rates
Soil Amendment Type	Application Rate
Lime	3 tons per acre
Fertilizer ^a	400 pounds per acre

Planting Recommendations

- Certified seed is preferred.
- Use proper inoculants prior to seeding for all legumes.
- Amend soil fertility and pH levels to satisfy the needs of the plant species.
- For unprepared seedbeds or seeding outside the optimum timeframes:
 - Add 50 percent more seed to the specified application rate, particularly during the periods of April 15 August 1, and October 1 March 1.
 - Double the seed application rate and consider planting an annual small grain like wheat (2 bushels [120 pounds] per acre) to act as a nurse crop.

2.1.2 **Pocahontas County**

The following seed mixtures, application rates, and soil amendment recommendations are for Pocahontas County, West Virginia. The recommendations are based on correspondence and discussions with Iden Gunther (NRCS Conservationist) and Susan Davis (West Virginia Department of Natural Resources). Seed Mix WVPO01 provides seeding recommendations for disturbed areas from the NRCS Critical Area Planting Standard that is commonly used with a high success rate in the County.

		TABLE 2.1.2-1		
Seed Mix WVPO01: Recommended Cool or Warm Seed Mixes for Pocahontas County, West Virginia				
		Seeding Application Rate		
Seed Mixture	Species / Mixture ^a	(lbs/acre/PLS) ^b	Soil Drainage Preference	pH Range
1	Crownvetch	10 - 15	Well – Moderately Well	5.0 - 7.5
	Perennial Ryegrass	20		
2	KY Bluegrass	20	Well – Moderately Well	5.5 - 7.5
	Redtop	3		
	Ladino Clover or	2		
	Birdsfoot Trefoil	10		
3	Timothy	8	Well - Poorly	5.5 - 7.5
	Birdsfoot Trefoil	8		
4	Orchardgrass	10	Well – Moderately Well	5.5 - 7.5
	Ladino Clover	2		
	Redtop	3		
5	Orchardgrass	10	Well – Moderately Well	5.5 - 7.5
	Ladino Clover	2		
5	Birdsfoot Trefoil	10	Well – Moderately Well	5.5 - 7.5
	Redtop	5		
	Orchardgrass	20		
Source: WVDEP, 2				
Species	in bold are more wildlife-friend		ble for use in filter strips.	
Ibs/acre/	PLS = pounds per acre of pure l	ive seed		

Recommended Seed Mixes and Application Rates

Recommended Soil Amendments and Application Rates

TABLE 2.1.2-2				
	Recommended Lime and Fertilizer	Application		
pH of Soil ^a	Lime Application Rate (tons/acre) ^b	Fertilizer Application Rate (10-20-20 or equivalent) (lbs/acre)		
> 6.0	2	500		
5.0 to 6.0	3			
< 5.0	4			
Source: WVDEP, 2012				
	rmined with a portable pH testing kit or by sending the lied it must be incorporated into the soil by disking, ba	e soil samples to a soil testing laboratory. When four tons of ackblading, or tracking up and down the slope.		
^b lbs/acre/PLS = pou	nds per acre of pure live seed			

TABLE 2.1.2-3							
	Recommended Mulch Ma	aterial Rates and Uses					
Material	Minimum Rates Per Acre	Coverage	Remarks				
Hay or Straw	2-3 Tons (100 – 150 Bales)	75% - 90%	Subject to wind blowing or washing unless tied down				
Wood Fiber, Pulp Fiber, Wood- Cellulose, Recirculated Paper	1,000 – 1,500 lbs	Cover all disturbed areas	Hydroseeding				
Source: WVDEP, 2012							

Recommended Mulch Material and Application Rates

Chemical Mulches, Soil Binders, and Tackifiers Recommendations

- Determine mulch-type and its appropriate application rate;
- A wide range of synthetic tackifiers (e.g., spray-on materials) are marketed to stabilize and protect the seeds and soil surfaces. These tackifiers are mixed with water and seed mixtures, and sprayed over the mulch and soils. They may be used alone in some cases as temporary stabilizers, or in conjunction with fiber mulch, straw or hay; and
- Chemical tackifiers, when used alone, do not have the capability to insulate the soil or retain soil moisture as effectively as organic mulches such wood fiber, straw, or hay.

Mulch Anchoring

- Depending on field conditions, mulch anchoring (e.g., mechanical methods or netting) may become necessary due to environmental conditions, including heavy winds or rapid water runoff (e.g., rain or snowmelt).
- Mechanical Anchoring
 - Apply mulch and pull a mulch anchoring tool over the mulch. When a disk is used, set the disk straight and pull across the slope. Mulch material should be tucked into the soil about three inches.
- Mulch Netting
 - Follow manufacturer's recommendations when positioning and stapling mulch netting into the soil.

2.1.3 Federal Lands

Monongahela National Forest – Pocahontas County

This section is pending additional consultation with the U.S. Forest Service.

2.1.4 State Lands

Seneca State Forest – Pocahontas County

This section is pending additional consultation with the West Virginia Department of Natural Resources.

2.1.5 Recommended Native Grasses and Pollinators Seed Mixtures, Application Rates, and Non-Native Cover Crop by Physiographical Region

Recommended Seed Mixtures by Geographical Region (Mountain Physiographic Region) and Drainage Class

The following seed mixtures are for the mountain and upland areas of West Virginia. These recommendations are based on discussions with Roundstone Native Seed and Robert Glennon, private lands biologist from the Conservation Management Institute, Virginia Tech and NRCS, and the Xerces Society.

TABLE 2.1.5-1								
Cross	Seed Mix P-MUDW01: 1 Geed Mix and Application Rates for		• 0	0				
Common Name	Scientific Name	Height (feet)	Sun Exposure	Seed Mix Rate (lbs/acre/PLS) ^b				
Little Bluestem	Schizachyrium scoparium	2 - 4	Full Sun	0.250				
Virginia Wild Rye	Elymus virginicus	2 - 4	Full Sun	0.250				
Tall Dropseed	Sporobolus compositus	2 - 3	Full Sun	0.050				
Purple Top	Tridens flavus	3 - 5	Part Shade	0.058				
Indian Grass	Sorghastrum nutans	3 - 6	Full Sun	0.167				
Switchgrass	Panicum virgatum	3 - 7	Full Sun	0.183				
Fall Panicum	Panicum anceps	2 - 4	Part Shade	0.042				
Total	_	_	_	1.0				
a Recommende	Jative Seed, 2015; Glennon, 2015 d seeding application rate is 8 to 18 p = pounds per acre of pure live seed	oounds per acre.						

West Virginia Excessively to Moderately Well Drained Sites

Seed Mix P-MUDW01: Recommended Mountain Physiological Region Forb Seed Mix and Application Rates for Excessively to Moderately Well Drained Sites in West Virginia							
Common Name	Scientific Name	Color	Bloom Period	Seed Application Rate (lbs/acre/PLS			
Lance Leaved Coreopsis	Coreopsis lanceolata	Yellow	Spring, Summer	0.385			
Smooth Beardtongue	Penstemon digitalis	White	Spring	0.146			
Common Milkweed	Asclepias syriaca	Pink	Spring, Summer	0.128			
Goat's Rue	Tephrosia virginiana	White/Pink	Spring, Summer	0.128			
Partridge Pea	Cassia fasciculata	Yellow	Summer	0.745			
Slender Mountain Mint	Pycnanthemum tenuifolium	White	Summer	0.069			
Early Goldenrod	Solidago juncea	Yellow	Summer	0.086			
Bergamot	Monarda fistulosa	Lavender	Summer	0.103			
Spiked Blazing Star	Liatris spicata	Pink	Summer	0.343			
Sneezeweed	Helenium autumnale	Yellow	Summer, Fall	0.128			
Gray Goldenrod	Solidago nemoralis	Yellow	Fall	0.086			
Iron Weed	Vernonia altissima	Purple	Summer, Fall	0.343			
Tall Coreopsis	Coreopsis tripteris	Yellow	Summer, Fall	0.051			
Fotal	—	_	_	2.74			

West Virginia Somewhat Poorly to Very Poorly Drained Sites

Seed Mix P-MUMP02: Recommended Mountain Physiographic Region Grass Seed Mix and Application Rate for Somewhat Poorly to Very Poorly Drained Sites in West Virginia								
Common Name	Scientific Name	Height (feet)	Sun Exposure	Seed Mix Rate (lbs/acre/PLS) ^b				
Switchgrass	Panicum virgatum	3 - 7	Full Sun	0.233				
Red Top Panicum	Panicum rigidulum	2 - 4	Full Sun	0.017				
Fowl Manna Grass	Glyceria striata	3 - 5	Part Shade	0.008				
Virginia Wild Rye	Elymus virginicus	2 - 4	Full Sun	0.217				
Canada Wild Rye	Elymus canadensis	2 - 5	Part Shade	0.167				
Deer Tongue Grass	Panicum clandestinum	2 - 4	Full Sun	0.058				
Big Bluestem	Andropogon gerardii	4 - 10	Full Sun	0.167				
Frank's Sedge	Carex frankii	1 - 2	Part Shade	0.042				
Fox Sedge	Carex vulpinoidea	2 - 3	Part Shade	0.025				
Fall Panicum	Panicum anceps	2 - 4	Part Shade	0.067				
Total	_	-	_	1.0				

TABLE 2.1.5-4							
Seed Mix P-MUMP02: Recommended Mountain Physiographic Region Forb Seed Mix Application Rate for Somewhat Poorly to Very Poorly Drained Sites in West Virginia							
Common Name	Scientific Name	Color	Bloom Period	Seed Application Rate (lbs/acre/PLS) ^a			
Ohio Spiderwort	Tradescantia ohiensis	Blue	Spring, Summer	0.167			
Smooth Beardtongue	Penstemon digitalis	White	Spring	0.083			
Butterfly Milkweed	Asclepias tuberosa	Orange	Spring, Summer	0.083			
Blackeyed Susan	Rudbeckia hirta	Yellow	Spring, Summer	0.134			
Wild Senna	Senna marilandica	Yellow	Summer	0.668			
Hoary Mountain Mint	Pycnanthemum incanum	White	Summer	0.033			
Lupine	Lupinus perennis	Blue	Summer	0.501			
Bergamot	Monarda fistulosa	Lavender	Summer	0.083			
Boneset	Eupatorium perfoliatum	White	Summer	0.083			
Joe-Pye Weed	Eupatorium fistulosum	Pink	Summer, Fall	0.125			
Showy Tickseed	Bidens aristosa	Yellow	Summer, Fall	0.501			
Sneezeweed	Helenium autumnale	Yellow	Summer, Fall	0.125			
Rough Goldenrod	Solidago rugosa	Yellow	Fall	0.083			
Total	_	_	_	2.67			

Recommended Non-Native Temporary Cover Crop Species and Non-Native Grass Cover Mix for Inclusion with Pollinator Mixtures

In areas where the erosion potential is high (e.g., steep slope areas) and/or sites that require stabilization within 30 days of disturbance, non-native temporary cover species in seed mixture P-NNTC, as shown in Table 2.1.5-5, should be used. In areas where erosion is likely to occur on steep slopes prior to the germination of native grasses and forbs, non-native grass mixture P-NNGC should be used in combination with the forb mixtures that are prescribed for non-steep slope areas within the Mountain Physiographic Region of West Virginia. Table 2.1.5-6 provides the specific non-native grass species to be included with the native forb seed mix in these areas.

TABLE 2.1.5-5								
Seed Mix P-NNTC: Recommended Mountain Physiographic Region Non-Native Temporary Cover Crop Species for Steep Slope Areas in West Virginia								
Scientific Name	Height (Inches)	Sun Exposure	Seeding Application Rate (lbs/acre/PLS) ^a	Seed Mix Planting Season				
Panicum ramosum	3 - 3.5	Full sun	5.0	Summer				
Avena sativa	2 - 2.5	Full sun	30.0	Spring and Fall				
olium multiflorum	2 - 2.5	Part shade	6.0	Fall and Winter				
	Non-Native Tempora Scientific Name anicum ramosum Avena sativa	Non-Native Temporary Cover Crop Species Scientific Name Height (Inches) anicum ramosum 3 - 3.5 Avena sativa 2 - 2.5	Non-Native Temporary Cover Crop Species for Steep Slope Are Scientific Name Height (Inches) Sun Exposure anicum ramosum 3 - 3.5 Full sun Avena sativa 2 - 2.5 Full sun	Non-Native Temporary Cover Crop Species for Steep Slope Areas in West VirginiaScientific NameHeight (Inches)Sun ExposureSeeding Application Rate (Ibs/acre/PLS) ^a anicum ramosum3 - 3.5Full sun5.0Avena sativa2 - 2.5Full sun30.0				

Seed Mix P-NNGC: Recommended Mountain Physiographic Region Non-Native Grass Cover Mix for Steep Slope Areas in West Virginia ^a							
Common Name	Scientific Name	Height (Inches)	Sun Exposure	Seed Mix Rate (lbs/acre/PLS) ^b			
Fescue	Festuca arundinacea	2 - 3	Part Shade	0.300			
Timothy	Phleum pratense	2 - 4	Part Shade	0.100			
Orchard Grass	Dactylis glomerata	2 - 3	Part Shade	0.100			
Red Top	Agrostis alba	2 - 3	Full Sun	0.020			
Ladino Clover	Trifolium repens	1 - 1.5	Part Shade	0.040			
Annual Rye Grass	Lolium multiflorum	2 - 2.5	Part Shade	0.170			
Creeping Red Fescue	Festuca rubra	1 - 2	Full Sun	0.250			
Kentucky Bluegrass	Poa pratensis	1-2	Full Sun	0.020			
Total	—	—	—	1.0			
Source: Roundstone Na	- tive Seed, 2015						

2.2 VIRGINIA

2.2.1 Augusta, Brunswick, Buckingham, Cumberland, Highland, Bath, Nelson, Nottoway, and Prince Edward Counties

The following erosion control prevention, forage species seed mixtures, and recommended soil amendments are for the Mountain and Piedmont Physiographic Regions of Virginia, which include Augusta, Brunswick, Buckingham, Cumberland, Highland, Nelson, Nottoway, and Prince Edward Counties. These recommendations are based on the U.S. Department of Agriculture-NRCS Virginia Plant Establishment Guide (Jones, et. al., 2014), which was recommended by Federal and Commonwealth agency contacts, including Charles Ivins (NRCS Conservationist), Charles Simmons (NRCS Conservationist), Davie Wade Harris (NRCS Conservationist), Jeffray Jones (State Biologist), J.B. Daniel (NRCS Conservationist), and Derek Hancock (NRCS Conservationist).

Recommended Grass Seed Mixtures, Species, Application Rates, and Planting Dates

Seed Mix VABCHNP01 (Table 2.2.1-1) provides a cool season species list mixture for erosion prevention, while Seed Mix VABCHNP02 (Table 2.2.1-2) provides cool and warm season species mixtures for forage.

			T	ABLE 2.2.1-1				
	Seed M	/lix VABCHNI	201: Recommended Coo	l Season Eros	ion Prevention Species	s and Seed Mixtures		
		Virginia	Seeding Rate (lbs/acre/PLS) ^a B:broadcast;	Plant Depth		Northern Piedmont		n Piedmont
Seeding Mix	Common Species Name	Native	D:drill (4-9" row)	(inches)	Best Dates	Possible Dates	Best Dates	Possible Dates
Average Last Frost			Ma	ay 1	Aj	Apr 15		
Perennial Grass	;							
1	Tall Fescue (use in high velocity and highly erosive situations		B: 60	1/4-1/2	Aug 15-Sep 10; Mar 15-Apr 10	Aug 1-Sep 30; Mar 1-Apr 30	Sep 1-Sep 20; Mar 1-Apr 1	Aug 25-Nov 1; Feb 15-Apr 15
2	Switchgrass	\checkmark	D:10; B:15	1⁄4	Mar 15-Jun 30		Mar 1-Jun15	
Mixtures								
3	Tall Fescue + Ladino Clover		B:40+3	1/4	Aug 15-Sep 10; Mar 15-Apr 10	Aug 1-Sep 30; Mar 1-Apr 30	Sep 1-Sep 20; Mar 1-Apr 1	Aug 25-Nov 1; Feb 15-Apr 15
4	Tall Fescue + Red Clover		B:40+6	1⁄4	Aug 15-Sep 10; Mar 15-Apr 10	Aug 1-Sep 30; Mar 1-Apr 30	Sep 1-Sep 20; Mar 1-Apr 1	Aug 25-Nov 1; Feb 15-Apr 15
5	Tall Fescue + Annual Lespedeza		B:40+10; D:30+8	1/4	Mar 1-Apr 15	Mar 1-Apr 15	Feb 15-Apr 1	Feb 15-Apr 1
6	Tall Fescue + Redtop		D/B: 40+10	1/4-1/2	Jul 25-Sep 1; Mar 20-Apr 20	Jul 15-Sep 15; Mar 1-May 15	Aug 25-Sep 15	Aug 25-Oct 25; Feb 15-Mar 31
7	Switchgrass + Red Fescue + Partridge Pea		D/B: 10+15+4	1/4	Mar 15-April 30	Mar 15-Jun 30	Mar 1-Apr 15	Feb 15-May 31
8	Switchgrass + Indiangrass + Big Bluestem		D/B: 5 each	1/4	Mar 15-Jun 30	Mar 15-Jun 30	Mar 1-Jun 15	Mar 1-Jun 15
9	Tall Fescue + Redtop + Birdsfoot Trefoil		D/B: 60+6+10	1/4-1/2	Jul 25-Sep 1; Mar 20-Apr 20	Jul 15-Sep 15; Mar 1-May 15	Aug 25-Sep 15	Aug 25-Oct 25; Feb 15-Mar 31
10	Switchgrass + Deer tongue + Partridge Pea	\checkmark	D/B: 8+8+4	1/4	Mar 15-April 30	Mar 15-Jun 30	Mar 1-Apr 15	Feb 15-May 31
11	Perennial Ryegrass + Redtop		D:5+2; B:7+3	1/2-3/4	Mar 1-Apr 15	Aug 1-Sep 15	Feb 15-April 1	Aug 15-Oct 1

9

Source: Jones, et. al., 2014 a lbs/acre/PLS = n

^a lbs/acre/PLS = pounds per acre of pure live seed

Note: The Virginia Plant Establishment Guide (Jones, et. al., 2014) provides acceptable seed mixtures and/or plant species rates, seeding dates, and other information that may be needed in the planning of practices and development of specifications for individual sites.

			TAB	BLE 2.2.1-2				
	Seed	Mix VABCHI	NP02: Recommended Cool a	and Warm	Season Forage Speci	es and Seed Mixtures		
			Seeding Rate (lbs/acre/PLS)	Plant		/Northern Piedmont ^a	Souther	rn Piedmont
Seeding Mix	Common Species Name	Virginia Native	B:broadcast; D:drill (4-9" row)	Depth (inches)	Best Dates	Possible Dates	Best Dates	Possible Dates
	Average I	Last Frost			Ν	May 1	A	Apr 15
Perennial Grass	ses							
101	Bermudagrass (Hybrid) ^b Sprigs $- 1$ bushel = 1.25 ft ³		B:30-40 bushels D:15-20 bushels	2"-4"	Not well adapted	May 1-Jun 15	Apr 15-Jun 1	Apr 1thru Jun 15 or thru Jul if irrigated
102	Bermudagrass ^b , Coated Seeds (Common & Cultivars)		B:10-12; D:8-10	1⁄4	Not well adapted	May 1-Jun 15	Apr 15– May 15	Apr 15-Jun 15
103	Big Bluestem ^c	\checkmark	B:10-12; D:8-10	1⁄4	Mar 15-Jun 30	Mar 15-Jun 30	Mar 1-Jun 15	Mar 1-Jun 15
104	Bluegrass		B:10-15; D:8-12 4-5 in mixtures	1⁄4	Aug 15-Sep 1; Mar 15-Apr 1	Aug 1-Sep 15; Mar 1-Apr 15	Seed in mixtures Mar 1- Apr 1; Aug 15 - Oct 1	Seed in mixtures Mar 1- Apr 1; Aug 15 - Oct 1
105	Eastern Gamagrass ^d (use non-stratified seed for winter planting and stratified seed for spring plantings)	\checkmark	R:8-10	1- 1.5	Nov 15-Feb 15; May 1-May30	Nov 15- Feb 15: May 1-Jun 30	Nov 25-Jan 31; Apr 20- May 15	Nov 25-Jan 31; Apr 15 - Jun 10
106	Indiangrass ^c	\checkmark	B:10-12; D:8-10	1⁄4	Mar 15-Jun 30	Mar 15-Jun 30	Mar 1-Jun 15	Mar 1-Jun 15
107	Orchardgrass ^e		B:12-15; D:8-12	1/4-1/2	Aug 20-Sep 10; Mar 15-Apr 1	Aug 15-Oct 1; Mar 1-Apr 15	Aug 25-Sep 15; Mar 1-Apr 1	Aug 25-Oct 25; Mar 1-Apr 15
109	Perennial Ryegrass ^e		D: 12-15 B:20-25; 6-10 in mixtures	1/4-1/2	Aug 20-Sep 10; Mar 15-Apr 1	Aug 15-Sep 25; Mar 1-Apr 15	Not well adapted	Aug 25-Oct 1; Feb 25-April 1
110	Prairiegrass		D:20-25; B:30-35 10-15 in mixtures	1/4-1/2	Aug 15 - Sep 15; Mar 15-Apr 15	Aug 15-Oct 15; Mar 1-Apr 30	Sep 1 - Oct 1; Mar 1-Mar 20	Aug 15-Oct 25; Feb 20-Apr 15
111	Switchgrass ^c	\checkmark	B:8-10; D:6-8	1⁄4	Mar 15-Jun 30	Mar 15-Jun 30	Mar 1-Jun 15	Mar 1-Jun 15
112	Tall Fescue		B:20-25; D:15-20	1/4-1/2	Aug 15-Sep 10; Mar 15-Apr 15	Aug 1-Sep 30; Mar 1-Apr 30	Sep 1-Sep 30; Mar 1-Apr 1	Aug 25-Nov 1; Feb 25-Apr 15
113	Timothy		B:10-12; D: 8-10	1/4-1/2	Aug 15-Sep 10; Mar 15-Apr 1	Aug 15-Oct 1; Mar 1-Apr 15	Not well adapted	Not well adapted
Mixtures								
114	$Orchardgrass + Alfalfa\ ^{\rm f}$		B:5+20; D:3+15	1/4-1/2	Aug 15-Sep 1; Mar 15-Apr 1	Aug 1-Sep 15; Mar 1-Apr15	Aug 25-Sep 15; Mar 1-Mar 20	Aug 25-Oct 15; Feb 25-Apr 1

			TAB	LE 2.2.1-2				
	Seed N	/lix VABCHI	NP02: Recommended Cool a	and Warm	Season Forage Speci	es and Seed Mixtures		
			Seeding Rate (lbs/acre/PLS)	Plant	01	/Northern Piedmont ^a	Souther	rn Piedmont
Seeding Mix	Common Species Name	Virginia Native	B:broadcast; D:drill (4-9" row)	Depth (inches)	Best Dates	Possible Dates	Best Dates	Possible Dates
115	Orchardgrass with 1 or more of the following: Ladino Clover Red Clover Annual Lespedeza		B: 10-12; D:8-10 1-2 4-6 10-12	1/4-1/2	Aug 20-Sep 10; Mar 15-Apr 1	Aug 15-Oct 1; Mar 1-Apr 15	Aug 25-Sep 15; Mar 1-Mar 20	Aug 25-Oct 15; Feb 25-Apr 1
116	Orchardgrass and Timothy with 1 or more of the following: Ladino Clover Red Clover Annual Lespedeza		B: 10-12; D:8-10 B: 4; D:2 1-2 4-6 10-12	1/4-1/2	Aug 20-Sep 10; Mar 15-Apr 1	Aug 15-Oct 1; Mar 1-Apr 15	Aug 25-Sep 15; Mar 1-Mar 20	Aug 25-Oct 15; Feb 25-Apr 1
117	Tall Fescue with 1 or more of the following: Ladino Clover Red Clover Annual Lespedeza		B:20-25; D:15-20 1-2 4- 6 10-12	1/4-1/2	Aug 15- Oct 1; Mar 1-Apr 15	Aug 15- Oct 1; Mar 1-Apr 15	Aug 25 - Oct 15; Feb 20-Apr 1	Aug 25 - Oct 15; Feb 20-Apr 1
118	Prairiegrass with 1 or more of the following: Red Clover Alfalfa ^f		B:20-25; D:15-20; 4-6 15	1/4-1/2	Aug 15 - Sep 15; Mar 10-Apr 10	Aug 1-Sep 20; Mar 1-Apr 15	Aug 25 - Sep 15; Mar 1-Mar 20	Aug 15-Oct 15; Feb 25-Apr 1
Annual Grasse	S							
119	Crabgrass ^g		B:6-8; D:4-6	1⁄4	May 15-May 31	May 1-Jun 30	May 1-May 31	Apr 15-Jun 30
120	Barley		B:140; D:120	1 - 1.5	Aug 15-Sep 15	Aug 10-Sep 30	Aug 25-Sep 15	Aug 15-Sep 30
121	Millet, Pearl		B:30-40; D:15-20	1⁄2 - 1	May 15-May 31	May 1-Jun 30	May 1-May 31	Apr 25-Jun 30
122	Millet, German Foxtail, Japanese		B:20-30;D:15-20	1⁄4	May 15-May 31	May 1-Jun 30	May 1-May 31	May 1-Jun 30
123	Oats, Winter ^h		B:80-96; D:65-80	1 – 1.5	Aug 15-Sep 10	Aug 10-Sep 15; Feb 1-Mar 1	Sep 1-Sep 15	Aug 25-Oct 1; Feb 1- Mar 1
124	Oats, Spring		B:80-96; D:65-80	1 - 1.5	Mar 15-Apr 1	Mar 15-Apr 10	Mar 5-Mar 20	Mar 5-Apr 1
125	Rye		B:120-150; D:90-110	1 – 1.5	Aug 15-Aug 31	Aug 15-Oct 25	Aug 25-Sep 15	Aug 20-Oct 31
126	Ryegrass		B:30-40; D:20-30	1/4-1/2	Aug 15-Sep 10	Aug 10-Sep 30	Aug 25-Sep 15	Aug 20-Oct 31
127	Teff ^{g, i}		B: 6-8; D 5-6	1/8	Jun 1-Jun 15	May 15 - Jul 1	May 20-Jun 10	May 1 - Jul 1
128	Wheat		B:150; D: 120	1 – 1.5	Aug 15-Aug 31	Aug 15-Oct 25	Aug 25-Sep 15	Aug 20-Oct 31
129	Small grain Mix (2 Grains)		Reduce each selection by 50%	1 – 1.5	See dates for small grains.	See dates for small grains.	See dates for small grains.	See dates for small grains.
130	Small grain mixed with annual ryegrass		Reduce Small grain 25% & ryegrass 50%	¹ /2 - 1	See dates for g	rains and ryegrass.	See dates for g	rains and ryegrass.
131	Sorghum-Sudangrass		B:30-40; D:20-30	1⁄2 - 1	May 15-May 31	May 1-Jun 30	May 1- May 31	Apr 25-Jun 30

			TAI	BLE 2.2.1-2				
	Seed I	Mix VABCHN	NP02: Recommended Cool	and Warm S	Season Forage Specie	s and Seed Mixtures		
		Virginia	Seeding Rate (lbs/acre/PLS) B:broadcast;	Plant Depth	Mountain/Valley/Northern Piedmont ^a			n Piedmont
Seeding Mix	Common Species Name	Native	D:drill (4-9" row)	(inches)	Best Dates	Possible Dates	Best Dates	Possible Dates
132	Sorghum, Forage		B: 15-20; R:5-10	1 - 1 1/2	May 15-May 31	May 1 – Jun 30	May 1–May 31	Apr 25 – Jun 30
133	Sudangrass		B:30-35; D:15-20	¹⁄2 - 1	May 15 -May 31	May 1 – Jun 30	May 1–May 31	Apr 25 – Jun 30
134	Triticale		B:140-180; D: 120-140	1 - 1.5	Aug 15-Aug 31	Aug 15-Oct 25	Aug 25-Sep 15	Aug 20-Oct 31
Perennial Legu	imes							
135	Alfalfa ^f		B:20-25; D:15-20	1⁄4	Aug 25-Sep 15;	Aug 15-Sep 25;	Sep 1-Sep 15;	Aug 25-Oct 1;
					Mar 20–Apr 7	Mar 15-Apr 15	Mar 10-Mar 20	Mar 5-Apr 5
136	Alfalfa (no-till seeding into grass)		D:10-12	1/4 - 1/2	Mar 20–Apr 7	Mar 15-Apr 15	Mar 10-Mar 20	Mar 5-Apr 5
137	Birdsfoot Trefoil (no-till into suppressed grass sod)		D:6-8	1⁄4	Aug 15-Sep 1	Aug1-Sep 15	Not adapted	Not adapted
138	Birdsfoot Trefoil (frost seed onto pasture)		B: 8-10	0	Feb 1-Mar 1	Jan 25-Mar 10	Not adapted	Not adapted
139	Ladino or White Clover (no-till into suppressed grass sod)		D:1-2	1⁄4	Aug 20-Sep 10; Mar 15-Apr 1	Aug 15-Sep 25; Mar 1-Apr 15	Aug 25-Sep 15; Mar 1-Mar 20	Aug 25-Oct 15; Feb 25-Apr 1
140	Ladino or White clover (frost seed onto pasture)		B:1-2	0	Feb 1-Mar 1	Jan 25-Mar 10	Jan 25-Feb 15	Jan 20-Mar 1
141	Red Clover (no-till into suppressed grass sod)		D:4-6	1/4 - 1/2	Aug 20-Sep 10; Mar 15-Apr 1	Aug 15-Sep 25; Mar 1-Apr 15	Aug 25-Sep 15; Mar 1-Mar 20	Aug 25-Oct 15; Feb 25-Apr 1
142	Red Clover (frost seed onto pasture)		B:4-6	0	Feb 1-Mar 1	Jan 25-Mar 10	Jan 25-Feb 15	Jan 20-Mar 1
Annual Legum	les							
143	Crimson Clover w/Ryegrass or small grain		B:20; D:15 & reduce small grain by 1/3	1/4 - 1/2	Aug 15-Sep 10	Aug 10-Sep 30	Aug 25-Sep 15	Aug 20-Oct 15
144	Lespedeza, Kobe (Southeast VA) (frost seeded onto pastures)		B:10-15	0	Not adapted	Not adapted	Not well adapted	Not well adapted
145	Lespedeza, Korean (frost seeded onto pastures)		B:10-15	0	Feb 1-Mar 1	Feb 1-Mar 15	Jan 25-Mar 1	Jan 25-Mar 10
146	Hairy Vetch w/ small grain		B: 15; D 10 & reduce small grain by 50%	1/2 - 1 1/2	Aug 15-Aug 31	Aug 15-Sep 15	Aug 25-Sep 15	Aug 20-Oct 1

			TA	BLE 2.2.1-2				
	Seed I	Mix VABCHN	P02: Recommended Coo	l and Warm S	Season Forage Speci	ies and Seed Mixtures		
			Seeding Rate (lbs/acre/PLS) Plant B:broadcast; Denth	Mountain/Valley/Northern Piedmont ^a		^a Southern Piedmont		
Seeding Mix	Common Species Name	Virginia Native	D:drill (4-9" row)	Depth (inches)	Best Dates	Possible Dates	Best Dates	Possible Dates
Other Specie	8							
147	Chicory		B: 3-4 D: 1-2	1/4 - 1/2	Apr 15-May5	Apr 1-May 15	Sep 1-Sep 15	Sep 1-Oct 10
	(in mixture w/grass & legume)							
148	Brassicas ^j (sow 1-2 of the following in a 50% rate mix of summer or winter		B: 2-3 D: 1-2	1/4 - 1/2	May 1 - Jun 30 Aug 1 - Sep 1	May 1 - Jun 30 Aug 1 - Sep 1	Apr 20 - Jun 20 Aug 1 - Sep 10	Apr 20 - Jun 20 Aug 1 - Sep 10
	annual grasses in late spring or late summer respectively)							
	Rape							
	Kale							
	Turnip Turnin X Bong							
	Turnip X Rape Radish							
	Rauisii							
Source: Ione	es, et. al., 2014							
	he northern piedmont planting dates may l	be on the oppos	ite end of the planting ran	ge compared t	o the mountains and	vallev in Southwest VA.		
	prigged and seeded Bermudagrass have be	**	1 0 0	J 1		•	er chance of winter ki	11.
	ative warm season grass planting date wil		•	U		1 0		
	astern Gama grass can be planted with a c	•		-	•	•		
T	his species tends to be a short lived perent the state especially when managed with t	nial when plante	d and managed in monocu	iltures in the p	biedmont and eastern	•		ntain and valley region
	all planted alfalfa should not be no-tilled;					ll 30-60 days before first l	cilling fros.t	
	anting too deep is a common cause of star		I	1	8	,	8	
It	is generally not recommended to plant oa inter.		st of the Blue Ridge becau	ise they will w	vinter kill, however th	ney are sometimes planted	late summer and gra	zed in the fall and early
Ν	ot recommended for no-till planting, need	s a clean firm s	eedbed to ensure establish	ment.				
	rassicas are not recommended in a monoc immer or winter annuals to avoid problem					problems with rumen fun	ction; they should be	planted mixed with

	TABLE 2.2.1-3
R	ecommended Soil Amendments
Туре	Application Rate
Lime	2 tons/acre
Fertilizer 10-10-10	1,000 lbs/acre

Mulching

The NRCS Conservation Practice Standard - Mulching (Code 484) (NRCS, 2014) provides a general recommendation for mulching in Virginia. Mulching materials should consist of natural/artificial materials that can provide a certain depth/thickness and durability to achieve adequate cover. Mulch should be applied evenly and, if necessary, anchored into the soil. As a minimum, apply manufactured mulches in accordance with the manufacturer's specifications. The Mulch Specifications table provides some general guidelines when using certain mulches.

	TABLE 2.2.1-4
м	Aulch Specifications
Mulch Type	Suggested Cover
Cereal Grain/Grass Hay	70% Ground Cover
Wood Products (Wood Chips, Bark)	\leq 2-inch thickness
Gravel / Other Inorganic Materials	0.75 to 2-inch diameter / 2-inch thickness

Mulch should be applied to provide adequate protection from erosion, yet allow light and moisture to penetrate into the seedbed. Typical mulching provides 70 percent cover (approximately 2,000 pounds of straw per acre) with the appropriate erosion control measure to hold the seed and straw in place during establishment, depending on slope (NRCS Code 342) (NRCS, 2011). There are several types of mulches that can be used to conserve soil moisture, promote plant growth, and reduce erosion; however, there are also mulches that can have the reverse affect (see Mulch Considerations table). Consider potential benefit or detrimental effects of mulching to the impacted and surrounding areas.

	TABLE 2.2.1-5			
Mulch Considerations				
Туре	Warning	Recommendation		
Rice Hulls (finely textured)	Limited oxygen penetration	<2 inches thick		
Thick/Tightly Packed Materials	Soggy, anaerobic conditions during wet weather	Avoid excessively thick/tightly packed		
	Interference with insect movements, increase of rate of crop pests/diseases	mulches		
	Provides nesting habitat for ground-burrowing rodents that can chew extensively on tree trunks/roots			
Sawdust (finely-divided plant residues)	Similar Carbon/Nitrogen ratio ties up soil nitrogen and necessitate supplemental nitrogen applications on crops	Use coarser materials, such as grain straw/chipped brush		
Plastic (Low permeability)	Increase concentrated flow and erosion on nearby sites	Refrain from using low permeability mulches		
Black Mulch	Warm the soil by conduction	Good for weed control		
Source: NRCS, 2014				

An operation and maintenance plan should clearly document:

- Purpose of mulch and type;
- Percent cover and/or thickness of mulch material;
- Timing of application;
- Site preparation; and
- Method of anchoring (i.e., netting, tackifiers, etc.).

Recommended Perennial Grasses and Pollinator Seed mixtures, Species, and Rates for Mountainous and Piedmont Regions

The following seed mixtures are for the Mountainous and Piedmont Regions of Virginia. These recommendations are based on discussions and information provided by Robert Glennon, private lands biologist from the Conservation Management Institute, Virginia Tech and NRCS, and the Xerces Society.

Grass	Good Mirr and Application Do			
	s Seeu Mix and Application Ra	tes for Excessively to Moderately	y Well Drained Sites in Virginia	
Common Name	Scientific Name	Cultivar or Germplasm	Drilled Seeding Rate ^a (weight of pure live seed (PLS) per acre)	Seeds per Square Foot
Little Bluestem	Schizachyrium scoparium	Cimarron (OK) or Suther Germplasm (NC)	0.5 pound	3
Splitbeard Bluestem	Andropogon ternarius	Missouri or Kentucky Ecotype	0.5 pound	3

	Seed Mix P-VABCHNP01: R			7• • . • .
Forb Seed	Mix and Application Rates for	Excessively to Model	Seeding Rate (weight of	Virginia
Common Name ^a	Scientific Name	Flowering Season	bulk seed per acre)	Seeds per Square Foot
Bearded Beggartick (A)	Bidens aristosa	Late Summer	1 pound	3
Plains Coreopsis (A)	Coreopsis tinctoria	Late Spring	1 ounce	3
Partridge Pea (A)	Chamaecrista fasciculata	Mid-Summer	2 pounds	3
Black-eyed Susan (B)	Rudbeckia hirta	Early Summer	2 ounces	3
Wild Bergamot (P)	Monarda fistulosa	Summer	1 ounce	3
Lanceleaf Coreopsis (P)	Coreopsis lanceolata	Late Summer	10 ounces	3
Maximilian Sunflower (P)	Helianthus maximilianii	Late Summer	11 ounces	3
Slender Mountain Mint (P)	Pycnanthemum tenuifolium	Late Summer	1 ounce	3
Purple Coneflower (P)	Echinacea purpurea	Early Summer	1.2 pound	3
Total	—	—	6.8 lbs/acre	33
Source: Glennon, 2015				

	and have	a High Pollinator Value		
Common Name	Scientific Name	Cultivar or Germplasm	Drilled Seeding Rate (weight of pure live seed (PLS) per acre)	Seeds per Square Foot
Grasses				
Beaked Panicum	Panicum anceps	SC or MD Ecotype	0.25 pound	3
Redtop Panicum	Panicum rigidulum	NC Ecotype	0.20 pound	3
Forbs (Wildflowers) – 8 of 9 H	ligh Value Pollinator Value			
Common Name A = Annual B = Biennial,	Scientific Name	Flowering Season	Seeding Rate (weight of bulk seed per acre)	Seeds per Square Foot
P = Perennial Aster, Purple-stemmed (P)	Symphyotrichum puniceum var. puniceum	Fall	3 ounces	3
Bergamot, Wild (P)	Monarda fistulosa	Summer	1 ounce	3
Coreopsis, Plains (A)	Coreopsis tinctoria	Late Spring	1 ounce	3
Goldenrod, Pine Barrens (P)	Solidago fistulosa	Late Summer	3 ounces	3
Joe Pye Weed, Spotted (P)	Eupatoriadelphus fistulosus	Late Summer	2 ounces	3
Partridge Pea (A)	Chamaecrista fasciculata	Mid-Summer	2 pounds	3
Rattlesnake Master (P)	Eryngium yuccifolium	Summer	8 ounces	3
Rosemallow (P)	Hibiscus moscheutos	Summer	2 ounces	3
Narrowleaf Sunflower (P)	Helianthus angustifolius	Late Summer	4 ounces	3
Total	_	—	4.0 lbs/acre	33

2.2.2 Federal Lands

George Washington National Forest - Augusta, Bath, and Highland Counties

This section is pending additional consultation with the U.S. Forest Service.

2.2.3 State Lands

James River Wildlife Management Area – Nelson County

The following seed mixtures and application rates recommendations are for the James River WWA in Nelson County, Virginia. The recommendations are based on correspondence and discussions with Virginia Department of Game and Inland Fisheries regional specialist staff (Amy Ewing, environmental services biologist/FWIS Manager, Virginia Department of Game and Inland Fisheries). These seed mixes are considered suitable for planting of the ACP pipeline. The specialist staff is supportive of the use of native vegetation mixes that stabilize the corridor while providing food and cover for a variety of wildlife.

James River Wildlife Management Area (WMA) Excessively to Moderately Well Drained – Partially Shade Sites

	TABLE 2.2.1-9	
Seed M	Aix VJRWMA01: Recommended Grass Seed Mix Excessively to Moderately Well Drained – Part	
Common Name	Scientific Name	Seed Mix Rate (lbs/acre/PLS) ^b
June Grass	Koeleria macrantha	0.012
Canada Wild Rye	Elymus canadensis	0.083
Virginia Wild Rye	Elymus virginicus	0.208
Creeping Red Fescue	Festuca rubra	0.167
Purple Top	Tridens flavus	0.083
Upland Bentgrass	Agrostis perennans	0.005
Little Bluestem	Schizachyrium scoparium	0.208
Broomsedge	Andropogon virginicus	0.033
Fall Panicum	Panicum anceps	0.167
Nimblewill	Muhlenbergia schreberii	0.033
Total	_	1.0
Source: Recommendations prov	ided by the Virginia Department of Game and Inland	Forest.
a Recommended seeding	application rate is 6.3 to 9.0 pounds per acre.	
b lbs/acre/PLS = pounds p	per acre of pure live seed	

James River WMA Excessively to Moderately Well Drained - Wildlife Sites

Seed Mix VJRWMA02: Recommended Grass Seed Mix and Application Rates for Excessively to Moderately Well Drained – Wildlife Sites ^a					
Common Name	Scientific Name	Seed Mix Rate (lbs/acre/PLS) ^b			
Big Bluestem	Andropogon gerardii	0.070			
Indian Grass	Sorghastrum nutans	0.070			
Little Bluestem	Schizachyrium scoparium	0.141			
Switchgrass (Blackwell)	Panicum virgatum	0.070			
Canada Wild Rye	Elymus canadensis	0.106			
Tall Dropseed	Sporobolus compositus	0.070			
Purple Top	Tridens flavus	0.035			
Plains Coreopsis	Coreopsis tinctoria	0.019			
Purple Prairie Clover	Dalea purpurea	0.057			
Blackeyed Susan	Rudbeckia hirta	0.033			
Illinois Bundleflower	Desmanthus illinoensis	0.077			
Partridge Pea	Cassia fasciculata	0.120			
Browneyed Susan	Rudbeckia triloba	0.025			
Maximilian Sunflower	Helianthus maximiliani	0.060			
Roundhead Lespedeza	Lespedeza capitata	0.033			
New England Aster	Aster novae-angliae	0.012			
Total	_	1.0			

	TABLE 2.2.1-11	
Seed Mix VJRWMA03: F	Recommended Grass Seed Mixes and Applicat	tion Rates for Steep Slopes Stabilization – Sites
Common Name	Scientific Name	Seed Mix Rate (lbs/acre/PLS) ^b
Seed Mix ^a		
Creeping Red Fescue	Festuca rubra	0.050
Virginia Wild Rye	Elymus virginicus	0.083
Fall Panicum	Panicum anceps	0.083
Side Oats Grama	Bouteloua curtipendula	0.083
Big Bluestem	Andropogon gerardii	0.083
Indian Grass	Sorghastrum nutans	0.083
Purple Top	Tridens flavus	0.033
Switchgrass	Panicum virgatum	0.083
Little Bluestem	Schizachyrium scoparium	0.083
Bird's Foot Trefoil	Lotus corniculatus	0.025
Lance Leaved Coreopsis	Coreopsis lanceolata	0.042
Blackeyed Susan	Rudbeckia hirta	0.008
Partridge Pea	Cassia fasciculata	0.058
Illinois Bundleflower	Desmanthus illinoensis	0.033
False Sunflower	Heliopsis helianthoides	0.042
Showy Tickseed	Bidens aristosa	0.042
Maximilian Sunflower	Helianthus maximiliani	0.042
Iron Weed	Vernonia altissima	0.025
Hairy Mountain Mint	Pycnanthemum pilosum	0.003
Gray Goldenrod	Solidago nemoralis	0.013
Total	_	1.0
Common Name		Seed Application Rate (lbs/acre/PLS) ^b
Seed Mix		
Buckwheat ^c		15-20
Millet		5-7
Korean lespedeza		5-7
Perennial Ryegrass		5-8
Blackwell switchgrass		3-4
Source: Recommendations provid	ed by the Virginia Department of Game and Inla	nd Forest.
	plication rate is 7.4 to 10.7 pounds per acre.	
b lbs/acre/PLS = pounds per	-	
	rost sensitive and deepening on the planting date or remove the application of buckwheat.	, increase the application rate Korean lespedeza to

James River WMA Steep Slope Stabilization Sites

2.2.4 Dinwiddie, Greensville, and Southampton Counties, and Chesapeake and Suffolk Cities (Coastal Plain Region)

The following seed mixtures, site preparation, seeding techniques, and amendments recommendations are for Dinwiddie, Greensville, Suffolk, Southampton, and Chesapeake Counties. These recommendations are based on information provided by Mr. Robert Glennon. NRCS Conservationists in these counties referred to Mr. Robert Glennon's recommendations.

2.2.4.1 Recommended Grass Seed Mixtures, Application Rates, and Planting Dates

Seeding species, cultivars, rates, and planting dates are contained in the table below. The materials identified as "common" do not require a specific cultivar for successful establishment and performance. Nurse crops must be sown at the same time as the perennial cover species to ensure that the site will have quick cover. The temporary cover specifications are intended for use when the site will not be sown to a perennial cover immediately after construction and a temporary cover is needed until the seed can be sown during the proper seeding season.

		Seeding Application Rate	
Species	Cultivars	(lbs/acre)	Seeding Dates
Tall Fescue and White Clover	(Cool Season Mixture)		
Tall Fescue	Bronson – endophyte free, Max-Q Jessup – friendly endophyte	20-25 pounds broadcast 15-20 drilled	September 1 – October 31; February 1 – March 31
White Clover	White Dutch Type	2 pounds broadcast, 1 pound drilled	September 1 – October 31; February 1 – March 31
Bermudagrass and Japanese I	Lespedeza (Warm Season Mixture)		
Bermudagrass	Common	10-12 pounds broadcast;	April 1 – June 10
	Cheyenne II	8-10 pounds drilled	
	Pasto Rico		
	Ranchero Frio		
Japanese Lespedeza	Kobe	10-12 pounds broadcast or drilled	April 1 – June 10
Nurse Crops (Sow with the Po	erennial Seed Mixtures for Quick Cover)		
Oats	Common	25-30 pounds broadcast; 20-25 drilled	September 1 – November 15; February 1 – April 20
Rye	Common	35-50 broadcast; 25-40 drilled	September 1 – November 15; February 1 – April 20
Wheat	Common	40-50 broadcast; 30-40 drilled	September 1 – November 15; February 1 – April 20
Millet (Browntop, German, Italian, Foxtail, Proso)	Common	10-15 broadcast; 7-10 drilled	April 20 – August 1
Temporary Crops (Sow on Ar	reas that will not be Seeded Immediately)		
Oats	Common	80-95 broadcast; 65-80 drilled	September 1 – November 15; February 1 – April 20
Rye	Common	120 broadcast; 100 drilled	September 1 – November 15; February 1 – April 20
Wheat	Common	120 broadcast; 100 drilled	September 1 – November 15; February 1 – April 20
Millet (Browntop, German, Italian, Foxtail, Proso	Common	20-30 broadcast; 15-20 drilled	April 20 – August 31

Site Preparation

The soils on the Coastal Plain of Virginia in Dinwiddie, Greensville, Suffolk, and Southampton counties typically have sandy topsoil but have a heavy clay subsoil close to the soil surface. The sandy topsoil must be kept separate during construction to prevent mixing with the subsoil, which will ensure easy till-ability and compaction and allow seeds to sow without restriction. To ensure optimum conditions in the soil for germination and early growth for soils sown to non-native species, the species should be tested, limed, and fertilized according to the soil test recommendations.

Seeding Technique

Seed may be established by broadcasting on a firm seedbed and packing the seed, or by drilling the seed into a firm seedbed and packing the seed. Drilled seed of the perennial seed grass species, legumes, and annual millets should only be placed at a depth of ¹/₄ inch. The nurse crops and temporary cover species oats, rye, and wheat may be broadcast but will perform best if drilled at a one-inch depth.

Mulching

To ensure that the seed will remain in place through germination and growth, seedlings must be mulched. Synthetic or processed mulch must be applied and anchored according to the manufacturer's recommendations. Straw (seed stalks of small grains – usually wheat) may be used as mulch at a rate of 75 to 100 pounds per acre (1.5 to 2.5 tons per acre). The mulch must be anchored with a sprayed on product or netting applied according to the manufacturer's recommendations. It should be noted that hay must not be used as mulch, as hay typically contains weeds that would negatively impact the restoration of the area.

2.2.4.2 Recommended Perennial Grasses and Pollinator Seed Mixtures, Species, and Application Rates for the Coastal Plain Region

The following seed mixtures are for the Coastal Plain Region of Virginia. These recommendations are based on discussions and information provided by Robert Glennon.

Common Name	Scientific Name	Cultivar or Germplasm	Seeding Rate (weight of pure live seed (PLS) per acre) Drilled	Seeds per Square Foot
Perennial Grasses in Mixture		*	,	
Little Bluestem	Schizachyrium scoparium	'Cimarron' (OK) or Suther Germplasm (NC)	0.5 pound	3
Splitbeard Bluestem	Andropogon ternarius	Missouri or Kentucky Ecotype	0.5 pound	3
Forbs (Wildflowers) in Mixture				
Common Name A = Annual B = Biennial P = Perennial	Scientific Name	Flowering Season	Seeding Rate (weight of bulk seed per acre) Drilled	Seeds per Square Foot
Narrowleaf Mountain Mint (P)	Pycnanthemum tenuifolium	Late Summer	1 ounce	3
Plains Coreopsis (A)	Coreopsis tinctoria	Late Spring	1 ounce	3
Partridge Pea (A)	Chamaecrista fasciculata	Mid-Summer	2 pounds	3
Black-eyed Susan (B)	Rudbeckia hirta	Early Summer	2 ounces	3
Bergamot, Spotted (P)	Monarda fistulosa	Summer	1 ounce	3
Lanceleaf Coreopsis (P)	Coreopsis lanceolata	Late Summer	10 ounces	3
Maximilian Sunflower (P)	Helianthus maximilianii	Late Summer	11 ounces	3
Indian Blanket (A)	Gaillardia pulchella	Indeterminate	9 ounces	3
Purple Coneflower (P)	Echinacea purpurea	Early Summer	1.2 pound	3
Total	_	_	6.4 lbs/acre	33

		TABLE 2.2.4-3		
Seed Mix P-VACSDGS02: Native Grasses and Forbs for Somewhat Poorly to Very Poorly Drained Soils and have a High Pollinator Value - Higher Pollinator Value (8 of 9 High Value)				
Common Name	Scientific Name	Cultivar or Germplasm	Seeding Rate (weight of pure live seed (PLS) per acre) Drilled	Seeds per Square Foot
Grasses in Mixture				
Beaked Panicum	Panicum anceps	SC or MD Ecotype	0.25 pound	3
Redtop Panicum	Panicum rigidulum	NC Ecotype	0.20 pound	3
Forbs (Wildflowers) in Mixture				
Common Name			Seeding Rate	
A = Annual B = Biennial,			(weight of bulk seed per acre)	
P = Perennial	Scientific Name	Flowering Season	Drilled	Seeds per Square Foot
Aster, Purple-stemmed (P)	Symphyotrichum puniceum var. puniceum	Fall	3 ounces	3
Sneezeweed, Common (P)	Helenium autumnale	Fall	2 ounces	3
Coreopsis, Plains (A)	Coreopsis tinctoria	Late Spring	1 ounce	3
Goldenrod, Wrinkleleaf (P)	Solidago rugosa	Late Summer	2 ounces	3
Joe Pye Weed, Spotted (P)	Eupatoriadelphus fistulosus	Late Summer	2 ounces	3
Partridge Pea (A)	Chamaecrista fasciculata	Mid-Summer	2 pounds	3
Rattlesnake Master (P)	Eryngium yuccifolium	Summer	8 ounces	3
Rosemallow (P)	Hibiscus moscheutos	Summer	2 ounces	3
Narrowleaf Sunflower (P)	Helianthus angustifolius	Late Summer	4 ounces	3
Total	_	_	4 lbs/acre	33

2.3 NORTH CAROLINA

2.3.1 Northampton County

The following recommendations of seed mixtures, rates, planting dates, and amendments are for Northampton County, North Carolina. The recommendation is from Paul Boone (NRCS District Conservationist).

Recommended Grass Seed Mixtures, Application Rates, Planting Dates, and Amendments

	TABLE 2.3.1-1		
Seed Mix NCNO	01: Recommended Cool Season Seed Mixture		
Common Species Name ^a	Seed Application Rate (lbs/acre/PLS) ^b	Planting Date	
Spring (February - March) and Fall (September - Novemb	per) Seeding		
Tall Fescue mixed with any of the following grains:	60	Feb - Nov	
Wheat	60	Oct 25 - Nov 15	
Oats and Barley	60	Sept 1 - Oct 15	
Rye	60	Sept 15 - Nov 1	
Korean Lespedeza	20	March - May	
Sercia Lespedeza	20	Oct - May	
a Recommendations provided by the Northampt	on County NRCS office District Conservationist.		
^b lbs/acre/PLS = pounds per acre of pure live se	ed		
Note: Apply small grain mulch at 2 tons/acre or check	ck with the NRCS office for alternatives mulches.		

Seed Mix NCNC	02: Recommended Warm Season Seed Mixture			
Common Species Name ^a Seed Application Rate (lbs/acre/PLS) Planting Date				
Temporary Cover				
Brown Top Miller	30-40	May 5 – July 5		
Japanese Millet	25	May 5 – July 5		
Permanent Cover				
Pensacola Bahia	25	March 15 – June 15		
Pensacola Bahia mixed with any of the following:	20	March - May		
Annual Lespedeza	20	March - May		
Kolb Lespedeza	20	March - May		
Common Lespedeza	20	March - May		
Korean Lespedeza	20	March - May		
Bermuda Grass (Hulled)	8-10	April - July		
Bermuda Grass				
Hulled Bermunda (up June)	6-10	April – July		
Unhulled Bermuda	15-18	January - March		

TABLE 2.3.1-3		
Recommended Soil Amendments		
Туре	Application Rate	
Line 2 tons/acre		
Fertilizer 10-10-10	1,000 lbs/acre	

2.3.2 Halifax and Wilson Counties

The following seed mixture, planting dates, and cover crop recommendations are primarily for Wilson County, but are also applicable for Halifax County. The recommendation is from David Little (NRCS District Conservationist).

	ed Mix NCHW01: Recommended Cool Season See	
Common Species Name ^a	Seed Application Rate (lbs/acre/PLS) ^b	Planting Date
Tall Fescue and White Clover	30-50	Sept 1 – Sept 30 (Coastal Plain)
Cover Crop ^a		
Buckwheat	80	Late Winter-Spring
Oats	180	Late Winter-Spring
Rye	120-180	Late Winter-Spring
Ryegrass	30-40	Late Winter-Spring
Oats and Ryegrass	90	Late Winter-Spring
Oats and Korean Lespedeza	20	Late Winter-Spring
Browntop Miller	30-40	Summer
Rye	120-180	Late Summer/Early Winter
Ryegrass	30-40	Late Summer/Early Winter
Oats (Before Oct 1)	120-180	Late Summer/Early Winter
Barley (Before Oct 15)	120-180	Late Summer/Early Winter
Wheat (After Oct 1)	120-180	Late Summer/Early Winter
Rye and Ryegrass mixture	60 Rye + 20 Ryegrass	Late Summer/Early Winter
Little barley	75-80	Late Summer/Early Winter
seasons of the year, and wher		water pollution prior to the establishment of

Recommended Grass Seed Mixtures, Application Rates, Planting Dates, and Cover Crops

2.3.3 Nash and Johnston Counties

The following species and cover crop seeding application rates, planting dates, and amendments recommendations are for Nash and Johnston counties. The seed mixture recommendations are from correspondence with Patrick Evans (NRCS District Conservationist Nash County) and Brian Loaholt (NRCS District Conservationist). Seed Mix NCNJ01 provides seeding specifications for conservation work.

Recommended Grass Seeding Species, Application Rates, Planting Dates, Cover Crops, and Amendments

		TABLE 2.3.3-1		
	S	eed Mix NCNJ01: Recommended Cool Season Grass S	seed Mixture	
Common	n Species Name ^a	Seed Application Rate (lbs/acre/PLS) ^b	Planting Date	
Tall Fest	cue	30-40	Sept 1 – Sept 30 (Coastal Plain)	
Sorghum (Cover crop) ^c		60-120	_	
c Notes:	seasons of the year, and w finished grade or perennia planned, to assure econom	on is desirable to minimize erosion and pollution and perm here a temporary seeding is needed to control erosion and l vegetation. The temporary measures should be coordina	water pollution prior to the establishment of ated with the permanent erosion control measures	

TABLE 2.3.3-2		
Recommended Lime and Fertilizer Application		
Type Application Rate		
Lime 2 tons/acre		
Fertilizer - 10-10-10	500 - 700 lbs/acre	

2.3.4 Sampson County

The following recommendations for seed mixtures, rates, planting dates, and amendments are for Sampson County. The recommendations are based on correspondence with Gavin Thompson (NRCS District Conservationist) and Susan Davis (West Virginia Department of Natural Resources). Seed Mixes NCSA01 and NCSA02 are NRCS recommended cool and warm season mixtures for disturbed areas. No pollinator species specific to the County were recommended by the Conservationist.

2.3.4.1 Recommended Grass Seed Mixtures, Application Rates, and Planting Dates

	TABLE 2.3.4-1	
Se	ed Mix NCSA01: Recommended Cool Season Seed Mixtu	re
Common Species Name ^a	Seeding Application Rate (lbs/acre/PLS) ^b	Planting Date
Tall Fescue or	40-50	Sept - March
Bermudagrass (hull attached)	15	January - March
 Recommendations provided b along the pipeline. b lbs/acre/PLS = pounds per acr 	y the Sampson County NRCS office District Conservationist. e of pure live seed	Used Tall Fescue to seed wet spots

TABLE 2.3.4-2				
See	d Mix NCSA02: Recommended Warm Season Seed Mixtu	re		
Common Species Name	Seeding Application Rate (lbs/acre/PLS)	Planting Date		
Bermudagrass (hull removed)	8-10	April – August		
 Recommendations provided by Ibs/acre/PLS = pounds per acre 	y the Sampson County NRCS office District Conservationist. e of pure live seed			

2.3.4.2 Recommended Lime and Fertilizer Application

Where soils are relatively uniform and amendments can be incorporated, use appropriate lime and fertilize according to a soils test. In the absence of a soil test, use the recommended lime and fertilizers application rates in the table below.

Recommended Lime and Fertilizer Application				
Туре	Application Rate			
Lime (dolomite)	1-2 tons/acre			
Fertilizer 10-10-10	500 - 800 lbs/acre ^a			

2.3.4.3 Planting Recommendations

Where conventional equipment is used for planting, seed shall be applied uniformly with cultipacker-seeders, drills, seeders or other mechanical seeders. Any equipment that will apply seed uniformly is acceptable. Seeding may be done by hand where it is not practical or feasible to use equipment.

2.3.4.4 Mulching Recommendations

- Mulching is essential on all sites, especially steep, erosive sites where plant establishment may be expected to be difficult.
- Use of dry, unchopped, and unweathered small grain straw or hay-free-seeds (from completing plant species). Spread at the rate of 1-2 tons per acre depending upon the site and season.
- Apply mulch uniformly so that about 25 percent of the ground surface is visible.
- Anchor mulch immediately after placement to minimize loss by water and/or wind.

Cumberland County 2.3.5

The following recommended seed mixture, rates, planting dates, cover crop, and amendments are for Cumberland County. The recommendations are from correspondence with Renessa Brown (NRCS District Conservationist). No pollinator species recommendations specific to the County were provided.

Cover Crop ^c Buckwheat Oats Rye Ryegrass	5-7 (drill) 6-8 (broadcast) 80 180 120-180	April 1 – May 15 (best); April 1 – June 7 (possible) Late Winter-Spring Late Winter-Spring
Oats Rye Ryegrass	80 180 120-180	Late Winter-Spring Late Winter-Spring
Buckwheat Oats Rye Ryegrass	180 120-180	Late Winter-Spring
Oats Rye Ryegrass	180 120-180	Late Winter-Spring
Rye Ryegrass	120-180	1 0
Ryegrass		
		Late Winter-Spring
Oats and Druggeoga	30-40	Late Winter-Spring
Oats and Ryegrass	20 and 90	Late Winter-Spring
Oats and Korean Lespedeza	20 and 90	Late Winter-Spring
Browntop Miller	30-40	Summer
Rye	120-180	Late Summer/Early Winter
Ryegrass	30-40	Late Summer/Early Winter
Oats (Before Oct 1)	180	Late Summer/Early Winter
Barley (Before Oct 15)	120-180	Late Summer/Early Winter
Wheat (After Oct 1)	120-180	Late Summer/Early Winter
Rye and Ryegrass mixture	60 Rye + 20 Ryegrass	Late Summer/Early Winter
Little barley	75-80	Late Summer/Early Winter

2.3.5.1 Recommended Seed Mixtures, Application Rates, and Planting Dates

a temporary seeding is needed to control erosion and water pollution prior to the establishment of finished grade or perennial vegetation. The temporary measures should be coordinated with the permanent erosion control measures planned, to assure economical and effective control.

TABLE 2.3.5-2				
Rec	commended Lime and Fer	tilizer Application		
Planting	Fertilizer Analysis	Fertilizer Rate (lbs/acre)	Lime Rate (lbs/acre)	
Perennial Grasses with or without Legumes, Fertilizer no incorporated	10-10-10	10 lbs / 1,000 sq. ft.	46 lbs / 1,000 sq. ft.	
Temporary Cover, Fertilizer not incorporated	10-10-10	12 – 16 lbs / 1,000 sq. ft.	92 lbs / 1,000 sq. ft.	

TABLE 2.3.5-3				
Recommended Mulch Material Rates and Uses				
Minimum Rates Per Acre Coverage		Remarks		
1 – 2 tons/acre	75% (25% of ground is visible)	Evenly spread mulch over the area by hand or blower-type spreading equipment		
—	100%	Secure in place if flowing water is involved		
_	100%	May be used in the place of mulch or sod; has the strength to withstand water flow. It is an accepted practice to sow half the seed before placing the matting. Sow the remaining half after the matting is laid.		
_	75% (25% of ground is visible)	Do not apply within 50 feet of surface waters		
—	_	Available as mulch material to be blown on after seeding or as a matting to be stapled on steep slopes, waterways, etc.		
	Minimum Rates Per Acre	Minimum Rates Per AcreCoverage1 - 2 tons/acre75% (25% of ground is visible)100%100%		

2.3.5.2 Planting Recommendations

Mulching should be specified to reduce damage from water run-off and improve moisture conditions for seedlings. Temporary vegetation can be satisfactorily established without the use of mulch.

2.3.6 Robeson County

The following seed mixture, rates, and planting date recommendations are for Robeson County. The recommendation comes from Jeremy Ruston (NRCS District Conservationist).

Recommended Grass Seed Mixtures

	TABLE 2.3.6-1	
Seed Mix NCRO	01: Recommended Warm Season Seed Mix	ature
Common Species Name ^a	Seeding Rate (lbs/acre/PLS) ^b	Planting Date
Switchgrass (Carthage or Cave-In-Rock cultivars)	1	April 1 – May 15
Little Bluestem	1.5	April 1 – May 15
Indian Grass	1	April 1 – May 15
a Recommendations provided by the Roberson b lbs/acre/PLS = pounds per acre of pure live s	n County NRCS office District Conservationis seed	st.

TABLE 2.3.6-2 Seed Mix P-NCRO01: Recommended Pollinator Seed Mixture Seeding Application Seed Rate (lbs/acre/PLS)^a Common Name Scientific Name Bloom Period Sun Soil Lanceleaf coreopsis Coreopsis lanceolata April - June Full - Shade Dry-Moist 0.3 Wrinkleleaf Full to Partial shade Solidago rugosa Late Summer Moist goldenrod Purple coneflower Echinacea purpurea April - September Full to Partial shade Dry Recommendations provided by the Roberson County NRCS office District Conservationist. Source: lbs/acre/PLS = pounds per acre of pure live seed

Recommended Pollinator Seed Mixtures

2.3.7 Recommended Native Grass and Pollinator Seed Mixtures, Application Rates, and Non-Native Cover Crop by Physiographical Region (Coastal Plain)

The following seed mixtures are for the Coastal Plan Region. These recommendations are from discussions with Roundstone Native Seed and Robert Glennon.

Recommended Seed Mixtures by Geographical Region (Coastal Plain) and Drainage Class

Grass Se	Seed Mix P-CPDW01: Recommended Coastal Plain Physiographic Region Grass Seed Mix and Application Rates for Excessively to Moderately Well Drained Sites in North Carolina ^a				
Common Name	Scientific Name	Height (Inches)	Sun Exposure	Seed Mix Rate (lbs/acre/PLS) ^b	
Little Bluestem	Schizachyrium scoparium	2-4	Full Sun	0.250	
Virginia Wild Rye	Elymus virginicus	2 - 4	Full Sun	0.250	
Tall Dropseed	Sporobolus compositus	2 - 3	Full Sun	0.050	
Purple Top	Tridens flavus	3 - 5	Part Shade	0.058	
Indian Grass	Sorghastrum nutans	3 - 6	Full Sun	0.167	
Switchgrass	Panicum virgatum	3 - 7	Full Sun	0.183	
Fall Panicum	Panicum anceps	2 - 4	Part Shade	0.042	
Total	_	_	_	1.0	
Sources: Roundstone a Recommend	Native Seed, 2015; Glennon, 2015 led seeding application rate is 8 to 1 S = pounds per acre of pure live see	1 1	_	1.0	

Seed Mix P-CPDW01: Recommended Coastal Plain Physiographic Region Forb Seed Mix and Application Rates for Excessively to Moderately Well Drained Sites in North Carolina				
Common Name	Scientific Name	Color	Bloom Period	Seed Application Rate (lbs/acre/PLS) ^b
Lance Leaved Coreopsis	Coreopsis lanceolata	Yellow	Spring, Summer	0.266
Spotted Beebalm	Monarda punctata	Pink	Spring, Summer	0.124
Common Milkweed	Asclepias syriaca	Pink	Spring, Summer	0.107
Smooth Beardtongue	Penstemon digitalis	White	Spring	0.107
Bergamot	Monarda fistulosa	Lavender	Summer	0.124
Partridge Pea	Cassia fasciculata	Yellow	Summer	0.621
Spiked Blazing Star	Liatris spicata	Pink	Summer	0.222
Lupine	Lupinus perennis	Blue	Summer	0.497
Early Goldenrod	Solidago juncea	Yellow	Summer	0.160
Starry Silphium	Silphium asteriscus	Yellow	Summer, Fall	0.178
Iron Weed	Vernonia altissima	Purple	Summer, Fall	0.222
Sneezeweed	Helenium autumnale	Yellow	Summer, Fall	0.124
Hairy Mountain Mint	Pycnanthemum pilosum	White	Summer, Fall	0.089
Total	_	_	_	2.84

TABLE 2.3.7-3

Common Name	Scientific Name	Height (Inches)	Sun Exposure	Seed Mix Rate (lbs/acre/PLS)
Switchgrass	Panicum virgatum	3 - 7	Full Sun	0.233
Red Top Panicum	Panicum rigidulum	2 - 4	Full Sun	0.017
Fowl Manna Grass	Glyceria striata	3 - 5	Part Shade	0.008
Virginia Wild Rye	Elymus virginicus	2 - 4	Full Sun	0.217
Canada Wild Rye	Elymus canadensis	2 - 5	Part Shade	0.167
Deer Tongue Grass	Panicum clandestinum	2 - 4	Full Sun	0.058
Big Bluestem	Andropogon gerardii	4 - 10	Full Sun	0.167
Frank's Sedge	Carex frankii	1 - 2	Part Shade	0.042
Fox Sedge	Carex vulpinoidea	2 - 3	Part Shade	0.025
Fall Panicum	Panicum anceps	2 - 4	Part Shade	0.067
Fotal	_	_	_	1.0
	- Native Seed, 2015; Glennon, 2015			

Seed Mix P-CPDW02: Recommended Coastal Plain Physiographic Region Forb Seed Mix and Application Rates for Somewhat Poorly to Very Poorly Drained Sites in North Carolina				
Common Name	Scientific Name	Color	Bloom Period	Seed Application Rate (lbs/acre/PLS) ^a
Smooth Beardtongue	Penstemon digitalis	White	Spring	0.169
Butterfly Milkweed	Asclepias tuberosa	Orange	Spring, Summer	0.056
Ohio Spiderwort	Tradescantia ohiensis	Blue	Spring, Summer	0.084
Blackeyed Susan	Rudbeckia hirta	Yellow	Spring, Summer	0.180
Spiked Blazing Star	Liatris spicata	Pink	Summer	0.264
Hoary Mountain Mint	Pycnanthemum incanum	White	Summer	0.034
Early Goldenrod	Solidago juncea	Yellow	Summer	0.113
Bergamot	Monarda fistulosa	Lavender	Summer	0.169
Showy Tickseed	Bidens aristosa	Yellow	Summer, Fall	0.366
Starry Silphium	Silphium asteriscus	Yellow	Summer, Fall	0.113
Narrow-Leaved Sunflower	Helianthus angustifolius	Yellow	Summer, Fall	0.113
Joe-Pye Weed	Eupatorium fistulosum	Pink	Summer, Fall	0.141
Total	_	_	_	1.80

Recommended Non-native Temporary Cover Crop Species and Non-native Grass Cover

Use of non-native temporary cover species (P-NNTC) on all plantings where erosion potential is high or where the site must be vegetated within 30 days is recommended. Furthermore, use the non-native grass mixes (P-NNGC) with the forb mixes where slope is steep for native species to germinate and where erosion potential is high.

		TABLE 2.3.7-5			
Seed Mix P-NNTC: Recommended Non-native Temporary Cover Crop Species					
Common Name	Scientific Name	Height (Inches)	Sun Exposure	Seeding Application Rate (lbs/acre/PLS) ^a	
For Summer Use in Nati	ve Mixes				
Brown Top Millet	Panicum ramosum	3 - 3.5	Full sun	5.0	
For Spring and Fall Use	in Native Mixes				
Spring Oats	Avena sativa	2 - 2.5	Full sun	30.0	
For Fall and Winter Use	e in Native Mixes				
Annual Rye Grass	Lolium multiflorum	2-2.5	Part shade	6.0	
Source: Roundstone N	- Native Seed, 2015				
^a lbs/acre/PLS	= pounds per acre of pure live se	ed			

Common NameScientific NameHeight (Inches)Sun ExposureSeed Mix Rate (Ibs/acre/PLS)FescueFestuca arundinacea2 - 3Part Shade0.300TimothyPhleum pratense2 - 4Part Shade0.100Orchard GrassDactylis glomerata2 - 3Part Shade0.100Red TopAgrostis alba2 - 3Full Sun0.020Ladino CloverTrifolium repens1 - 1.5Part Shade0.040Annual Rye GrassLolium multiflorum2 - 2.5Part Shade0.170Creeping Red FescueFestuca rubra1 - 2Full Sun0.020Kentucky BluegrassPoa pratensis1 - 2Full Sun0.020Total———1.0Source:Roundstone Native Seed, 2015		Seed Mix P-NNGC	: Recommended Non-nativ	ve Grass Cover Mix ^a	
TimothyPhleum pratense2 - 4Part Shade0.100Orchard GrassDactylis glomerata2 - 3Part Shade0.100Red TopAgrostis alba2 - 3Full Sun0.020Ladino CloverTrifolium repens1 - 1.5Part Shade0.040Annual Rye GrassLolium multiflorum2 - 2.5Part Shade0.170Creeping Red FescueFestuca rubra1 - 2Full Sun0.250Kentucky BluegrassPoa pratensis1-2Full Sun0.020Total———1.0	Common Name	Scientific Name	Height (Inches)	Sun Exposure	Seed Mix Rate (lbs/acre/PLS) ^b
Orchard GrassDactylis glomerata2 - 3Part Shade0.100Red TopAgrostis alba2 - 3Full Sun0.020Ladino CloverTrifolium repens1 - 1.5Part Shade0.040Annual Rye GrassLolium multiflorum2 - 2.5Part Shade0.170Creeping Red FescueFestuca rubra1 - 2Full Sun0.250Kentucky BluegrassPoa pratensis1-2Full Sun0.020Total———1.0	Fescue	Festuca arundinacea	2 - 3	Part Shade	0.300
Red TopAgrostis alba2 - 3Full Sun0.020Ladino CloverTrifolium repens1 - 1.5Part Shade0.040Annual Rye GrassLolium multiflorum2 - 2.5Part Shade0.170Creeping Red FescueFestuca rubra1 - 2Full Sun0.250Kentucky BluegrassPoa pratensis1-2Full Sun0.020Total———1.0	Timothy	Phleum pratense	2 - 4	Part Shade	0.100
Ladino CloverTrifolium repens1 - 1.5Part Shade0.040Annual Rye GrassLolium multiflorum2 - 2.5Part Shade0.170Creeping Red FescueFestuca rubra1 - 2Full Sun0.250Kentucky BluegrassPoa pratensis1-2Full Sun0.020Total———1.0	Orchard Grass	Dactylis glomerata	2 - 3	Part Shade	0.100
Annual Rye GrassLolium multiflorum2 - 2.5Part Shade0.170Creeping Red FescueFestuca rubra1 - 2Full Sun0.250Kentucky BluegrassPoa pratensis1-2Full Sun0.020Total———1.0	Red Top	Agrostis alba	2 - 3	Full Sun	0.020
Creeping Red FescueFestuca rubra1 - 2Full Sun0.250Kentucky BluegrassPoa pratensis1-2Full Sun0.020Total1.0	Ladino Clover	Trifolium repens	1 - 1.5	Part Shade	0.040
Kentucky Bluegrass Poa pratensis 1-2 Full Sun 0.020 Total — — — 1.0	Annual Rye Grass	Lolium multiflorum	2 - 2.5	Part Shade	0.170
Total 1.0	Creeping Red Fescue	Festuca rubra	1 - 2	Full Sun	0.250
	Kentucky Bluegrass	Poa pratensis	1-2	Full Sun	0.020
Source: Roundstone Native Seed, 2015	Total	—	—	—	1.0
	Source: Roundstone Na	ative Seed, 2015			
	b lbs/acre/PLS =	pounds per acre of pure live se	ed		

3.0 SUPPLY HEADER PROJECT

3.1 WEST VIRGINIA

3.1.1 Wetzel and Tyler Counties

The following recommended seed mixtures, rates, and amendments are primarily for Tyler County but also include a portion of Wetzel County, West Virginia. The recommendation is from correspondence with Dustin Adkins (NRCS District Conservationist). The recommendation is for the area starting at Mile 23 (estimated portion in Tyler County) through Mockingbird Hill (Wetzel County). No pollinator species specific to the County were recommended by the Conservationist.

Recommended Seed Mixtures, Application Rates, Planting Dates, and Amendments

	Seed Mix WVWE01: Recommended Cool Season	Seed Mixture
Seed Mixture	Common Species Name	Seed Rate (lbs/acre/PLS) ^a
1	Orchard Grass	8
	Ladino Clover	2
2	White Clover	2
	Orchardgrass	5
	Kentucky Bluegrass	5
3	Red Clover	4
	Alsike Clover	2
	Orchardgrass	4

TABLE 3.1.1-2			
Recomm	nended Seeding Dates for Permanent Cover		
Planting Dates Suitability			
March 1 to April 15	Best seeding periods.		
August 1 to October 1			
December 1 to March 1	Good seeding period. Dormant seeding.		
April 15 to August 1	HIGH RISK – moisture stress likely.		
October 1 to December 1	HIGH RISK – freeze damage to young seedlings.		
Source: WVDEP, 2012			

	TABLE 3.1.1	-3
	Recommended Lime and Fertilizer Appli	cation for Permanent Seeding
		Fertilizer
pH of Soil	Lime (tons/ acre)	(10-20-20 or equivalent) (lbs/acre)
> 6.0	2	500
5.0 to 6.0	3	
< 5.0	4	

Recommended Lime and Fertilizer Application

Lime should be applied to all permanent seedlings. Once pH is known, use the information in the above Table to determine the amount (tons) of lime to use onsite. For the best results, apply the lime and fertilizer at the time of the seedbed preparation. The recommended lime and fertilizer application for temporary seeding in the absence of a soil test is provided in the below table.

TABLE 3.1.1-4						
Recor	nmended Lime and F	ertilizer Application fo	or Temporary Seeding (Ab	sent of a Soil Test)		
Nitrogen (N)Phosphorus (P2O5)Potassium (K2O)RecommendationsSpecies(lbs/acre)(lbs/acre)(lbs/acre)(per acre)						
Cool Season Grass	40	80	80	400 lbs 10-20-20		
Cool Season Grass & Legume	30	60	60	300 lbs 10-20-20		
Temporary Cover	40	40	40	200 lbs 19-19-19		

3.1.2 State Lands

Lewis Wetzel Wildlife Management Area – Wetzel County

The following seed mixtures, application rates, and soil amendments recommendations are for the Lewis Wetzel WMA in Wetzel County, West Virginia. The recommendations are based on correspondence and discussions with the West Virginia Department of Natural Resources (Steve Rauch, District Wildlife Biologist), which recommended the use of the seed mixtures and soil amendments discussed in the West Virginia Enhancing Wildlife Habitat on Oil and Gas Infrastructure booklet (West Virginia Department of Natural Resources, 2015).

Recommended Seed Mixtures and Application Rates

The following planting recommendations are intended to enhance early successional stage habitat found along access roads and pipelines.

	TABLE 3.1.2-1				
Seed Mix W	VLWWMA01: Recommended Grass Seed Mixes	and Application Rates			
Common Species Name	Scientific Name	Seeding Application Rate (lbs/acre/PLS) ^a			
Perennial, Cool Season Seed Mix ^b					
Ladino White Clover ^c	Trifolium repens	4			
Mammoth Red Clover ^c	Trifolium pratense	5			
Forage Clover	Cichorium intybus	2			
Winter Wheat ^d	Triticum aestivum	50			
Perennial, Cool Season, Slopes Seed Mix	ζ ^e				
Ladino White Clover ^c	Trifolium repens	8			
Red Clover ^c	Trifolium pratense	5			
Birdsfoot Trefoil ^c	Lotus corniculatus	8			
Orchardgrass	Dactylis glomerata	15			
Winter Wheat ^d	Triticum aestivum	50			
Source: WVDRN, 2015					
^a lbs/acre/PLS = pounds per acr	re of pure live seed				
^b Ideal for use in areas where the	Ideal for use in areas where the landscape is generally flat and where the objective is to have vegetative cover for pollinator species and wildlife habitat for turkey/grouse broods, and forage for deer				
	treated with the appropriate inoculant before seeding	ng.			
	1 through October 15 or substitute annual rye. Sprind retain the other species as listed.	ng planting: substitute oats at the same rate between			
e Ideal for sloped areas, as gras	ses are typically added to cool season mixes to prov	vide habitat and erosion control measures.			

Recommended Lime and Fertilizer Application

Application of soil amendments should be based on soil test recommendations. In the absence of a soil test, fertilizer and lime should be applied at the rates shown in Table 3.1.2-2.

	TABLE 3.1.2-2			
Recommended Lime and Fertilizer Application				
Туре	Application Rate			
Lime	3 tons/acre			
Fertilizer - 10-20-20	600 lbs/acre			
Source: WVDRN, 2015				

3.1.3 **Doddridge and Harrison Counties**

The following recommended seed mixtures, planting dates, and amendments are for Doddridge and Harrison counties. These recommendations are based on the collection of correspondences with federal and state agencies, including Greg Stone (NRCS Acting State Resource Conservationist), Jeff Griffith (NRCS District Conservationist). No pollinator species specific to the County were recommended by the Conservationists.

	Seed Mix WVDH01: Recomm	ended Cool Season Seed Mixtures	
Seed Mixture	Common Species Name ^a	Seed Application Rate (lbs/acre/PLS) ^b	Suitable Land Use
1	Orchardgrass	10	Pasture or Hay
	Ladino Clover	2	
	Red Clover	3	
	Redtop	3	
2	Kentucky Bluegrass	20	Pasture
	Ladino Clover	2	
	Red Clover	3	
	Redtop	3	Pasture or Hay
3	Orchardgrass	20	
	Redtop	5	
	Birdsfoot Trefoil	10	

Recommended Seed Mixtures and Application Rates

Recommended Seeding Dates for Permanent Cover and Amendments

TABLE 3.1.3-2				
Recommended Seeding Dates for Permanent Cover				
Planting Dates	Suitability			
March 1 to April 15	Best seeding periods.			
August 1 to October 1				
December 1 to March 1	Good seeding period. Dormant seeding.			
April 15 to August 1	HIGH RISK – moisture stress likely.			
October 1 to December 1	HIGH RISK – freeze damage to young seedlings.			

	TABLE 3.1.3-3		
Recommended Lime and Fertilizer Application			
Туре	Application Rate		
Lime	3 tons/acre		
Fertilizer - 10-20-20	400 lbs/acre		

Planting Recommendations

- Certified seed is preferred.
- All legumes should be planted with proper inoculants prior to seeding.
- Soil fertility and pH level will be amended to satisfy the needs of the plant species planned.
- For unprepared seedbeds or seeding outside the optimum timeframes:
 - Add 50 percent more seed to the specified rate, particularly during the periods of April 15 August 1, and October 1 March 1.
 - Double the seeding rate and consider planning an annual small grain like wheat (2 bushels [120 pounds] per acre) to act as a nurse crop.

3.1.4 Recommended Native Grasses and Pollinators Seed Mixtures, Application Rates, and Non-Native Cover Crop by Physiographical Region

Use the same recommended pollinator seed mixtures, non-native temporary cover, and non-native grass cover as indicted in Section 1.1.3 for the ACP in West Virginia.

3.2 PENNSYLVANIA

3.2.1 Westmoreland County

Seed mixtures, rates, and amendments were selected based on appropriate site conditions and recommendations from Christopher Droste (Conservation District) and adapted from the Pennsylvania Department of Environmental Protection Erosion and Sediment Pollution Control Program Manual. No pollinator species specific to the County were recommended by the Conservationist.

	TABLE 3.2.1-1		
Seed Mix P	AWE01: Recommended Cool Season Seed Mi	ixture	
	Seeding Applicat	ion Rate (lbs/acre/PLS) ^b	
Common Species Name	Most Sites	Adverse Sites	
Birdsfoot trefoil ^a , plus	6	10	
Tall fescue	30	35	

Recommended Seed Mixtures and Application Rates

Recommended Soil Amendments

	Soil Am	endment Application Rate Equivaler	nts ^a	
Soil Amendment	Per Acre	Per 1,000 Square feet (lbs)	Per 1,000 square Yard (lbs)	Notes
Agricultural lime	7.5 tons	300	3100	Or as per soil test; may not be required in agricultural fields
20-20-20 fertilizer	1,000 lbs	25	210	Or as per soil test; may not be required in agricultural fields

		TABLE 3	.2.1-3	
		Recommended Mulc	h Type and Rates	
Mulch Type	Per Acre (tons)	Per 1000 Square Feet (lbs)	Per 1000 Square Yard (lbs)	Notes
Straw	3	140	1240	Either wheat or oat straw, free of weeds, not chopped or finely broken
Hay	3	140	1240	Timothy, mixed clover and timothy or other native forage grasses
Wood Chips	4-6	185-275	1650-2500	May prevent germination of grasses and legumes
Hydromulch	1	47	415	See limitations above

4.0 **REFERENCES**

- Glennon, Robert. 2015. Personal communication with Herbert Pirela of Environmental Resources Management, Inc. Private Lands Biologist.
- Jones, J., Glennon, B., Lawrence, C., Faulkner, D., and C. Gordon. 2014. USDA-NRCS Virginia Plant Establishment Guide. Revised 2014.
- Natural Resource Conservation Service. 2011. National Conservation Practice Standard Critical Area Planting, Code 342.
- Natural Resource Conservation Service. 2014. Conservation Practice Standard Mulching, Code 484. Technical Guide Section IV: 484-VA-1.
- Roundstone Native Seed. 2015. Jeremy Hamlington, personal communication with Herbert Pirela of Environmental Resources Management, Inc. Horticulturist.
- West Virginia Department of Environmental Protection. 2012. West Virginia Erosion and Sediment Control Field Manual. Available online at: <u>http://www.dep.wv.gov/oil-and-gas/Documents/Erosion%20Manual%2004.pdf</u>. Accessed October 2015.
- West Virginia Department of Natural Resources. 2015. Enhancing Wildlife Habitat on Oil and Gas Infrastructure. Available online at: <u>http://www.wvdnr.gov/Publications/OilGasAnd</u> <u>Wildlife.pdf</u>

Attachment A Summary of Seed Mixes by County for the Atlantic Coast Pipeline and Supply Header Project

				ATTACHMENT A		
Summary of Seed Mixtures by County for the Atlantic Coast Pipeline and Supply Header Project						
Approximate Milepost Range	County and State	Suggested Cool Season Seed Mix Number ^a	Suggested Warm Season Seed Mix Number ^a	Suggested Pollinator Seed Mix Number ^a	Federal, State/Commonwealth, or local Agency/ Subject Matter Expert Contact Information	
Atlantic Coast I	Pipeline					
Spread 1 (AP-1)						
0.0–29.1	Harrison, WV	WVHLRU01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	District Conservationist - Jeff Griffith (304) 624-9232 ext. 11; jeff.griffith@wv.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.	
	Lewis, WV	WVHLRU01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	District Conservationist - Jeff Griffith (304) 624-9232 ext. 110; jeff.griffith@wv.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.	
	Upshur, WV	WVHLRU01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	Acting State Conservationist - Greg Stone (304) 284-7579; greg.stone@wv.usda.gov. Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.	
Spread 2 (AP-1)						
29.1–50.6	Upshur, WV	WVHLRU01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	Acting State Conservationist - Greg Stone (304) 284-7579; greg.stone@wv.usda.gov,Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.	
	Randolph, WV	WVHLRU01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	District (1) Wildlife Biologist - Steve Rauch (304) 825-6787; Steven.E.Rauch@wv.gov.	
Spread 2 A (AP-	1)					
50.6-65.3	Randolph, WV	WVHLRU01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	District (1) Wildlife Biologist - Steve Rauch (304) 825-6787; Steven.E.Rauch@wv.gov	
Spread 3 (AP-1)						
65.3-79.2	Randolph, WV	WVHLRU01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	District (1) Wildlife Biologist - Steve Rauch (304) 825-6787; Steven.E.Rauch@wv.gov	
	Pocahontas, WV	WVPO01	WVPO01; P-MUDW01 or MUMP02; P-NNTC or P-NNGC	P-MUDW01 or MUMP02; P-NNTC or P-NNGC	District Conservationist - Iden Gunther (304) 255-9225; idun.guenther@wv.usda.gov. Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.	
Spread 3A (AP-1 79.2-91.3	1)					
	Pocahontas, WV	WVPO01	WVPO01; P-MUDW01 or MUMP02; P-NNTC or P-NNGC	P-MUDW01 or MUMP02; P-NNTC or P-NNGC	District Conservationist - Iden Gunther (304) 255-9225; idun.guenther@wv.usda.gov. Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.	

				ATTACHMENT A						
Summary of Seed Mixtures by County for the Atlantic Coast Pipeline and Supply Header Project										
Approximate Milepost Range	County and State	Suggested Cool Season Seed Mix Number ^a	Suggested Warm Season Seed Mix Number ^a	Suggested Pollinator Seed Mix Number ^a	Federal, State/Commonwealth, or local Agency/ Subject Matter Expert Contact Information					
	Highland, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	District Conservationist - Charles Ivins (540) 248-6218 ext. 122; charles.ivins@va.usda.gov, Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov.					
Spread 4 (AP-1)										
91.3–125.9	Highland, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	District Conservationist - Charles Ivins (540) 248-6218 ext. 122; charles.ivins@va.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov.					
	Bath, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	District Conservationist – Charles Simmons; charles.simmons@va.usda.gov, Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov.					
	Augusta, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	District Conservationist - Charles Ivins (540) 248-6218 ext. 122; charles.ivins@va.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov					
Spread 5 (AP-1)										
125.9–183.3	Augusta, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	District Conservationist - Charles Ivins (540) 248-6218 ext. 122; charles.ivins@va.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov					
	Nelson, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	State Biologist - Jeffray Jones (804) 287-1691; Jeffray.Jones@va.usda.gov. Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					
Spread 6 (AP-1)										
183.3–239.6	Nelson, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	State Biologist - Jeffray Jones (804) 287-1691; Jeffray.Jones@va.usda.gov. Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					
	Nelson, VA; James River WWA	VJRWMA01; VJRWMA02; or VJRWMA03	VJRWMA01; VJRWMA02; or VJRWMA03		Environmental Services Biologists – Amy Ewing (804) 367-2211; Amy.Ewing@dgif.virginia.gov					
	Buckingham, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	District Conservationist - David Harris (434) 983-4757 x 101; david.harris@va.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov					
	Cumberland. VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	District Conservationist - David Harris (434) 983-4757 x 101; david.harris@va.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov					
	Prince Edward, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	District Conservationist - J.B. Daniel (434) 392-4171; j.b.daniel@va.usda.gov. Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					
	Nottoway, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					

				ATTACHMENT A						
Summary of Seed Mixtures by County for the Atlantic Coast Pipeline and Supply Header Project										
Approximate Milepost Range	County and State	Suggested Cool Season Seed Mix Number ^a	Suggested Warm Season Seed Mix Number ^a	Suggested Pollinator Seed Mix Number ^a	Federal, State/Commonwealth, or local Agency/ Subject Matter Expert Contact Information					
Spread 7 (AP-1)										
239.6–300.1	Nottoway, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					
	Dinwiddie, VA	VACSDGS01	VACSDGS01	P-VACSDGS01 or P- VACSDGS02	Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					
	Brunswick, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					
	Greensville, VA	VACSDGS01	VACSDGS01	P-VACSDGS01 or P- VACSDGS02	Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					
	Northampton, NC	NCNO01	NCNO02	P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist - Paul Boone (252) 534-2591; paul.boone@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					
Spread 8 (AP-2)										
0.0–61.6	Northampton, NC	NCNO01	NCNO02	P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist - Paul Boone (252) 534-2591; paul.boone@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					
	Halifax, NC	NCHW01	P-CPDW01 or P- CPMP02	P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist -David Little (252) 237-2711; David.Little@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					
	Nash, NC	NCNJ01	P-CDW01 or P-CPMP02	P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist - Patrick Evans (252) 459-4116; patrick.evans@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					
Spread 9 (AP-2)										
61.6–61.6	Nash, NC	NCNJ01	P-CPDW01 or P- CPMP02	P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist - Patrick Evans (252) 459-4116; patrick.evans@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Roundstone Native Seed (270) 234-7160.					
	Wilson, NC	NCHW01	P-CPDW01 or P- CPMP02	P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist -David Little (252) 237-2711; David.Little@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					
	Johnston, NC	NCNJ01	P-CDW01 or P-CPMP02	P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist - Brian Loadholt (919) 934-7156; brian.loadholt@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					

				ATTACHMENT A						
Summary of Seed Mixtures by County for the Atlantic Coast Pipeline and Supply Header Project										
Approximate Milepost Range	County and State	Suggested Cool Season Seed Mix Number ^a	Suggested Warm Season Seed Mix Number ^a	Suggested Pollinator Seed Mix Number ^a	Federal, State/Commonwealth, or local Agency/ Subject Matter Expert Contact Information					
	Sampson, NC	NCSA01	NCSA02	P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist - Gavin Thompson (910) 592-7963; gavin.thompson@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					
Cumberland, NC		NCCU01 NCCU01		P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist - Renessa Hardy-Brown (910) 484-8479; renessa.brown@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					
Spread 10 (AP-2	2)									
61.5–183.0	Cumberland, NC	NCCU01	NCCU01	P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist - Renessa Hardy-Brown (910) 484-8479; renessa.brown@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					
	Robeson, NC P-CPDW01 or P- CPMP02		NCRO01	P-CPDW01, P- CPMP02, or P- NCRO01; P-NNTC or P-NNGC	District Conservationist - Jeremy Roston (910) 739-5478; jeremy.roston@usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					
Spread 11 (AP-3	3)									
0.0-83.0	Northampton, NC	NCNO01	NCNO02	P-CPDW01 or P- CPMP02; P-NNTC or P-NNGC	District Conservationist - Paul Boone (252) 534-2591; paul.boone@nc.usda.gov. Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.					
	Greensville, VA	VACSDGS01	VACSDGS01	P-VACSDGS01 or P- VACSDGS02	Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					
	Southampton, VA	VACSDGS01	VACSDGS01	P-VACSDGS01 or P- VACSDGS02	Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					
	Suffolk, VA	Suffolk, VA VACSDGS01		P-VACSDGS01 or P- VACSDGS02	Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					
Spread 12 (AP-4	4; AP-5)									
0.0–0.4; 0.0- 1.1	Brunswick, VA	VABCHNP01	VABCHNP02	P-VABCHNP01 or P- VABCHNP02	District Conservationist - Davie Wade Harris (434) 848-2145 ext. 102; davie.harris@va.usda.gov					
	Greensville, VA	VACSDGS01	VACSDGS01	P-VACSDGS01 or P- VACSDGS02	Private Lands Biologist - Bob Glennon (757) 357-7004, ext. 126; Robert.Glennon@va.usda.gov					

	Summary o											
	Summary	Summary of Seed Mixtures by County for the Atlantic Coast Pipeline and Supply Header Project										
County and State	Suggested Cool Season Seed Mix Number ^a	Suggested Warm Season Seed Mix Number ^a	Suggested Pollinator Seed Mix Number ^a	Federal, State/Commonwealth, or local Agency/ Subject Matter Expert Contact Information								
roject												
5)												
Wetzel, WV	WVWE01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	District Conservationist - Dustin Adkins (304) 758-2173; dustin.adkins@wv.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.								
Wetzel, WV; Lewis Wetzel WMA	WVLWWMA01			District Wildlife Biologist - Steve Rauch (304)825-6787; steven.e.rauch@wv.gov								
Doddridge, WV	WVDH01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	Acting State Conservationist - Greg Stone (304) 284-7579; greg.stone@wv.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.								
Tyler, WV	WVWE01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	District Conservationist - Dustin Adkins (304) 758-2173; dustin.adkins@wv.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.								
Harrison, WV	WVDH01	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	P-MUDW01 or P- MUMP02; P-NNTC or P-NNGC	Acting State Conservationist - Greg Stone (304) 284-7579; greg.stone@wv.usda.gov. Private Lands Biologist - Bob Glennon (757) 357- 7004, ext. 126; Robert.Glennon@va.usda.gov. Roundstone Native Seed (270) 234-7160.								
5)												
Westmoreland, PA	PAWE01	None Recommended	None Recommended	Westmoreland Conservation District, Christopher Droste, Senior Erosion Control Specialist (724) 837-5271; chris@wcdpa.com.								
1	 roject Wetzel, WV Wetzel, WV; Lewis Wetzel WMA Doddridge, WV Tyler, WV Harrison, WV Westmoreland, 	County and State Number a roject ************************************	County and State Number a Seed Mix Number a roject ************************************	County and State Number a Seed Mix Number a Seed Mix Number a roject Permitian and the seed Mix Number a Seed Mix Number a Seed Mix Number a S) Wetzel, WV WVWE01 P-MUDW01 or P-MUDW01 or P-MUDW02; P-NNTC or P-NNGC P-MUDW02; P-NNTC or P-NNGC Wetzel, WV; WVLWWMA01 WVLWWMA01 P-MUDW01 or P-MUDW01 or P-MUDW01 or P-MUDW01 or P-MUMP02; P-NNTC or P-NNGC P-MUDW01 or P-MUMP02; P-NNTC or P-NNGC Tyler, WV WVWE01 P-MUDW01 or P-MUMP02; P-NNTC or P-NNGC P-MUDW01 or P-MUMP02; P-NNTC or P-NNGC Harrison, WV WVDH01 P-MUDW01 or P-MUMP02; P-NNTC or P-NNGC P-MUDW01 or P-MUMP02; P-NNTC or P-NNGC S) Westmoreland, PAWE01 None Recommended None Recommended								

ATLANTIC COAST PIPELINE, LLC ATLANTIC COAST PIPELINE

and

DOMINION TRANSMISSION, INC. SUPPLY HEADER PROJECT

Restoration and Rehabilitation Plan

Appendix C Recommended Seed Mixes by Milepost (to be provided prior to construction)

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	0.4	snrh005	Jacks Swamp	Intermittent		6	6	Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	1.1	snrh007	UNT to Jacks Swamp	Intermittent		4	4	Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	1.9	snrh006	Jacks Swamp	Perennial		29	15	Open Cut	C, NSW		NA
North Carolina	AP-2	Perm AR	8.3	snrh010	UNT to Trouble Field Creek	Intermittent			5	Perm AR	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	8.5	snrg002	UNT to Trouble Field Creek	Perennial		5	5	Dam and Pump	с		NA
North Carolina	AP-2	Perm AR	8.5	snrh009	UNI to Trouble Field Creek UNI to	Perennial			10	Perm AR	С		NA
North Carolina	AP-2	Perm AR	8.5	snrh009	Trouble Field Creek	Perennial			10	Perm AR	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	8.8	snrg003	UNT to Trouble Field Creek	Intermittent		5	4	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	9.6	snrh004	UNT to Roanoke RIver	Perennial		4	3	Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr	9.8	shlh001	Roanoke River	Perennial		355	360	HDD	AFSA, C	Potential for ESA- listed species	February 1 to June 30/August 15 through November 15
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	11.8	ohlc001	Mush Island Gut	Pond		Pond		Pond	NA		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	11.9	shlc003	UNT to Mush Island Gut	Intermittent		5	5	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	11.9	shlc004i	UNT to Mush Island Gut	Intermittent		9	6	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	12.4	shlc002	UNT to Mush Island Gut	Intermittent		5	4	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	12.4	shlc001	UNT to Mush Island Gut	Intermittent		7	5	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	13.3	shlo003	Mush Island Gut	Intermittent		5	4	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	13.6	shlf001	UNT to Roanoke River	Perennial		9	9	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	13.9	shlf002	UNT to Roanoke River	Intermittent		8	7	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	14.0	shlf003	UNT to Roanoke River	Ephemeral		3	3	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Surv Corr,	14.1	shlh003	UNT to Roanoke River UNT to	Perennial		13	10	Dam and Pump	С		NA
North Carolina	AP-2	Temp ROW Ferm ROW, Surv Corr,	14.1	shlh004	Roanoke River UNT to the	Perennial			6	Not Crossed by Centerline	с		NA
North Carolina	AP-2	Temp ROW	14.4	shlp002	Roanoke River	Perennial		3	3	Dam and Pump	с		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	14.7	nhd_nc_n _004	UNT to the Roanoke River	Intermittent		6	5	1) Flume 2) Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	15.3	nhd_nc_n 003	Little Quankey Creek	Perennial		21	10	1) Dam and Pump 2) Flume		Potential for ESA- listed species	NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	15.4	shlf004	UNT to Little Quankey Creek	Perennial			12	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	15.7	isdha007	Little Quankey Creek	Perennial				Open Cut	С	Potential for ESA- petitioned species	May 15 to July 31
North	AP-2	ROW, Surv Corr, Temp ROW	16.9	nhd_nc_a	Quankey Creek			10	10	Dam and Pump	с	Potential for ESA-	NA
North		Perm ROW, Surv Corr, Temp			UNT to Quankey	Perennial		10		Not Crossed by		listed species	
Carolina	AP-2	ROW Perm ROW, Surv Corr, Temp	17.4	shlg005	Creek UNT to Marsh	Intermittent			3	Centerline Not Crossed by	С		NA
Carolina North Carolina	AP-2 AP-2	ROW Perm ROW	18.1 18.2	shlg007 shlg008	Swamp UNT to Marsh Swamp	Intermittent Ephemeral			6	Centerline Not Crossed by Centerline	C C		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	18.2	shlg008	UNT to Marsh Swamp	Ephemeral			2	Not Crossed by Centerline	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	18.2	shlg007	UNT to Marsh Swamp	Intermittent			6	Not Crossed by Centerline	с		NA
	, , , , Z	ROW, Temp CPY,	10.2	ongoor	UNT to	mont				Contonino			
North Carolina	AP-2	Temp ROW	18.5	shlg009	Marsh Swamp	Perennial		12	9	Dam and Pump	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North		Temp			UN1 to Marsh					Contractor Yard -			
Carolina	AP-2	CPY Perm	18.6	shlb050	Swamp	Perennial			12	Temporary Impact	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	20.1	shlh008	Marsh Swamp	Perennial		15	15	Open Cut	C, Sw, NSW	Potential for ESA- listed species	NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	20.5	shlh007	UNT to Marsh Swamp	Intermittent		6	5	Dam and Pump	с		NA
North	AP-2	ROW, Surv Corr, Temp ROW	21.0	shih019	UNT to Marsh Swamp	Intermittent		4	4	Dam and Pump	с		NA
North	AP-2	Perm ROW, Surv Corr, Temp ROW	22.8	shih016	UNT to Beaverda m Swamp	Intermittent		5	5	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	23.1	shlh017	Beaverda m Swamp	Perennial		63	45	Open Cut	C, Sw, NSW	Potential for ESA- listed species	NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW Perm	23.3	shlh018	UNT to Beaverda m Swamp	Intermittent		4	3	1) Flume 2) Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	23.6	shla002	UNT to Beaverda m Swamp	Intermittent		4	4	1) Flume 2) Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	24.0	shlg012	UNT to Beaverda m Swamp	Perennial		5	5	1) Flume 2) Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	25.0	shlb100	UNT to Beaverda m Creek	Intermittent		3	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	26.6	shlh009	UNT to Burnt Coat Swamp	Perennial		9	8	Open Cut	C, Sw, NSW	Potential for ESA- listed species	NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	26.9	shlh010	UNT to Burnt Coat Swamp	Intermittent		2	2	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	27.4	shlh011	Jacket Swamp	Perennial		28	25	Open Cut	С	Potential for ESA- listed species	NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	27.7	shlh012	UNT to Jacket Swamp	Intermittent		5	5	1) Flume 2) Open Cut	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	29.8	shla001	Breeches Swamp	Perennial		16	15	1) Flume 2) Open Cut	C, Sw, NSW		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	30.6	shlh015	UNT to Rocky Swamp	Intermittent			6	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	31.0	shlh020	UNT to Rocky Swamp	Intermittent		4	4	Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr	31.2	shlo001	UNT to Rocky Swamp	Intermittent			4	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	31.2	shlo002	UNT to Rocky Swamp	Intermittent		3	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	32.0	isdha001	Rocky Swamp	Perennial				Open Cut	WS-IV, NSW	Potential for ESA- listed species	March 15 to May 31/August 15 to September 30
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	32.7	shlh013	UNT to Rocky Swamp	Intermittent		7	6	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	32.8	shlh014	UNT to Rocky Swamp	Intermittent		9	6	Dam and Pump	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North					UN1 to Fishing								
Carolina	AP-2	Perm AR	33.5	shlh022	Creek UNI to	Perennial			4	Perm AR	С		NA
North Carolina	AP-2	Perm AR	33.5	shlh022	Fishing Creek	Perennial			4	Perm AR	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr	33.7	shlg011	UN1 to Fishing Creek	Perennial		8	8	HDD	с		NA
North Carolina	AP-2	Perm ROW, Surv Corr	33.9	snag001	Fishing Creek	Perennial		104	40	HDD	AFSA, WSIV, NSW	Potential for ESA- listed species	February 15 to June 30
North Carolina	AP-2	Perm ROW, Surv Corr	34.8	snag003	UN1 to Fishing Creek	Intermittent			3	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	34.8	snag002	UNT to Fishing Creek	Intermittent		5	5	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	35.1	snag004	UNT to Fishing Creek	Intermittent		4	4	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	37.0	isdna012	Black Swamp	Perennial				Open Cut	WS-IV, NSW		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	39.7	snab100	UNT to Swift Creek	Intermittent		2	2	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	39.9	snah001	UNT to Swift Creek	Intermittent		5	4	Dam and Pump	с		NA
North Carolina	AP-2	Temp ATWS	40.3	snah028	UNT to Swift Creek	Perennial			8	Not Crossed by Centerline	С		NA
North		ROW, Surv Corr, Temp ATWS, Temp	40.0		UNT to Swift	Descrit		0	<u></u>	Derrord D			
Carolina North Carolina	AP-2	ROW Perm ROW, Surv Corr	40.3	snah002 snah003	Creek Swift Creek	Perennial Perennial		6	6	Dam and Pump HDD	C AFSA, C, NSW	Potential for ESA- listed species	NA February 15 to June 30

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	40.9	snah006	UNT to Flat Rock Branch	Perennial		9	8	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	41.6	snah005	UNT to Flat Rock Branch	Perennial		7	6	Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	41.7	snah004	UNT to Flat Rock Branch	Perennial		4	4	Dam and Pump	с		NA
North	AP-2	ROW, Surv Corr, Temp ROW	42.0	snah029	UNT to Flat Rock Branch	Intermittent		4	4	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	42.1	snah025	UNT to Flat Rock Branch	Perennial		68	10	1) Flume 2) Open Cut	C, NSW		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	42.2	snah026	UNT to Flat Rock Branch	Perennial		9	4	1) Flume 2) Open Cut	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	42.8	snab103	UNT to Flat Rock Branch	Intermittent		3	3	Dam and Pump	с		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	43.7	N/A	Flat Rock Branch	Perennial				1) Flume 2) Open Cut	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr Perm	44.0	snab104	UNI to Flat Rock Branch UNI to	Intermittent			3	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr Perm ROW,	44.4	snab105	Flat Rock Branch	Perennial			4	Not Crossed by Centerline	С		NA
North Carolina	AP-2	Surv Corr, Temp ROW	44.4	snac001	Flat Rock Branch	Perennial		6	8	Open Cut	C, NSW	Potential for ESA- listed species	NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
		ROW, Surv Corr,											
North Carolina	AP-2	Temp ROW	44.8	snag012	Flat Rock Branch	Perennial		7	6	Open Cut	C, NSW	Potential for ESA- listed species	NA
North		ROW, Surv Corr, Temp			UNT to Pig Basket								
Carolina	AP-2	ROW Surv Corr,	47.2	snah008	Creek	Perennial		5	4	Dam and Pump	С		NA
North Carolina	AP-2	Temp ROW	47.6	onah005	Unnamed Pond	Pond		Pond		Pond	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	47.6	snah009	Pig Basket Creek	Perennial		30	25	1) Dam and Pump 2) Flume 3) Open Cut	C, NSW	Potential for ESA- listed species	NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	47.6	snah010	UNT to Pig Basket Creek	Intermittent		9	9	1) Dam and Pump 2) Open Cut	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	48.7	nhd_nc_k _005	UNT to Stony Creek	Intermittent		6	5	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	48.7	nhd_nc_k _006	Stony Creek	Perennial		10	10	Open Cut	С	Potential for ESA- listed species	NA
North Carolina	AP-2	Surv Corr, Temp ROW	49.2	snah016	UNT to Stony Creek	Perennial			4	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	49.5	snah017	UNT to Stony Creek	Perennial		8	6	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	50.2	snag008	UNT to Stony Creek	Perennial		19	8	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	50.2	snag007	UNT to Stony Creek	Perennial		6	6	Dam and Pump	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	50.2	snag008	UNT to Stony Creek	Perennial			8	Not Crossed by Centerline	с		NA
North Carolina	AP-2 AP-2	Surv Corr, Temp ROW	50.2	snag005	UNI to Stony Creek	Perennial			4	Not Crossed by Centerline	c		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	50.8	snag005	UNT to Stony Creek	Perennial		4	4	1) Flume 2) Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	51.5	snag009	UNT to Stony Creek	Perennial		17	8	1) Dam and Pump 2) Flume	WSIV, NSW		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	51.6	snag010	UNT to Stony Creek	Perennial		6	5	Dam and Pump	С		NA
North Carolina	AP-2	Perm AR	52.0	onag002	UNT to Sapony Creek	Pond		Pond		Pond	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	53.3	snah021	UNT to Sapony Creek	Perennial		24	10	Open Cut	С	Potential for ESA- listed species	NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	54.0	ncwq011	Little Sapony Creek	Perennial				Open Cut	WS-IV, NSW	Potential for ESA- listed species	NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	54.9	snah020	UNT to Sapony Creek	Perennial		8	8	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	56.1	snah023	UNT to Sapony Creek	Perennial		13	8	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	56.3	snah024	Sapony Creek	Perennial		30	20	Open Cut	WSIV, NSW	Potential for ESA- listed species	NA

State	Project Segment		Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North		ROW, Surv Corr, Temp			UNT to Sapony					1) Flume 2) Open			
Carolina	AP-2	ROW Perm ROW, Surv Corr,	56.6	snah022	Creek UNT to	Perennial		23	10	Cut	С		NA
North Carolina	AP-2	Temp ROW Perm	57.0	snah019	Sapony Creek	Intermittent		10	7	1) Flume 2) Open Cut	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	58.8	snap004	UNT to Tar River	Perennial		3	3	Dam and Pump	с		NA
	711-2	Perm ROW, Surv Corr,	50.0	3114004		1 Gronnia		5	5	Dam and Fump			170
North Carolina	AP-2	Temp ROW	59.1	snap003	UNT to Tar River	Intermittent		8	3	Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr Perm	59.1	snap002	UNT to Tar River	Intermittent		3	3	Dam and Pump	C ASFA,		NA
North Carolina	AP-2	ROW, Surv Corr	59.4	snao011	Tar River	Perennial		159	130	HDD	NSW	Potential for ESA- listed species	February 15 to June 30
North Carolina	AP-2	Perm GB, Perm ROW, Surv Corr, Temp GB, Temp ROW	60.4	snao009	UNT to Tar River	Ephemeral		3	2	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	61.9	snao008	UNT to Toisnot Swamp	Ephemeral		3	3	Dam and Pump	с		NA
North Carolina	AP-2	Perm ROW, Surv Corr	62.7	snao007	UNI to Toisnot Swamp	Intermittent		2	2	Dam and Pump	С		NA
North		ROW, Surv Corr, Temp	<u> </u>		Toisnot	Derid		Derid		0	WSIII,	Potential for ESA-	
Carolina North Carolina	AP-2 AP-2	ROW Perm ROW, Surv Corr	62.8 62.9	onao003 onao002	Swamp Toisnot Swamp	Pond Pond		Pond Pond	40 40	Open Cut Open Cut	NSW WSIII, NSW	listed species Potential for ESA- listed species	NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	63.0	snao006	UNT to Toisnot Swamp	Ephemeral		4	2	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	63.3	snao005	UNT to Beaverda m Creek	Ephemeral		2	2	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	63.3	snao004	UNT to Beaverda m Creek	Intermittent		5	5	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	63.5	snao003	UNT to Beaverda m Creek	Ephemeral		6	6	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	64.5	snao002	UNT to Bloomers Swamp	Ephemeral		2	2	Dam and Pump	С		NA
North Carolina	AP-2	Surv Corr, Temp ROW	64.6	onao001	Unnamed Pond	Pond		Pond	30	Pond	NA		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW Perm	65.1	snah030	UNT to Bloomery Swamp	Perennial		8	8	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	65.2	snah031	UNT to Bloomery Swamp	Perennial		6	8	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	65.6	snao001	UNT to Juniper Creek	Ephemeral		2	2	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	66.1	swio015	UNT to Juniper Creek	Perennial		9	8	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	66.3	swio016	UNT to Juniper Creek	Intermittent		8	4	Dam and Pump	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
		Perm ROW,											
North		Surv Corr, Temp		nhd_nc_k	Millstone							Potential for ESA-	
Carolina	AP-2	ROŴ	66.9	_007	Creek	Perennial		5	10	Open Cut	С	listed species	NA
		Perm ROW,											
North		Surv Corr,			UNT to					Net Greened by			
North Carolina	AP-2	Temp ROW	66.9	nhd_nc_k _008	Millstone Creek	Intermittent			5	Not Crossed by Centerline	с		NA
		ROW,											
		Surv Corr,			UNT to								
North Carolina	AP-2	Temp ROW	67.7	swio001	Millstone Creek	Intermittent		8	2	1) Dam and Pump 2) Open Cut	с		NA
		ROW,	-							, -1			
		Surv Corr,			UNT to								
North Carolina	AP-2	Temp ROW	67.8	swio002	Millstone Creek	Perennial		2	1.5	1) Dam and Pump 2) Open Cut	с		NA
Carolina	AF-2	Ferm	07.0	5010002	Cleek	Felelilla		2	1.5	2) Open Cut	C		NA
		ROW, Surv Corr,			UNT to								
North		Temp			Marsh								
Carolina	AP-2	ROW Perm	68.3	swio003	Swamp	Intermittent		5	5	Dam and Pump	С		NA
		ROW, Surv Corr,			UNT to								
North		Temp			Marsh								
Carolina	AP-2	ROW	69.1	swio004	Swamp	Perennial		22	6	Dam and Pump	С		NA
		ROW,											
North		Surv Corr, Temp			UNT to Marsh					1) Dam and Pump			
Carolina	AP-2	ROŴ	69.3	swio005	Swamp	Perennial		9	5	2) Open Cut	С		NA
		ROW,											
North		Surv Corr, Temp			UNT to Marsh								
Carolina	AP-2	ROW	69.5	swio006	Swamp	Intermittent		5	5	Dam and Pump	с		NA
		ROW,											
		Surv Corr,											
North Carolina	AP-2	Temp ROW	69.7	swio007	Marsh Swamp	Perennial		9	8	Open Cut	C, NSW	Potential for ESA- listed species	NA
Saronna	/ 1 2	Perm	00.7	51110007	Champ	i oroninai		5			0,1000	10100 00000	11/3
		ROW, Surv Corr,			UNT to								
North		Temp	70.4	autic 0.00	Marsh	Denemial		,	4	Dom or d Diver	6		NA
Carolina	AP-2	ROW	70.4	swio009	Swamp	Perennial		4	4	Dam and Pump	С		NA
		ROW, Surv Corr,			UNT to								
North		Temp			Marsh								
Carolina	AP-2	ROW	70.5	swio008	Swamp	Perennial		9	5	Dam and Pump	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW Perm	70.9	swio013	UNT to Marsh Swamp	Perennial		19	4	Open Cut	С	Potential for ESA- listed species	NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	71.0	swio011	UNT to Marsh Swamp	Perennial		16	20	1) Dam and Pump 2) Flume 3) Open Cut	с	Potential for ESA- listed species	NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	71.0	swio012	UNT to Marsh Swamp	Intermittent		10	10	1) Dam and Pump 2) Open Cut	С	Potential for ESA- listed species	NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	72.2	swip001	UNT to Contentne a Creek	Ephemeral		6	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	72.3	swic001	UNT to Contentne a Creek	Intermittent		5	5	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	72.5	dwic001	UNT to Contentne a Creek	Canal/Ditch		11	5	Dam and Pump	Unclassifi ed		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	73.1	swib100	UNT to Contentne a Creek	Perennial		4	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	73.3	swib100	UNT to Contentne a Creek	Perennial		6	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ATWS, Temp ROW	73.4	swib100	UNT to Contentne a Creek	Perennial		5	3	Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr	73.6	swic002	Contentne a Creek	Perennial		69	40	HDD	AFSA, WSV, NSW	Potential for ESA- listed species	February 15 to June 30
North Carolina	AP-2	Surv Corr, Temp ATWS	73.8	swic003	UN1 to Contentne a Creek	Ephemeral			4	Not Crossed by Centerline	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North		Surv Corr, Temp			UNI to Contentne					Not Crossed by			
Carolina	AP-2	ROW	73.9	swip008	a Creek	Intermittent			3	Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	74.1	swip006	UNT to Contentne a Creek	Intermittent		7	2	Dam and Pump	с		NA
		-			UNI to						-		
North Carolina	AP-2	Perm AR	74.4	swio017	Buckhorn Branch	Ephemeral			4	Perm AR	С		NA
North Carolina	AP-2	Perm AR	74.4	swio017	UNT to Buckhorn Branch	Ephemeral			4	Perm AR	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	74.6	swip002	UNT to Buckhorn Branch	Ephemeral		3	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	74.9	swip003	UNT to Buckhorn Branch	Ephemeral		5	4	1) Dam and Pump 2) Open Cut	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	75.8	swip017	UNT to Buckhorn Branch	Perennial		5	4.5	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	75.8	swip009	UNT to Buckhorn Branch	Intermittent			3	Not Crossed by Centerline	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	78.9	sjob101	UNT to Little Buffalo Creek	Ephemeral		2	2	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	78.9	sjob102	UNT to Little Buffalo Creek	Ephemeral		2	2	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	79.2	sjob103	UNT to Little Buffalo Creek	Perennial		9	5	1) Dam and Pump 2) Flume	с		NA
North Carolina	AP-2	Perm GB, Temp GB	79.3	sjob103	UNT to Little Buffalo Creek	Perennial			5	Not Crossed by Centerline	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	79.3	sjob103	UNT to Little Buffalo Creek	Perennial		17	5	1) Dam and Pump 2) Flume	С		NA
North	AP-2	Perm ROW, Surv Corr, Temp			Little Buffalo							Potential for ESA-	
Carolina North		ROW Perm ROW, Surv Corr, Temp	79.5	sjob104	Creek UNT to Little	Perennial		31	20	Open Cut 1) Dam and Pump	C, NSW	listed species	NA
Carolina North	AP-2	ROW Perm ROW, Surv Corr, Temp	81.0	sjop013	River UNT to Little	Intermittent		2	1.5	2) Open Cut	С		NA
Carolina North Carolina	AP-2 AP-2	ROW Perm ROW, Surv Corr	82.0 82.5	sjop003 sjoe001	River UNI to Little River	Intermittent Intermittent		5	5	Dam and Pump HDD	C C		NA
North Carolina	AP-2	Perm ROW, Surv Corr Perm	82.5	sjoe002	Little River UNI to	Perennial		57	50	HDD	AFSA, WSV, NSW	Potential for ESA- listed species	February 15 to June 30/March 15 to May 31/August 15 to September 30
North Carolina	AP-2	ROW, Surv Corr Perm ROW, Surv Corr,	82.6	sjoe004	Little River UNT to	Intermittent		6	6	HDD	С		NA
North Carolina	AP-2	Temp ROW Perm ROW,	83.4	sjoe005	Buffalo Creek	Perennial		6	6	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	Surv Corr, Temp ROW	83.5	sjoe006	UNT to Buffalo Creek	Intermittent		3	3	1) Dam and Pump 2) Flume	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	84.6	sjop001	Big Branch	Intermittent		15	6	1) Dam and Pump 2) Open Cut	C, NSW		NA
North Carolina	AP-2	Perm GB	84.6	sjoo014	UT to Big Branch UNT to	Ephemeral			4	Not Crossed by Centerline	С		NA
North Carolina	AP-2	Perm GB, Temp GB Perm ROW,	84.6	sjop002	Big Branch	Intermittent			5	Not Crossed by Centerline	C, NSW		NA
North Carolina	AP-2	Surv Corr, Temp ROW	85.9	sjoo003	UNT to Little Creek	Perennial		8	8	1) Dam and Pump 2) Open Cut	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	86.5	sjoo004	Little Creek	Perennial		5	4	Open Cut	C, NSW	Potential for ESA- listed species	March 15 to May 31/August 15 to Sept
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	87.3	sjoo005	UNT to Moccasin Creek	Intermittent		3	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	88.9	sjop005	UNT to Moccasin Creek	Intermittent		4	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	89.7	sjop007	Moccasin Creek	Perennial		17	12	1) Dam and Pump 2) Flume	C, NSW		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	91.2	sjop008	UNT to Bawdy Swamp	Intermittent		2	2	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	92.1	sjop010	Bawdy Swamp	Perennial		8	8	Conventional Bore (with US70 Business crossing)	C, NSW		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	93.6	sjop015	UNT to Mill Branch	Intermittent		14	4	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	95.1	sjob011	UNT to Neuse River	Intermittent		8	6	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Surv Corr,	95.3	sjop018	UNT to Polecat Branch UNT to	Intermittent			4	Not Crossed by Centerline	С		NA
North Carolina	AP-2	Temp ROW Ferm ROW,	95.8	sjob010	Polecat Branch	Intermittent			4	Not Crossed by Centerline	С		NA
North Carolina	AP-2	Surv Corr, Temp ROW	96.3	sjob009	UNT to Polecat Branch	Perennial		4	4	Dam and Pump	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	Temp CPY	96.4	sjob109	Polecat Branch	Intermittent			4	Contractor Yard - Temporary Impact	с		NA
North		Perm Perm ROW, Surv Corr, Temp		0,00.100	Polecat							Potential for ESA-	
Carolina	AP-2	ROW	97.5	sjoo008	Branch	Perennial	13	9	8	Open Cut	с	listed species	NA
North		Perm ROW, Surv Corr, Temp			UNT to Polecat					1) Dam and Pump			
Carolina	AP-2	ROW Surv Corr,	97.7	sjoo009	Branch UN1 to	Intermittent	10	10	10	2) Flume	С		NA
North Carolina	AP-2	Temp ROW	98.2	nhd_nc_n _008	Neuse River	Intermittent			5	Not Crossed by Centerline	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	98.2	sjoo010	UNT to Neuse River	Perennial		19	26	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	98.5	sjob105	Neuse River	Perennial		138		Cofferdam	AFSA, WSV, NSW	Potential for ESA- listed species	February 1 to June 30/May 15 to July 31
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	98.6	nhd_nc_k _009	UNT to Neuse River	Intermittent		7	5	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	98.7	nhd_nc_k _010	Unnamed Pond	Pond		Pond		Pond	С		NA
North Carolina	AP-2	Perm AR	98.8	sjob007	UN1 to Neuse River	Intermittent	5		5	Perm AR	с		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	98.8	nhd_nc_k _011	UNT to Neuse River	Intermittent		40	5	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	98.8	nhd_nc_k _011	UNT to Neuse River	Intermittent		5	5	Dam and Pump	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	98.9	nhd_nc_k _011	UNT to Neuse River	Intermittent			5	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	99.7	djod001	UNT to Neuse River	Canal/Ditch		5		Flume	Unclassifi ed		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	101.3	isdjo001	Hannah Creek	Perennial				Open Cut	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	102.4	sjob006	UNT to Hannah Creek	Intermittent		1	1	Dam and Pump	с	Potential for ESA- listed species	NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	102.8	sjob005	UNT to Hannah Creek	Intermittent		4	4	1) Dam and Pump 2) Open Cut	С	Potential for ESA- listed species	NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	102.8	sjob004	UNT to Hannah Creek	Perennial		4	4	1) Dam and Pump 2) Open Cut	С	Potential for ESA- listed species	NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Surv Corr,	103.9	sjob003	UNT to Hannah Creek	Perennial		4	4	1) Dam and Pump 2) Open Cut	С	Potential for ESA- listed species	NA
North Carolina	AP-2	Temp ROW	104.4	ojoa004	Unnamed Pond	Pond		Pond		Pond	NA		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	105.1	isdjo002	Whiteoak Branch	Perennial				Open Cut	C, NSW		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	106.7	isdjo004	Stone Creek	Perennial				Open Cut	C, NSW		NA
North Carolina	AP-2	ROW, Surv Corr. Temp ROW	107.6	isdjo005	UNT to Johnson Swamp	Perennial				Open Cut	C, NSW		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North		Surv Corr, Temp			UNP to Johnson								
Carolina	AP-2	ROW Perm	108.1	ojob100	Swamp	Pond		Pond		Pond	NA		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	110.5	sjop016	UNT to John K Swamp	Ephemeral		3	3	Open Cut	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	113.1	sjoo007	Mill Branch	Intermittent		8	7	Dam and Pump	C, NSW		NA
North				nhd_nc_m	UNT to								
Carolina	AP-2	Perm AR	114.1	_001	Mill Creek	Intermittent	6		5	Perm AR	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	114.2	sjoq001	UNT to Jumping Run	Perennial		11	5	1) Flume 2) Dam and Pump	С		NA
North	AP-2	ROW, ROW, Surv Corr, Temp ROW	115.4	ssao003	UNT to Juniper Run	Ephemeral		5	3	Dam and Pump	с		NA
North Carolina	AP-2	ROW, ROW, Surv Corr, Temp ROW	116.9	ssa0003	Little Juniper Run	Perennial		8	8	1) Dam and Pump 2) Open Cut			NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	117.2	ssap003	Juniper Run	Perennial		17	12	1) Dam and Pump 2) Flume 3) Open Cut			NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW Perm	118.9	ssao007	Beaverda m Swamp	Perennial		36	9	1) Dam and Pump 2) Open Cut	C, Sw		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	119.7	ssaa001	Beaverda m Swamp	Perennial		Wetland- Waterbody Complex	25	1) Dam and Pump 2) Flume 3) Open Cut			NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	121.9	ssao004	UNT to Starlins Swamp	Intermittent		8	2	1) Dam and Pump 2) Open Cut	С		NA

	Project	Facilities			Feature_	Waterbody	Access Road	Centerline	Survey/Desktop	Construction	State Reg	Federal	State/Commonwealth or Federal
State	Segment	Crossed	Milepost	Unique ID	Name	Regime	Crossing (feet)	Crossing (feet)	Estimated OHWM Width (feet)	Method	Class	Classifications	Time of Year Restrictions (work limited between dates listed)
		ROW,											
North		Surv Corr, Temp			Unnamed								
Carolina	AP-2	ROŴ	121.9	osao002	Pond	Pond		Pond		Pond	NA		NA
		ROW,											
North		Surv Corr, Temp			Starlins					1) Dam and Pump			
Carolina	AP-2	ROW	122.2	ssao006	Swamp	Perennial		25	15	2) Open Cut	C, Sw		NA
		ROW,											
North		Surv Corr, Temp			Starlins			Wetland- Waterbody		1) Dam and Pump			
Carolina	AP-2	ROW	122.3	ssao005	Swamp UN1 to	Perennial		Complex	20	2) Open Cut	C, Sw		NA
North	15.0	D 10	100 5	004	Mingo						0		
Carolina	AP-2	Perm AR	122.5	ssag001	Swamp UNT to	Intermittent			4	Perm AR	С		NA
North Carolina	AP-2	Perm AR	122.5	ssag001	Mingo Swamp	Intermittent			4	Perm AR	с		NA
North Carolina	AP-2	Perm AR	122.5	osag001	Unnamed Pond	Pond		Pond		Pond	NA		NA
North					Unnamed								
Carolina	AP-2	Perm AR	122.5	osag001	Pond UN1 to	Pond		Pond		Pond	NA		NA
North Carolina	AP-2	Perm AR	123.0	scme001	Mingo Swamp	Perennial	18		12	Perm AR	с		NA
	AF-2	PellilAK	123.0	Scheout	UNIto	Felelilla	10		12	Pelli AK	C		NA
North Carolina	AP-2	Perm AR	123.1	scmo014	Mingo Swamp	Perennial			10	Perm AR	С		NA
North					UNI to Mingo								
Carolina	AP-2	Perm AR	123.1	scmo014	Swamp	Perennial			10	Perm AR	С		NA
North					UNT to Mingo								
Carolina	AP-2	Perm AR	123.1	scmo014	Swamp UN1 to	Perennial			10	Perm AR	С		NA
North	15.0	D 10	100.1		Mingo	.			10		0		
Carolina	AP-2	Perm AR	123.1	scmo014	Swamp UN1 to	Perennial			10	Perm AR	С		NA
North Carolina	AP-2	Perm AR	123.1	scmo016	Mingo Swamp	Perennial	8		7	Perm AR	с		NA
Carolina	/ 2	ROW,	120.1	23110010	Stramp	. oronnidi	Ŭ				Ŭ		147.1
		Surv Corr,			UNT to								
North Carolina	AP-2	Temp ROW	125.2	scmc004	Black River	Intermittent		6	5	 Dam and Pump Open Cut 	С		NA
		ROW,								_, _,			
		Surv Corr,			UNT to								
North Carolina	AP-2	Temp ROW	125.8	scmp007e	South River	Ephemeral		8	8	1) Dam and Pump 2) Flume	с		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	Surv Corr, Temp ROW	125.8	scmp007i	UN1 to South River	Intermittent			10	Not Crossed by Centerline	С		NA
North Carolina	AP-2	Perm AR	126.7	scmp008	UNT to Cape Fear River	Ephemeral	4		4	Perm AR	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	126.7	scmp008	UNT to Cape Fear River	Ephemeral		4	4	1) Flume 2) Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	126.8	scmp009	UNT to Cape Fear River	Perennial	8	19	8	1) Dam and Pump 2) Open Cut	с		NA
North	AP-2	ROW, Surv Corr, Temp ROW	127.3		UNT to Cape Fear River	Perennial		25	6	1) Dam and Pump 2) Open Cut			NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	129.0	scmp022	UNT to Cape Fear River	Intermittent		3	3	Dam and Pump	С		NA
North Carolina	AP-2	Perm AR	129.2	scmo041	UNT to Cape Fear River	Perennial	4		4	Perm AR	с		NA
North Carolina	AP-2	Perm AR	129.2	scmo041	Cape Fear RIver	Perennial			4	Perm AR	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	129.4	scmc001	UNT to Cape Fear River	Perennial		8	7	Dam and Pump	С		NA
North Carolina	AP-2	Surv Corr, Temp ROW Perm	129.6	scmc002	UNT to Cape Fear River	Perennial			30	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	129.7	scmc003	UNT to Cape Fear River	Ephemeral		4	3	1) Flume 2) Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	130.1	scmc005	UNT to Cape Fear River	Intermittent		3	3	1) Dam and Pump 2) Open Cut	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	Perm AR	131.1	scmp021	UNT to Cape Fear River	Intermittent	4		4	Perm AR	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	131.5	scmp005	UNT to Cape Fear River	Perennial		6	5	Dam and Pump	с		NA
North Carolina	AP-2	Surv Corr, Temp ROW Perm	131.6	scmb102	UNT to Cape Fear River	Ephemeral			3	Not Crossed by Centerline	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	131.7	scmp003	UNT to Cape Fear River	Intermittent		2	2.5	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	131.7	scmp004	UNT to Cape Fear River	Intermittent		5	4	Dam and Pump	с		NA
North Carolina	AP-2	Surv Corr, Temp ROW	131.8		UNT to Cape Fear River	Intermittent			3	Not Crossed by Centerline	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	132.7	scmp001	UNT to Cape Fear River	Intermittent		9	9	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	132.8	scmo037	UNT to Cape Fear River	Perennial		24	4	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	Surv Corr, Temp ROW	132.8		UNT to Cape Fear River	Perennial			4	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	132.8	scmo037	UNT to Cape Fear River	Perennial		4	4	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	Perm MLR, Surv Corr Perm	132.9	scmp037	UNT to Cape Fear River	Perennial			15	M&R Workspace	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	133.2	scmp037	UNT to Cape Fear River	Perennial		39	15	1) Dam and Pump 2) Flume	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	133.4	scmp039	UNT to Cape Fear River	Intermittent		3	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	133.8	scmp042	UNT to Cape Fear River	Intermittent		11	6	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	133.9		UNT to Cape			3	3		С		
North		ROW, Surv Corr, Temp		scmp041	Fear River UNT to Cape	Ephemeral				Dam and Pump 1) Dam and Pump			NA
Carolina	AP-2	ROW Perm ROW, Surv Corr, Temp	134.2	scmp040	Fear River UNT to Gum Log	Perennial		13	10	2) Flume	С		NA
Carolina	AP-2	ROW Perm ROW, Surv Corr,	135.0	scmp100	Canal	Intermittent		7	6	Dam and Pump	С		NA
North Carolina	AP-2	Temp ROW	135.8	nhd_nc_f_ 013	Unnamed Pond	Pond		Pond		Pond	NA		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	136.9	scmq001	UNT to Bakers Swamp	Perennial		7	6	1) Flume 2) Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	137.0	scmq003	UNT to Bakers Swamp	Perennial		7	4	1) Flume 2) Dam and Pump	С		NA
North		Perm ROW, Surv Corr, Temp			UNT to Bakers					1) Flume 2) Dam			
Carolina	AP-2	ROW Perm ROW,	137.1	scmq004	Swamp	Perennial		8	8	and Pump	С		NA
North Carolina North	AP-2	Surv Corr, Temp ROW Temp	137.1	scmp058	UNT to Big Creek Unnamed	Intermittent		8	8	Dam and Pump	с		NA
Carolina	AP-2	CPY	141.6	ocme020	Pond	Pond		Pond		Pond	NA		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	141.8	scmr005	UNT to Buck Creek	Intermittent		5	4	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	142.0	scmr006	UNT to Buck Creek	Ephemeral		4	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	142.7	scmo031	UNT to Sandy Creek	Ephemeral		5	4	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	142.8	scmo032	UNT to Sandy Creek	Ephemeral		2	2	Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr	142.8	scmo033	UN1 to Sandy Creek	Ephemeral			3	Not Crossed by Centerline	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	142.9	scmo034	UNT to Sandy Creek	Ephemeral		3	4	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	143.2	scmo035	Sandy Creek	Perennial		11	6	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	143.3	scmf002	UNT to Sandy Creek	Intermittent		7	4	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	143.4	scmf003	UNT to Sandy Creek	Intermittent		6	5	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	144.7	scmf001	UNT to Cedar Creek	Intermittent			3	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	146.2	scmp043	UNT to Cedar Creek	Perennial		6	6	Dam and Pump	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
		ROW,											
N I a set la		Surv Corr,			UNT to								
North Carolina	AP-2	Temp ROW	146.5	scmo039	Cedar Creek	Intermittent		2	2	Dam and Pump	С		NA
		ROW,											
		Surv Corr,			UNT to								
North Carolina	AP-2	Temp ROW	146.6	scmo038	Cedar Creek	Perennial		6	4	1) Dam and Pump 2) Flume	с		NA
Carolina	AF-2	Perm	140.0	50110030	Cleek	Felelillidi		0	4	2) Fluttie	C		NA NA
		ROW, Surv Corr,			UNT to								
North		Temp			Cedar								
Carolina	AP-2	ROW Perm	146.7	scmo020	Creek	Intermittent		4	3	Dam and Pump	С		NA
		ROW,											
North		Surv Corr, Temp			UNT to Cedar								
Carolina	AP-2	ROW	147.0	scmo021	Creek	Ephemeral		2	2	Dam and Pump	С		NA
		ROW, Surv Corr,			UNT to								
North		Temp			Cedar								
Carolina	AP-2	ROW Perm	147.0	scmo021	Creek	Ephemeral		9	2	Dam and Pump	С		NA
		ROW, Surv Corr,			UNT to								
North		Temp			Cedar								
Carolina	AP-2	ROW	147.1	scmo022	Creek	Ephemeral		2	2	Dam and Pump	С		NA
		ROW,			UNT to								
North		Surv Corr, Temp			Big Alligator								
Carolina	AP-2	ROW	150.3	scmp051	Swamp	Ephemeral		4	4	Dam and Pump	С		NA
		Perm ROW,			UNT to								
		Surv Corr,			Big								
North Carolina	AP-2	Temp ROW	150.4	scmp054	Alligator Swamp	Ephemeral		3	2	Dam and Pump	С		NA
		ROW,			UNT to			-			-		
		Surv Corr,			Big								
North		Temp	450.4		Alligator	Devencial		22	45	1) Dam and Pump			NA
Carolina	AP-2	ROW	150.4	scmp052	Swamp UNI to	Perennial		22	15	2) Flume	С		NA
North		Surv Corr, Temp			Big Alligator					Not Crossed by			
Carolina	AP-2	ROW	150.4	scmp051	Swamp	Ephemeral			4	Centerline	С		NA
		ROW,											
		Surv Corr,			UNT to								
North		Temp ROW,		nhd_nc_n	Big Alligator					1) Flume 2) Dam			
Carolina	AP-2	Temp TS	150.8	_001	Swamp	Canal/Ditch		5	5	and Pump	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North		ROW, Surv Corr, Temp			UNT to Big Alligator								
Carolina	AP-2	ROW Perm ROW, Surv Corr,	151.1	scmp056	Swamp	Intermittent		10	10	Dam and Pump	С		NA
North Carolina	AP-2	Temp ROW Perm	151.6	scmo028	UNt to Hair Canal	Perennial		6	5	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	151.7	scmo029	Hair Canal	Perennial		31	15	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	Surv Corr, Temp ROW	152.8	scmr003	UNT to Cape Fear River	Intermittent			28	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	153.1	scmr002	UNT to Cape Fear River	Perennial		11	9	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	153.2	scmr001	UNT to Cape Fear River	Intermittent		4	4	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	153.5	scmp048	UNT to Cape Fear River	Ephemeral		3	2	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ATWS, Temp ROW	153.8	scmp045	UNT to Cape Fear River	Perennial		11	12	1) Dam and Pump 2) Flume	С		NA
North		ROW, Surv Corr, Temp ATWS, Temp			UNT to Cape					1) Dam and Pump			
Carolina North	AP-2	ROW Perm ROW,	154.0		Fear River UNT to Cape	Perennial		6	6	2) Flume	С		NA
Carolina North Carolina	AP-2 AP-2	Surv Corr Perm ROW, Surv Corr	154.1 154.2		Fear River Cape Fear River	Perennial Perennial		48 326	60	HDD HDD	C AFSA, WSIV	Potential for ESA- listed species	NA February 15 to June 30

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	Perm ROW, Surv Corr	154.3	scmo027	UNT to Cape Fear River	Intermittent		19	6	HDD	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	154.6	scmo024	UNT to Cape Fear River	Perennial		12	10	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	154.6	scmo025	UNT to Cape Fear River	Intermittent			3	Not Crossed by Centerline	С		NA
North Carolina	AP-2	Perm AR	154.6	scmo024	UNT to Cape Fear River	Perennial	10		10	Perm AR	с		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW Perm ROW,	154.7	scmo023	UNT to Cape Fear River	Intermittent		3	3	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	Surv Corr, Temp ROW	155.1	nhd_nc_f_ 042	UNT to Cape Fear River	Intermittent		21	5	1) Dam and Pump 2) Flume	с		NA
North Carolina	AP-2	Perm ROW, Surv Corr	155.2	scmo036	UNT to Cape Fear River	Perennial		5	2	1) Dam and Pump 2) Flume	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	156.4	scmp059	Longs Branch	Perennial		11	9	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	157.3	scmp049	UNT to Swans Creek	Perennial		4	3	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	158.3	scmg002	UNT to Kirks Mill Creek	Intermittent		4	4	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	158.3	scmg001	UNT to Kirks Mill Creek	Intermittent		9	9	Dam and Pump	С		NA
North Carolina	AP-2	Surv Corr, Temp ROW	158.9	scme002	Kirks Mill Creek	Intermittent			2	Not Crossed by Centerline	WSIV		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
N I - mth		ROW, Surv Corr,			UNT to Kirks Mill								
North Carolina	AP-2	Temp ROW Perm	159.1	scmh001	Creek	Intermittent		6	5	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr	160.4	sroo001	Gallberry Swamp	Perennial			15	Not Crossed by Centerline	C, Sw		NA
North Carolina	AP-2	Perm ROW	160.5	sroo001	Gallberry Swamp	Perennial			15	Not Crossed by Centerline	C, Sw		NA
North Carolina	AP-2	Surv Corr, Temp ROW	161.8	oroh003	UNI to Little Marsh	Pond		Pond	40	Pond	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	161.9	sroh011	Little Marsh Swamp	Intermittent		10	8	Dam and Pump	С		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp ROW	164.2	srog006	UNT Little Marsh Swamp	Intermittent		8	8	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	166.2	srof001	Mercer Branch	Intermittent		16	15	1) Dam and Pump 2) Flume	C, Sw		NA
North Carolina	AP-2	Surv Corr, Temp ROW	166.8	srof002	UNT to Black Branch	Ephemeral			5	Not Crossed by Centerline	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	167.0	srof003	Black Branch	Intermittent		8	8	1) Dam and Pump 2) Flume	C, Sw		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	170.2	srog005	UNT to Tenmile Swamp	Ephemeral		3	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	171.4	srog004	UNT to Little Tenmile Swamp	Intermittent		6	4	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	171.8	sroh015	UNT to Saddletre e Swamp	Intermittent		5	4	Dam and Pump	С		NA
North Carolina	AP-2	Perm AR	172.0	sroh013	UNI to Saddletre e Swamp	Intermittent			4	Perm AR	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North					UNI to Saddletre								
Carolina	AP-2	Perm AR	172.0	sroh013	e Swamp	Intermittent			4	Perm AR	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	172.0	srog003	UNT to Little Tenmile Swamp	Intermittent		7	4	Dam and Pump	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	172.4	srog002	UNT to Saddletre e Swamp	Intermittent		7	3	Dam and Pump	С		NA
North Carolina	AP-2	Perm GB, Temp GB	172.4	sroo002	UT to Saddletre e Swamp	Ephemeral			3	Not Crossed by Centerline	с		NA
North Carolina	AP-2	Perm ROW, Surv Corr, Temp GB, Temp ROW	172.4	srog001	UNT to Saddletre e Swamp	Intermittent		3	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	174.0	sroh010	Raft Swamp	Perennial		40	40	1) Dam and Pump 2) Flume 3) Open Cut			NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	177.0	nhd_nc_n _007	Swamp	Perennial		11	10	1) Flume 2) Dam and Pump	с		NA
North Carolina	AP-2	Perm AR	177.6	sroc002	UN1 to Richland Swamp	Ephemeral			3	Perm AR	C, Sw		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	178.5	srop001	Burnt Swamp	Perennial		43	25	1) Flume 2) Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	178.6	srop002	UNT to Burnt Swamp	Ephemeral		23	8	1) Flume 2) Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ATWS, Temp ROW, Temp TS	179.2	srop003	UNT to Burnt Swamp	Perennial		10	10	1) Flume 2) Dam and Pump	С		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	181.1	sroh008	Moss Neck Swamp	Perennial		21	20	1) Dam and Pump 2) Flume	C, Sw		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	181.3	sroh007	UNT to Moss Neck Swamp	Intermittent		2	2	Dam and Pump	с		NA
North Carolina	AP-2	Surv Corr, Temp ROW Perm	181.6	sroe001	UNT to Little Bear Swamp	Intermittent			4	Not Crossed by Centerline	с		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW Perm	181.6	sroh005	UNT to Bear Swamp	Perennial		8	7	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	181.7	sroh004	UNT to Bear Swamp	Intermittent		5	3	Dam and Pump	С		NA
North Carolina	AP-2	ROW, Surv Corr, Temp ROW	181.7	sroh003	UNT to Bear Swamp	Intermittent		3	3	Dam and Pump	С		NA
North		ROW, Surv Corr, Temp			UNT to Bear			5		Not Crossed by			
Carolina	AP-2	ROW Perm ROW, Surv Corr,	182.2	sroh002	Swamp UNT to	Intermittent			3	Centerline	С		NA
North Carolina North Carolina	AP-2 AP-3	Temp ROW	182.3 0.2	sroh001 snrh005	Bear Swamp Jacks Swamp	Perennial		5	5	Dam and Pump Temp AR	c c		NA
North		ROW, Surv Corr, Temp			Jacks	Intermittent			0				
Carolina North	AP-3	ROW Perm ROW, Surv Corr, Temp	0.6	N/A	Swamp UNT to Jack's	Perennial				Open Cut	C		NA
Carolina	AP-3	ROW	1.3	snrc002	Swamp	Ephemeral		14	3	Dam and Pump	C, NSW		NA

State	Project Segment	Facilities Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
North		ROW, Surv Corr, Temp			UNT to Jack's								
Carolina	AP-3	ROW Perm	1.5	snrc001	Swamp	Ephemeral		3	3	Dam and Pump	C, NSW		NA
North Carolina	AP-3	ROW, Surv Corr, Temp ROW	3.6	snrp002	UNT to Cypress Creek	Intermittent		3	3	Dam and Pump	C, NSW		NA
North		ROW, Surv Corr, Temp			UNT to Cypress								
Carolina	AP-3	ROW Perm ROW, Surv Corr,	4.2	snrp003	Creek UNT to	Intermittent		10	7	Dam and Pump	C, NSW		NA
North		Temp			Cypress					1) Dam and Pump			
Carolina	AP-3	ROW	5.9	snrp017	Creek	Perennial		8	7	2) Open Cut	C, NSW		NA
North		ROW, Surv Corr, Temp			UNT to Cypress					1) Flume 2) Dam and Pump 3)			
Carolina	AP-3	ROW	5.9	snrp016	Creek UNT to	Perennial		31	9	Open Cut	C, NSW		NA
North Carolina	AP-3	Perm AR	6.5	snrp015	Cypress Creek	Intermittent			4	Perm AR	C, NSW		NA
North Carolina	AP-3	ROW, Surv Corr, Temp ROW	7.0	snrp005	UNT to Cypress Creek	Perennial		7	3	Dam and Pump	C, NSW		NA
North		ROW, Surv Corr, Temp			Cypress								
Carolina	AP-3	ROW Perm ROW,	7.4	N/A	Creek	Perennial				Flume	C, NSW		NA
North		Surv Corr, Temp			UNT to Cypress								
Carolina	AP-3	ROW Surv Corr,	7.8	snrb101	Creek UNT to	Ephemeral		2	2	Dam and Pump	C, NSW		NA
North Carolina	AP-3	Temp ROW	10.0	snro004	Cypress Creek	Perennial			8	Not Crossed by Centerline	с		NA
N I - mt		ROW, Surv Corr,			0								
North Carolina	AP-3	Temp ROW	10.0	snro003	Cypress Creek	Perennial		33	30	1) Dam and Pump 2) Flume	С		NA
North Carolina	AP-3	Perm ROW, Surv Corr	10.2	snro002	UNT to Cypress Creek	Perennial		4	3	Dam and Pump	с		NA

State	Project Segment	Crossed	Milepost	Unique ID	Feature_ Name	Waterbody Regime	Access Road Crossing (feet)	Centerline Crossing (feet)	Survey/Desktop Estimated OHWM Width (feet)	Construction Method	State Reg Class	Federal Classifications	State/Commonwealth or Federal Time of Year Restrictions (work limited between dates listed)
		ROW,											
		Surv Corr,											
North		Temp			Cypress								
Carolina	AP-3	ROW	10.3	snro001	Creek	Perennial		3	3	Dam and Pump	С		NA
North					UNI to Meherin								
Carolina	AP-3	Perm AR	10.8	snrr004	River	Ephemeral			2.5	Perm AR	С		NA
					UNI to								
North Carolina	AP-3	Perm AR	11.2	snrr001	Meherin River	Intermittent	9		8	Perm AR	с		NA
Carolina	AP-3	Perm	11.2	SHITUUT	River	mermilieni	9		0	Feini AK	C		NA
		ROW,											
		Surv Corr,			UNT to								
North		Temp			Meherrin								
Carolina	AP-3	ROW	11.6	snrp012	River	Intermittent		4	4	Dam and Pump	С		NA